

US EPA RECORDS CENTER REGION 5



466732

# *2003 Annual Report*

## *East Hennepin Avenue Site*

*Prepared for  
General Mills, Inc.*

*February 2004*





RECEIVED

MAR 9 2004

MPCA, WMR Division  
RIP/IS Section

## *2003 Annual Report*

### *East Hennepin Avenue Site*

*Prepared for  
General Mills, Inc.*

*February 2004*



*4700 West 77th Street  
Minneapolis, MN 55435  
Phone: (952) 832-2600  
Fax: (952) 832-2601*



# 2003 Annual Report

## East Hennepin Avenue Site

### Table of Contents

|       |  |    |
|-------|--|----|
| 1.0   | Introduction .....   | 1  |
| 1.1   | Site Operation and Brief Geological Overview .....                     | 1  |
| 1.2   | Site History.....  | 2  |
| 1.3   | 2003 Operations .....  | 2  |
| 2.0   | Quality Assurance.....   | 4  |
| 3.0   | Groundwater Monitoring.....  | 6  |
| 3.1   | Water Level Monitoring.....  | 6  |
| 3.1.1 | Glacial Drift.....   | 6  |
| 3.1.2 | Carimona Member of Platteville Formation .....                         | 6  |
| 3.1.3 | Magnolia Member of Platteville Formation.....                          | 6  |
| 3.1.4 | St. Peter Sandstone .....  | 7  |
| 3.2   | Water Quality Monitoring .....   | 7  |
| 3.2.1 | Monitoring Wells in the Glacial Drift.....                             | 7  |
| 3.2.2 | Monitoring Wells in the Carimona Member of Platteville Formation ..... | 8  |
| 3.2.3 | Monitoring Wells in the Magnolia Member of Platteville Formation.....  | 8  |
| 3.2.4 | Monitoring Wells in the St. Peter Sandstone .....                      | 8  |
| 3.2.5 | Prairie du Chien/Jordan Monitoring Well.....                           | 8  |
| 3.2.6 | Offsite Groundwater Pump-out System .....                              | 8  |
| 3.2.7 | Onsite Glacial Aquifer Pump-out and Treatment Systems .....            | 9  |
| 3.2.8 | Onsite Magnolia Aquifer Pump-out System .....                          | 9  |
| 3.3   | Surplus Wells .....  | 9  |
| 4.0   | Remedial Action Operations.....  | 11 |
| 4.1   | Groundwater Pump-out Systems .....                                     | 11 |
| 4.1.1 | Onsite Glacial Drift System.....                                       | 11 |
| 4.1.2 | Downgradient Glacial Drift System.....                                 | 11 |
| 4.1.3 | Carimona System.....   | 12 |
| 4.1.4 | Magnolia System .....  | 12 |
| 4.2   | Maintenance and Downtime.....  | 12 |
| 4.3   | Groundwater Treatment System .....                                     | 13 |
| 5.0   | Discussion of Water Quality Results .....                              | 14 |
| 5.1   | Glacial Aquifer .....  | 14 |
| 5.1.1 | Site Groundwater Pump-out Systems .....                                | 14 |
| 5.1.2 | Downgradient Pump-out System .....                                     | 15 |
| 5.1.3 | Glacial Aquifer Monitoring Wells .....                                 | 16 |
| 5.1.4 | BTEX in the Glacial Aquifer.....                                       | 16 |
| 5.2   | Carimona Member of Platteville Formation .....                         | 16 |
| 5.3   | Magnolia Member of Platteville Formation.....                          | 17 |
| 5.3.1 | Magnolia Member Pumping Wells.....                                     | 17 |



## Table of Contents (continued)

|       |                                   |    |
|-------|-----------------------------------|----|
| 5.3.2 | Magnolia Monitoring Wells.....    | 18 |
| 5.3.3 | BTEX in the Magnolia Member ..... | 18 |
| 5.4   | St. Peter Sandstone.....          | 18 |
| 5.5   | Prairie du Chien/Jordan .....     | 19 |
| 6.0   | Conclusions .....                 | 20 |
| 7.0   | Recommendations for 2004 .....    | 22 |
|       | References .....                  | 23 |

## List of Tables

|          |  |
|----------|--|
| Table 1  | 2003 Groundwater Elevations, Glacial Drift Wells                           |
| Table 2  | 2003 Groundwater Elevations, Carimona Member Wells                         |
| Table 3  | 2003 Groundwater Elevations, Magnolia Member Wells                         |
| Table 4  | 2003 Groundwater Elevations, St. Peter Sandstone Wells                     |
| Table 5  | 2003 Water Quality Data, Glacial Drift Wells                               |
| Table 6  | 2003 Water Quality Data, Carimona Member Wells                             |
| Table 7  | 2003 Water Quality Data, Magnolia Member Wells                             |
| Table 8  | 2003 Water Quality Data, St. Peter Sandstone Wells                         |
| Table 9  | 2003 Water Quality Data, Prairie du Chien/Jordan Well                      |
| Table 10 | 2003 Water Quality Data, Downgradient Glacial Drift Pump-out System        |
| Table 11 | 2003 Water Quality Data, Site Glacial Drift Pump-out and Treatment Systems |
| Table 12 | 2003 Water Quality Data, Magnolia Pump-out System                          |
| Table 13 | 2003 Pumping Rates   |
| Table 14 | Recovery Test Comparison Summary   |
| Table 15 | Summary of 2003 Activities   |
| Table 16 | Proposed Wells to be Abandoned and Previously Abandoned Wells              |



## **Table of Contents (continued)**

### **List of Figures**

- Figure 1 East Hennepin Avenue Site - Regional Location Map
- Figure 2 Generalized Geologic Column
- Figure 3 East Hennepin Avenue Site Map
- Figure 4 Site Monitoring Well Locations
- Figure 5 Glacial Drift Aquifer Water Table Elevations, October 27, 2003
- Figure 6 Carimona Member, Potentiometric Surface Elevations, October 27, 2003
- Figure 7 Magnolia Member, Potentiometric Surface Elevations, October 27, 2003
- Figure 8 St. Peter Sandstone Monitoring Locations and Potentiometric Surface Elevations, October 27, 2003
- Figure 9 Glacial Drift, Groundwater Quality (TCE), October 27, 2003
- Figure 10 Glacial Drift Wells, TCE Concentrations, 1985–2003
- Figure 11 Carimona Member, Groundwater Quality (TCE), October 27, 2003
- Figure 12 Carimona Member Wells, TCE Concentrations, 1985–2003
- Figure 13 Magnolia Member, Groundwater Quality (TCE), October 27, 2003
- Figure 14 Magnolia Member Wells, TCE Concentrations, 1985–2003
- Figure 15 St. Peter Sandstone, Groundwater Quality (TCE), October 27, 2003
- Figure 16 St. Peter Sandstone Wells, TCE Concentrations, 1985–2003
- Figure 17 Trichloroethene in Glacial Aquifer Pump-out Systems, 1985–2003
- Figure 18 Magnolia Groundwater Pump-out System (MG1, MG2) Discharge TCE Concentrations, (1993–2003)
- Figure 19 Wells Proposed for Abandonment
- Figure 20 2003 Pumping Rates Over Time

### **List of Appendices**

- Appendix A East Hennepin Avenue Site, 2000–2005 Operations and Monitoring Plan
- Appendix B Field Sampling Report and Laboratory Data Reports
- Appendix C Quality Assurance/Quality Control Data
- Appendix D Historic Water Elevation, Water Quality Data, and Well Construction Information
- Appendix E Well Sealing Records on 2003



# 1.0 Introduction

---

This report summarizes the results from annual monitoring and remedial action operations conducted at the East Hennepin Avenue Site (Figure 1) during 2003. The activities completed in 2003 were generally consistent with those that have been conducted since 1985. The goals of the remedial action are to minimize the further migration of volatile organic compounds (VOCs), in particular, trichloroethylene (TCE), released from the former disposal area, and to improve the quality of the groundwater in the glacial drift and Platteville formation.

## 1.1 Site Operation and Brief Geological Overview

The current system consists of seven pump-out wells, a water treatment facility, and monitoring well networks in four aquifers. The pump-out wells are designed to control the movement of the plumes in the surficial glacial drift and in the underlying Carimona and Magnolia Members of the Platteville Formation. Four pump-out wells remove affected groundwater from the immediate vicinity of the site, which is treated by air stripping and discharged to the Minneapolis storm sewer system. Three pump-out wells remove less-affected groundwater downgradient of the site, which is discharged directly to the City storm sewer system and undergoes passive air stripping as the water flows to the Mississippi River. Annual and quarterly activities were completed in 2003 to monitor the effectiveness of the remediation systems.

Figure 2 shows a generalized geologic section of the site. There are about 50 feet of unconsolidated sediment underlying the site. As much as 10 feet of fill and peat are present near the surface. Underlying that is about 30 to 50 feet of sand alluvium, and 0 to 10 feet of clay till at the base. The uppermost bedrock is either the Decorah Shale (0 to 5 feet thick) or the Carimona member of the Platteville Limestone.

Groundwater generally flows southwest toward the Mississippi River. The water table occurs at about Elevation 830 to 840 feet MSL beneath the site, and the river is at about Elevation 725 feet MSL. Typically, there are downward gradients from the glacial drift aquifer to the Platteville Limestone, and from the Platteville Limestone to the underlying St. Peter Sandstone (the surface of the nearby Mississippi River occurs at about the middle of the St. Peter Sandstone). Because of this downward gradient, the groundwater in the Platteville Limestone beneath the site flows toward the northwest.



## **1.2 Site History**

From about 1930 until about 1977, General Mills operated a technical center and research laboratories at 2010 East Hennepin Avenue in Minneapolis, Minnesota. Food research was conducted at this property until 1947, when General Mills commenced chemical research in addition to the food research. Beginning in about 1947, laboratory solvents from the chemical research operations were reportedly disposed of in a soil absorption pit located in the southeast portion property. The pit consisted of three 55-gallon drums that were perforated, stacked one on top of the another, and buried with the bottom of the deepest drum about 10 to 12 feet below the ground surface. The pit was used until approximately 1962.

On August 31, 1977, Henkel Corporation purchased the property at 2010 East Hennepin Avenue from General Mills. The drums and pipe that made up the disposal site were reportedly excavated in 1981, and the bottom of the excavation was reportedly about 12 feet deep. The action of removing and replacing the soil likely caused volatilization of much of the VOCs that were present prior to the excavation, and homogenization of those that remained afterward. In addition, some offsite soil was used in backfilling.

Site characterization work began in 1981. On October 23, 1984, a Response Order by Consent between the Minnesota Pollution Control Agency (MPCA) and General Mills, Inc., was executed by the MPCA Board, and this Response Order is the basis for subsequent and on-going remedial activities. The site is listed on the National Priorities List (USEPA ID Number MND051441731), but no Record of Decision was ever issued. In 1985, operation of the remediation systems began.

In September 1994 and 1999, the MPCA issued Five-Year Reviews of the site. The 1999 review generally affirmed the 1984 Response Order, and led to a request for additional minor site investigation.

In 2001, General Mills completed an investigation of the shallow soils in the area of the former disposal site. The results of the study led to a recommendation of no further action. The MPCA approved the letter report (September 28, 2001 letter from Mark Rys to Larry Deeney) with a request for reporting of additional monitoring parameters (benzene, ethylbenzene, toluene and xylene).

## **1.3 2003 Operations**

The pump-out and treatment systems operated within acceptable limits in 2003. 2003 monitoring results indicate that the pump-out systems are effectively preventing further lateral migration of VOCs in the glacial drift and Platteville. No complete risk pathways exist at the Site. Water quality data from the glacial drift, Platteville, St. Peter, and Prairie du Chien/Jordan are consistent with historic results.



The 2003 monitoring and remediation were carried out in response to the requirements of:

- Part II of Exhibit A to the October 23, 1984, Response Order by Consent between General Mills, Inc., and the MPCA;
- the January 1985 groundwater pump-out system plan, East Hennepin Avenue Site;
- Minnesota Department of Natural Resources (MDNR) water appropriation permits (85-6144 and 85-6145);
- NPDES Permit MN 0056022 (renewed on May 15, 2000);
- City of Minneapolis site registration;
- the 2000-2005 Operations and Monitoring Plan (Appendix A);
- agreements made between GMI and the MPCA.



## 2.0 Quality Assurance

---

This section presents a review of the field sampling procedures and laboratory performance throughout 2003 as measured by the quality control samples. The monitoring program is described in Appendix A. Appendix B contains the field sampling report and laboratory report from the December monitoring event (previous data were presented in quarterly NPDES reports). The results of the analyses of the QC samples are in tables in Appendix C. The analytical data were evaluated according to the procedures outlined in the Barr Engineering Company Standard Operating Procedures for Routine Level Organic Data Validation (Barr 1999) derived from the U.S. EPA Functional Guidelines for Organic Data Review (1999).

Staff from Barr Engineering Company collected the field data and the samples submitted for laboratory analysis. Tri-Matrix Laboratories in Grand Rapids, Michigan, analyzed the samples using U.S. EPA approved methodologies.

The quality control review included reviewing the holding times, methods, trip samples and field blank samples, surrogate spike sample recoveries, matrix and matrix spike duplicate sample data (when applicable/relevant), laboratory control samples, and masked (or blind) duplicate sample data. Matrix spike (MS) and matrix spike duplicate (MSD) samples or laboratory control samples (LCS) and laboratory control sample duplicate (LCSD) data and masked duplicate sample data are used to measure laboratory based precision and accuracy. The accuracy was determined by the percent recovery of the spiked compounds, and the precision was determined by calculating the Relative Percent Difference (RPD) for the duplicate data pairs where both samples had detectable concentrations.

Field, trip and laboratory blank samples were collected and analyzed to monitor potential interference from incomplete decontamination of field equipment, sample transport contamination, and laboratory procedures. Following EPA guidance, positive concentrations in samples less than 5 times (or 10 times for common laboratory contaminants) the blank sample concentrations are qualified as potentially false positive values, and noted in the data tables.

The lab completed all analyses within holding times.

The trip blank for the October sampling event contained a trace amount of toluene at 2.2 µg/l. No detectable concentrations of target compounds were reported in any of the field or laboratory blanks associated with the 2003 monitoring. Table C-1 presents a summary of the blank sample results for 2003.



All surrogate spike recoveries for the 2003 sampling met acceptance criteria, indicating an acceptable level of precision and accuracy.

The laboratory control sample (LCS) percent recovery for all target compounds in 2003 met established acceptance criteria, indicating an acceptable level of precision and accuracy.

The MS and MSD data all met established acceptance criteria, indicating an acceptable level of precision and accuracy.

Masked duplicate samples were collected from sampling locations well 110, well 113 and MG-EFF. A summary of the masked duplicate sample results for 2003 are presented in Appendix C (Table C-2). The precision was determined by calculating the RPD for the data pairs where both sets of data had positive concentrations. The RPD results are dependent on the homogeneity of the sample. High RPDs are expected when results are at or near the reporting limit and do not always indicate poor precision. All RPD results met acceptance criteria.

All quality control aspects of the groundwater monitoring program at the site demonstrated compliance with the data quality objectives as measured by the quality control samples. All analytical data were validated and determined useable as presented in the data tables.



## **3.0 Groundwater Monitoring**

---

Figure 3 is a map of the site. Figure 4 shows the site monitoring points.

### **3.1 Water Level Monitoring**

The 2003 monitoring program included measuring water levels from six wells screened in the glacial drift; nine wells screened in the Carimona Member of the Platteville Formation; five wells open to the Magnolia Member of the Platteville Formation; and four wells screened in the St. Peter Sandstone. Well construction details are shown in Appendix D. Water level monitoring was carried out in accordance with the 2000–2005 Operations and Monitoring Plan (Appendix A). Historic groundwater elevations are in Appendix D. The 2003 water level measurements are described in Sections 3.1.1 through 3.1.4.

#### **3.1.1 Glacial Drift**

Groundwater elevations were measured in glacial drift monitoring wells Q, T, V, W and X on October 27, 2003 (Table 1). The estimated water table contours in the glacial drift are shown on Figure 5. As in past years, the 2003 water levels indicate groundwater in the glacial drift flows toward the southwest.

#### **3.1.2 Carimona Member of Platteville Formation**

Groundwater elevations were measured in nine Carimona Member monitoring wells 8, 9, 10, 11, 12, RR, SS, UU and WW on October 27, 2003 (Table 2). The estimated Carimona potentiometric surface is shown on Figure 6. As in past years, the 2003 water levels indicate groundwater in the Carimona member flows toward the north-northwest.

#### **3.1.3 Magnolia Member of Platteville Formation**

Water levels were measured in Magnolia Member monitoring wells OO, QQ, TT, VV and 14 on October 27, 2003 (Table 3). The estimated potentiometric surface is shown on Figure 7. As in past years, the 2003 water levels indicate groundwater in the Magnolia member flows toward the northwest. A recovery test was performed in October 2003 to verify capture areas for Magnolia pump-out wells MG1 and MG2, as discussed later in this report.



### **3.1.4 St. Peter Sandstone**

Water levels were measured in St. Peter Sandstone monitoring wells 200, 201, 202 and 203 on October 27, 2003 (Table 4). Figure 8 shows the locations of the St. Peter Sandstone monitoring wells and the estimated potentiometric surface. As in past years, the water levels indicate groundwater in the St. Peter Sandstone flows toward the southwest.

## **3.2 Water Quality Monitoring**

The 2003 annual monitoring program included the collection of water quality samples from monitoring wells screened in the glacial drift, wells open to the Carimona or Magnolia Members of the Platteville Formation, wells screened in the St. Peter Sandstone, and one well open to the Prairie du Chien/Jordan (former Henkel well). All monitoring activities were performed in accordance with the 2000-2005 Operations and Monitoring Plan (Appendix A). The 2000-2005 Operations and Monitoring Plan required that groundwater samples collected from the glacial drift, Platteville Formation, St. Peter Sandstone, and Prairie du Chien/Jordan wells during even years be analyzed for trichloroethylene (TCE) and during odd years be analyzed for the a longer list (Appendix A). The groundwater samples collected during 2003 were analyzed in accordance with the Plan.

The results of the 2003 analyses of monitoring well samples are in Tables 5 through 9. Results from the pumping wells are in Tables 10 through 12. The corresponding applicable Consent Order and NPDES permit limits are also shown in the tables. Historic TCE concentrations and corresponding Consent Order and NPDES permit limits for the glacial drift, Carimona Member, Magnolia Member, St. Peter Sandstone, Prairie du Chien/Jordan, and the groundwater pump-out and treatment system are summarized in Appendix D. The laboratory reports and chain-of-custody forms are in Appendix B. The results from the 2003 monitoring program are discussed in Section 5.0.

### **3.2.1 Monitoring Wells in the Glacial Drift**

Groundwater samples were collected from five glacial drift monitoring wells (Q, T, V, W and X) on October 27, 2003. The results from the laboratory analyses are in Table 5 and the TCE concentrations are shown on Figure 9. The 1985 through 2003 historic TCE concentrations in samples from glacial drift wells Q, X and V are shown on Figure 10.



### **3.2.2 Monitoring Wells in the Carimona Member of Platteville Formation**

Groundwater samples were collected from six monitoring wells (9, 10, 11, 12, SS and UU) screened in the Carimona Member of the Platteville Formation. The samples were collected over the period of October 28-30, 2003. The results from the laboratory analyses are in Table 6 and the TCE concentrations are shown on Figure 11. The 1985 through 2003 TCE concentrations for samples from Carimona Member wells 10 and 11 are shown on Figure 12.

### **3.2.3 Monitoring Wells in the Magnolia Member of Platteville Formation**

Groundwater samples were collected from three monitoring wells (14, QQ and TT) open to the Magnolia Member on October 28-29, 2003. The results from the laboratory analyses are in Table 7 and the TCE concentrations are shown on Figure 13. The 1985 through 2003 TCE concentrations for Magnolia Member wells QQ and TT are shown on Figure 14.

### **3.2.4 Monitoring Wells in the St. Peter Sandstone**

Groundwater samples were collected from St. Peter Sandstone monitoring wells 200, 202 and 203 on October 30-31, 2003. The results from the laboratory analyses are in Table 8 and the TCE concentrations are shown on Figure 15. Historic TCE concentrations for St. Peter Sandstone well 200 are shown on Figure 16.

### **3.2.5 Prairie du Chien/Jordan Monitoring Well**

A groundwater sample was collected from the former Henkel well, open to the Prairie du Chien/Jordan, on October 31, 2003. The results from the laboratory analysis are in Table 9.

### **3.2.6 Offsite Groundwater Pump-out System**

Composite samples were collected in June and October of 2003 from the downgradient glacial drift pump-out wells 111, 112 and 113. This composite was made up of equal volumes of groundwater grab samples from wells 111, 112 and 113. At the request of the MPCA, well-specific samples were also collected from the wells during the other two quarters (March and August) in 2003. For the events when individual samples were collected, the equivalent downstream discharge concentration was calculated using the results from the individual well samples using a flow-weighted average method based on the pumping rates of the individual wells. The samples were analyzed for the VOCs required by the NPDES permit



(Appendix A). The results from the laboratory analyses are in Table 10. The 1985 through 2003 TCE concentrations for the downgradient groundwater pump-out system discharge are shown on Figure 17.

### **3.2.7 Onsite Glacial Aquifer Pump-out and Treatment Systems**

Groundwater treatment system influent and effluent samples were collected quarterly (March, June, August, and October). Samples were collected using a combination of composite and grab samples, similar to the sampling of the downgradient pump-out well system described above. A composite influent sample was made up of equal volume grab samples from wells 109 and 110 during the June and October events. At the request of the MPCA, grab samples from wells 109 and 110 were analyzed during the March and August monitoring events. The combined influent concentration was calculated using a flow-weighted average. Air stripper effluent samples were collected after groundwater pumped from wells 109 and 110 had been treated in the air stripper. The results from the laboratory analyses are in Table 11. The 1985 through 2003 TCE concentrations for the air stripper influent and effluent samples are shown on Figure 17.

### **3.2.8 Onsite Magnolia Aquifer Pump-out System**

Samples were collected from the Magnolia groundwater pump-out system wells MG1 and MG2 quarterly (March, June, August, and October). Effluent from these wells is discharged to the base of the air stripper and then to the storm sewer. Similar to the other pump-out systems, a composite sample was analyzed during the June and October events, and individual well grab samples were analyzed during the March and August monitoring events. The results from the laboratory analysis are in Table 12. The 1993 through 2003 TCE concentrations for the MG pump-out well effluent are shown on Figure 18.

## **3.3 Surplus Wells**

This site has been investigated thoroughly over the years. Over time, it was recognized that many of the monitoring wells and two former recovery wells were no longer necessary for monitoring or recovery. These wells were not abandoned, but instead were retained in case further sampling or aquifer information was necessary. However, such needs have not been realized. These wells are not sampled and typically not used for water level information. Water quality information is obtained from wells in the same formation within a few hundred feet of these wells. Therefore, there are a number of wells that no longer serve any useful purpose, and have in fact become potential liabilities.



In accordance with the plan presented in the approved 2002 annual report, the following wells were abandoned in 2003: 1, G, GG, 106, 107, and 108. Copies of the abandonment records for these wells are in Appendix E. Additional approved abandonments could not be completed due to access issues (primarily student parking). Additional excess wells are scheduled for abandonment in 2004, as previously approved by the MPCA.



## 4.0 Remedial Action Operations

---

Although the new NPDES permit no longer requires monthly reporting of discharge, General Mills believed it was prudent to continue monthly site visits and system checks to ensure continuing system performance.

### 4.1 Groundwater Pump-out Systems

The East Hennepin Avenue Site groundwater pump-out system is made up of seven wells:

- Onsite glacial drift pump-out wells 109 and 110 (Figure 5)
- Onsite Platteville pump-out wells MG1 and MG2 (Figure 7)
- Downgradient glacial drift pump-out wells 111, 112 and 113 (Figure 5)

The performance of each pump-out system is discussed in Sections 4.1.1 through 4.1.4. The combined groundwater pump-out systems removed and discharged 309 million gallons of groundwater in 2003 (591 gpm). The average monthly pumping rate (gpm) for each of the pump-out wells is shown in Table 13. The operational downtime and operating time percentage for 2003 for each system are shown in Table 13. Figure 19 is a series of graphs illustrating pumping performance in 2003.

#### 4.1.1 Onsite Glacial Drift System

The onsite glacial drift pump-out well system (wells 109 and 110) is designed to contain groundwater in the glacial drift with the highest TCE concentrations as set forth in the October 25, 1984 Consent Order. The average combined pumping rate for the onsite glacial drift pump-out system during 2003 was 129 gallons per minute. Average monthly pumping rates for each well ranged from 41 to 81 gpm. A total of approximately 67.6 million gallons was removed from the glacial drift by the onsite glacial drift pump-out well system in 2003.

#### 4.1.2 Downgradient Glacial Drift System

The downgradient glacial drift pump-out well system is designed to contain groundwater in the glacial drift downgradient of the site with a concentration of TCE exceeding 270 µg/L as specified in the Consent Order. The downgradient glacial drift pump-out wells 111, 112 and 113 operated at an average combined rate of 266 gallons per minute in 2003. The pumping rates are monitored monthly, and individual monthly



pumping rates ranged from 58 to 124 gallons per minute (Table 13). Approximately 139 million gallons of groundwater was removed from the glacial drift by the downgradient pump-out system during 2003.

#### **4.1.3 Carimona System**

Carimona pump-out well 108 was abandoned in 2003, and had not been operated since 1993 when Magnolia pump-out wells MG1 and MG2 began operation.

#### **4.1.4 Magnolia System**

The Magnolia pump-out well system (wells MG1 and MG2) is designed to contain groundwater with a TCE concentration exceeding 27  $\mu\text{g/L}$  in both the Magnolia and Carimona Members of the Platteville Formation. Wells MG1 and MG2 operated at an average combined rate of 195 gallons per minute in 2003. The pumping rates are monitored monthly, and individual monthly pumping rates ranged from 67 to 106 gallons per minute. A total groundwater volume of approximately 102 million gallons was removed from the Platteville Formation during 2003 (Table 14).

A 24-hour aquifer recovery test was performed in October to verify capture areas for the Magnolia Member pump-out system. The pump-out wells were shut down for 24 hours. Water levels were measured in Carimona Member wells RR, SS and WW and Magnolia Member wells OO, TT and VV prior to shut down and 24 hours after shut down. Water level recoveries for these wells ranged from 2.30 to 9.70 feet (Table 14). The recovery test is discussed in detail in Section 5.7.

### **4.2 Maintenance and Downtime**

All pump-out wells were operated continuously at the maximum sustainable yield of the pumps or aquifer during 2003, except for shutdowns caused by electrical or mechanical failures, or the need for well or system maintenance. Table 13 presents reasons for downtime during 2003.

Appendix A lists target and action level pumping rates for each of the groundwater pump-out wells. When pumping rates for an individual well dropped below the monthly action level (Table 13), action was taken to return the pumping rate above the action level. Monthly pumping rates for the pump-out wells at wells 109 and 110 were above action levels indicating that the pump-out wells were operating effectively. However, the monthly pumping rates for the other pump-out wells were occasionally below their respective pumping rate action level. Well 112 again had the poorest performance in 2003, as was the case in recent years. Repeated maintenance, including redevelopment, chemical treatment, and new equipment,



have had limited success. In December 2002, the conveyance line between the well and the discharge point was jetted with a high-pressure line. Initially this action was encouraging, but overall performance in 2003 did not improve. Wells 111 and 113 typically performed well above design rate in 2003, so the slower rate at well 112 should not affect overall capture of the system. Well 113 fell below the action levels on two occasions in 2003. The pump in well 113 was about 10 years old, and was replaced in January 2004.

### **4.3 Groundwater Treatment System**

The glacial aquifer groundwater extracted on site contains the highest VOC concentrations, and is treated actively with an onsite air-stripping tower. The remaining extracted groundwater contains much lower concentrations of VOCs, and this groundwater is passively treated by discharge to the storm sewer system.

Influent and effluent data are summarized in Table 11. The NPDES Permit discharge limits include an annual average effluent TCE concentration of 50  $\mu\text{g/L}$  with a daily maximum limit of 100  $\mu\text{g/L}$ . The 2003 results from the treatment system effluent were below detection limits in all samples, in compliance with the NPDES Permit discharge limits.

The air stripper tower is designed to remove greater than 99 percent of volatile organic compounds from influent groundwater at a discharge rate of up to 150 gallons per minute and a total VOC concentration equal to 1985 conditions, or about 1,000  $\mu\text{g/L}$ . The pumping rate to the tower in 2003 averaged 129 gpm, and the influent VOC concentration ranged from 211  $\mu\text{g/L}$  to 305  $\mu\text{g/L}$ , so the system is operating well within design assumptions. Trace concentrations of VOCs detected in all of the four samples collected from the stripping tower effluent in 2003, confirming that the treatment system was operating effectively.

A complete media change-out of the stripper tower was conducted during a two week period in May of 2003. The spent material was shipped on May 29, 2003 to the SKB Rosemount industrial waste facility for proper disposal.

Scale formation within the air-stripping tower has been identified as a cause of decreased treatment efficiency. In 2000, General Mills installed a pre-treatment system in an effort to reduce hardness buildup. The effectiveness of this system continues to be evaluated. The system was upgraded once in 2001 with a multi-frequency model. A second upgrade to a more powerful unit was completed in February 2002. The effectiveness of this technology is not completely proven, and will continue to be evaluated.



## 5.0 Discussion of Water Quality Results

---

The 2003 monitoring results are consistent with past monitoring results. Graphical representations of historic TCE concentrations in samples from selected glacial drift, Carimona Member, Magnolia Member, and St. Peter Sandstone monitoring wells, the down gradient pump-out system, groundwater treatment system, and Magnolia pump-out system are shown on Figures 10, 12, 14, 16, 17 and 18, respectively. Historic TCE water quality data from the various sampling locations are in Appendix D.

Glacial drift and Platteville monitoring is focused on indicator wells selected to monitor pump-out system effectiveness. Several wells within the containment zone of the glacial drift and Platteville pump-out well systems are consequently not monitored. Historic TCE water quality results for samples from the indicator wells are in Appendix D.

### 5.1 Glacial Aquifer

The groundwater elevations indicate that the direction of groundwater flow in the glacial drift is to the southwest. The 2003 groundwater elevations are within the range of historic water elevations. Water level measurements collected during 1985 and 1986 following startup of the groundwater pump-out well systems demonstrated the effectiveness of the onsite and downgradient glacial drift pump-out systems in preventing lateral migration of glacial drift groundwater with TCE concentrations exceeding 270  $\mu\text{g/L}$ . Glacial drift groundwater elevations from 2003 indicate that the lateral containment zone established during 1985 and 1986 continues to be maintained.

#### 5.1.1 Site Groundwater Pump-out Systems

The results from the analyses of samples collected in 2003 from the onsite glacial drift pump-out well system indicate that the average TCE influent concentration was about 218  $\mu\text{g/L}$  and that the average total VOC concentration was about 250  $\mu\text{g/L}$  (Table 11). The laboratory results indicate that TCE remains the predominant volatile organic compound in the groundwater in the immediate vicinity of the Site. Historic trends are as follows (Figure 17):

- Glacial aquifer TCE concentrations in the onsite pump-out wells were:
  - Initially, about 1,000  $\mu\text{g/L}$ ;
  - Stabilized at about 400  $\mu\text{g/L}$  from about 1988 to 1999;



- Decreased to about 300  $\mu\text{g/L}$  from 1999 through 2000;
  - Decreased to about 250  $\mu\text{g/L}$  in 2001
  - Decreased to about 220  $\mu\text{g/L}$  in 2002.
  - Remained at about 220  $\mu\text{g/L}$  in 2003.
- Glacial aquifer TCE concentrations in the downgradient pump-out wells were:
    - Initially, about 300  $\mu\text{g/L}$ ;
    - Steadily declined to about 100  $\mu\text{g/L}$  in about 1991;
    - Steady at about 70  $\mu\text{g/L}$  since 1994 ( $\sim 2\mu\text{g/L}$  at 111;  $\sim 100\mu\text{g/L}$  at 113).
  - TCE concentrations in the onsite Magnolia wells were:
    - Initially, about 25  $\mu\text{g/L}$ ;
    - Declined to about 18  $\mu\text{g/L}$  by 1996
    - Stabilized at about 11  $\mu\text{g/L}$  since 2002.

Analyses of samples collected from wells 109 and 110 are in Table 11. The samples from well 110 contain about 325  $\mu\text{g/L}$  TCE; samples from well 109 contain about 130  $\mu\text{g/L}$  TCE. These results are consistent with pump-out well specific monitoring that has been conducted over the past five years.

### **5.1.2 Downgradient Pump-out System**

The average TCE concentration in 2003 samples was 48  $\mu\text{g/L}$ , and the average total VOC concentration was 57  $\mu\text{g/L}$  (Table 10), similar to results from the past 11 years (Figure 17). The NPDES permit establishes a pH limit and a requirement that no foam or oil sheen be present. The pH was consistently between 6.0 and 9.0 and there was no foam or oil sheen visible on any of the samples.

Analyses of samples collected from the individual pump out wells are in Table 10. The concentration of TCE detected in the sample from well 111 is one to two orders of magnitude lower than detected in samples from wells 112 and 113 (Table 10). Samples from well 113 consistently contain the highest TCE concentrations. TCE concentrations in samples from well 111 are near the detection limit. These results



are consistent with pump-out well specific monitoring that has been conducted over the past 4 years. These wells are designed to be pumped at similar rates.

### **5.1.3 Glacial Aquifer Monitoring Wells**

The 2003 monitoring results from the downgradient sentry wells (Table 5) indicate that the downgradient pump-out system is effective in laterally containing glacial drift groundwater with a TCE concentration exceeding 270  $\mu\text{g/L}$ . The results from 2003 are consistent with historical results. The TCE concentrations generally decreased after the startup of the glacial drift pump-out well systems in 1985 through about 1991, and thereafter have generally stabilized.

### **5.1.4 BTEX in the Glacial Aquifer**

At the request of the MPCA, BTEX (benzene, ethylbenzene, toluene and xylene) are being reported. None of these compounds were detected in the 2003 monitoring well samples collected from the glacial aquifer. Nor were these compounds detected in the samples from pumping wells 109, 110, 111, 112, or 113.

## **5.2 Carimona Member of Platteville Formation**

Water levels in the Carimona monitoring wells were generally comparable to those measured in recent years. The potentiometric levels (Figure 6) indicate that the direction of groundwater flow in the immediate vicinity of the site continues to be towards the northwest.

Historic TCE concentrations (1986-2003) reported for wells 10 and 11 are shown on Figure 12. Historic results for all wells are in Table D-7 (Appendix D).

Samples from wells SS, 9, and 12 during 2003 have typically had the lowest TCE concentrations of the Carimona monitoring wells, less than 5  $\mu\text{g/L}$ . The 2003 results are similar to historic results.

When sampling began in the mid-1980s, samples from the other Carimona wells typically had TCE concentrations ranging from 100s to 1,000s of  $\mu\text{g/L}$ . The TCE concentrations in samples from these wells have generally declined since the startup of the Platteville groundwater recovery system in 1985, and stabilized in about 1995 at concentrations less than 100  $\mu\text{g/L}$ . The 2003 concentrations in the samples from these wells are consistent with historic results, with all results being less than 50  $\mu\text{g/L}$ . Based on the water level data, groundwater from wells UU, 8, and 10 is likely flowing toward either: well SS, where the TCE concentration is about 3  $\mu\text{g/L}$ ; or downward into the Magnolia member where groundwater is being captured (see next section).



Toluene, ethylbenzene and xylene were not detected in any of the Carimona member well samples. Benzene was detected in the samples from wells 9 and 11. Benzene detected at 9 was 12  $\mu\text{g/L}$ .

### **5.3 Magnolia Member of Platteville Formation**

The potentiometric groundwater surface elevations measured in October 2003 are similar to water elevations measured since the Magnolia pump-out system began operation in 1993. The potentiometric levels (Figure 7) indicate the direction of groundwater flow in the immediate vicinity of the Site continues to be northwest.

#### **5.3.1 Magnolia Member Pumping Wells**

The 2003 results indicate an average TCE concentration of 12  $\mu\text{g/L}$  and an average total VOC concentration of 15.8  $\mu\text{g/L}$  in the groundwater extracted from the Magnolia member (Table 12). There was a general downward trend of TCE in the Magnolia well effluent since system startup in 1993 through 2002 (Figure 18). The TCE concentration in the initial Magnolia effluent samples was about 30  $\mu\text{g/L}$ . The concentration of TCE measured in the 2003 samples from well MG1 was approximately two times that in samples from well MG2, which is also consistent with historic data.

The NPDES permit establishes discharge limits for the Magnolia pump-out system for TCE and pH, and a requirement that no foam or an oil sheen be present. Throughout 2003, TCE was below its limit, the pH was between the permit limits of 6.0 and 9.0 and there was no foam or oil sheen.

A 24-hour recovery test was performed using the Magnolia Member wells on October 27 and 28, 2003. The test was performed as outlined in the 2000-2005 Operations and Monitoring Plan. The purpose of the test was to determine if Magnolia pump-out wells MG1 and MG2 are maintaining an adequate capture zone in the Platteville Formation. The recovery test involved measuring water levels in wells RR, SS, VV, OO, TT and WW prior to and 24 hours after a shutdown of pump-out wells MG1 and MG2. The difference between the two measurements is the recovery, which is equivalent to the drawdown created by the pumping of the wells. The annually computed drawdown is compared to the drawdown measured during the initial testing in 1992.

The drawdowns measured in 2003 range from 2.30 feet in well RR to 9.70 feet in well TT (Table 14). In each case, the 2003 drawdown exceeds the 1992 drawdown. Since the 1992 drawdowns were shown to provide adequate capture, and the 2003 drawdowns all exceed the startup drawdowns, it follows that the Magnolia pump-out system maintained adequate capture in 2003.



### **5.3.2 Magnolia Monitoring Wells**

The analyses of samples from Magnolia Member wells indicate no detection of TCE in the sample from well QQ. TCE concentrations of 4.7  $\mu\text{g/L}$  and 5.6  $\mu\text{g/L}$  were detected in samples from wells 14 and TT, respectively (Table 7). Figure 14 shows TCE concentrations over time in samples from wells QQ and TT.

Prior to start up of the Magnolia pumping wells, samples from well TT contained about 25  $\mu\text{g/L}$  TCE and samples from well QQ contained about 8  $\mu\text{g/L}$  TCE. Following start up of pumping, TCE concentrations at both wells TT and QQ declined to less than 10  $\mu\text{g/L}$ . Well 14 was installed in 1998 to provide an additional downgradient monitoring point. TCE had increased in both wells TT and 14, and appeared to have stabilized from 2000-2002 at about 8  $\mu\text{g/L}$ . In 2003 TCE concentrated levels have dropped to about 5  $\mu\text{g/L}$ . TCE concentrations in samples from pumping well MG1 have also dropped to concentrations less than 10  $\mu\text{g/L}$ . TCE in Magnolia pumping well MG2 samples has dropped to less than 20  $\mu\text{g/L}$ . TCE concentrations remain below the Consent Order level of 27  $\mu\text{g/L}$  in all samples. The pumping rates, the recovery test data, and the water quality data show that pump-out wells MG1 and MG2 continue to effectively capture Platteville Formation groundwater and control the extent of the TCE concentration specified in the Consent Order.

### **5.3.3 BTEX in the Magnolia Member**

BTEX compounds were not detected in the samples from the Magnolia monitoring wells.

## **5.4 St. Peter Sandstone**

Water elevations in St. Peter monitoring wells 200, 201, 202 and 203 were consistent with historic water elevations, and the potentiometric levels (Figure 8) indicate the direction of groundwater flow is to the southwest, consistent with regional flow in the St. Peter Sandstone and historic data from the site.

Historically, TCE concentrations have been highest in samples from well 200, which is a few hundred feet downgradient of the site. From initial site work through 1997, samples from well 200 contained about 100  $\mu\text{g/L}$  TCE. After 1997, the concentrations dropped off sharply, and have been below 10  $\mu\text{g/L}$  since 2000.

Consistent with historic results, TCE concentrations were not detectable in the sample from well 202. The 2003 sample from well 203 contained 28  $\mu\text{g/L}$  TCE. This was the fourth year of increasing concentrations.

None of the BTEX compounds were detected in the samples from the St. Peter monitoring wells.



## **5.5 Prairie du Chien/Jordan**

TCE was detected at 4 µg/L in the sample collected from the Henkel well in 2003. Concentrations when monitoring began in the mid-1980s were near 50 µg/L. TCE has been below 10 µg/L in all but one sample since 1994, and has been below detection in three of the six samples since 1998.

None of the BTEX compounds were detected in the sample from the Prairie du Chien/Jordan aquifer monitoring well.



## 6.0 Conclusions

---

1. The 2003 operations and maintenance were consistent with historic O&M. The remediation system is about 15 years old, and remaining original equipment is beginning to wear, leading to slightly more maintenance each year, but this should not affect overall performance of the system. No emergency or contingency actions were necessary in 2003. Table 15 summarizes monitoring and maintenance completed in 2003.
2. The stripper media was changed out in May 2003. General Mills continues to evaluate the performance of a pre-treatment unit, and has installed an updated version.
3. All water level data are consistent with historic data, and the groundwater flow patterns in the various aquifers appear to have stayed constant.
4. The 2003 water quality monitoring results are generally consistent with historic results. The monitoring program appears to be appropriate and adequate for the site. As discussed in the following paragraphs, water quality remains stable at most wells, but there have been some significant declining trends.
5. Groundwater produced by glacial aquifer pumping well 110 continues to have TCE concentrations above the Consent Order limit of 270  $\mu\text{g/L}$ . TCE concentrations appear to be declining in the onsite glacial aquifer pump out wells, and appear stable in the downgradient glacial aquifer pumping wells and monitoring wells. Most downgradient monitoring well samples contain less than 10  $\mu\text{g/L}$  TCE, including pump out well 111.
6. The Carimona Member acts as a leaky confining layer between the glacial drift and the Magnolia Member. TCE in samples from the Carimona member dropped by one to two orders of magnitude, and have remained stable at less than 100  $\mu\text{g/L}$  for many years. Concentrations of TCE were detected above the Consent Order limit (27  $\mu\text{g/L}$ ) in one well in 2003, 48  $\mu\text{g/L}$  at well 11. This is an upgradient well in the Carimona member. Benzene was detected at 12  $\mu\text{g/L}$  at well 9.
7. The Magnolia Member pump-out wells have a greater influence on the vertical gradient than did Carimona pump-out well 108. The increased hydraulic gradient causes increased leakage from the Carimona Member into the Magnolia Member, and allows for greater capture of affected groundwater. The Magnolia Member pump-out wells MG1 and MG2 effectively act as containment wells for lateral



flow of groundwater in the Carimona Member, per the Consent Order, and in the Magnolia member. The Magnolia Member recovery test data indicate that pump-out wells MG1 and MG2 are maintaining equal or better capture compared to their initial assessment. The highest TCE concentrations from the Magnolia Member wells are detected in the samples from pumping well MG1 (~15 µg/L). The TCE concentrations in all Magnolia Member samples from 2003 were below the Consent Order limit of 27 µg/L. However, given the concentrations detected in the Carimona Member and the glacial aquifer, pumping of the Magnolia wells should continue.

8. In the last five years, TCE concentrations have declined dramatically in St. Peter aquifer well 200, which is closest to the site, from about 100 µg/L to less than 5 µg/L. Although TCE concentrations have been increasing in samples from well 203, it appears that the rate of increase is declining.
9. Trichloroethene was detected in the Henkel well sample, which has been the case in three of the last six samples. The 2003 concentration is much lower than when monitoring began in the mid-1980s.
10. At the request of the MPCA, General Mills has reported and evaluated benzene, ethylbenzene, toluene, and xylene results in the 2002 and 2003 water quality monitoring data. There were only a few reported detections of BTEX compounds in the shallow aquifers, and the data as a whole suggest that this site is not a significant source of these compounds.
11. General Mills has identified a number of wells that are no longer useful to the site remediation, and so have become potential liabilities. About half were abandoned in 2003, and the remaining excess wells should be abandoned in 2004.



## 7.0 Recommendations for 2004

---

1. Continue operation and maintenance of the onsite pump-out and groundwater treatment systems and the downgradient glacial drift pump-out system in accordance with the 1984 Consent Order and other regulatory documents.
2. Inspect the groundwater pump-out wells and treatment systems on at least a monthly basis.
3. Submit treatment system and pump-out system monitoring results on a quarterly basis per the NPDES permit.
4. Monitor groundwater elevations and groundwater quality in accordance with the 2000–2005 Operations and Monitoring Plan.
5. Collect and analyze pump-out well-specific samples during two quarters in 2004.
6. Discontinue monitoring of benzene, ethyl benzene, toluene and xylene.
7. Abandon wells that are no longer necessary (see Figure 20 and Table 16).



## References

---

- Barr Engineering Company, February 2003. *2002 Annual Report East Hennepin Ave. Site*. Prepared for General Mills, Inc.
- Barr Engineering Company, August 30, 2001. Letter report from William J Bangsund to Larry Deeney, General Mills (copied to Mark Rys and Dagmar Romano, MPCA), re: results of shallow soil investigation, East Hennepin Ave. Site.
- Barr Engineering Company, 1999. *Standard Operating Procedures for Routine Level Organic Data Validation*, 1999.
- MPCA, September 28, 2001. Letter from Dagmar Romano, MPCA, to Larry Deeney, General Mills. Re: Approval of shallow soil investigation report, East Hennepin Avenue Site.
- MPCA, May 15, 2000. National Pollutant Discharge Elimination System Permit, MN 0056022.
- MPCA, September 1999. Five-Year Review Report, General Mills/Henkel Corporation.
- MPCA, September 1994. Five-Year Review Report, General Mills/Henkel Corporation.
- MPCA, October 25, 1984. Administrative Consent Order.
- USEPA. *USEPA Contract Laboratory Program National Functional Guidelines for Organic Data Review*, OSWER 9240.1-05A-P, October 1999.



Tables



**Table 1**  
**2003 Groundwater Elevations**  
**Glacial Drift Wells**

(elevations in ft.-MSL)

| <b>Location<br/>Date</b> | <b>Q<br/>10/27/2003</b> | <b>T<br/>10/27/2003</b> | <b>V<br/>10/27/2003</b> | <b>W<br/>10/27/2003</b> | <b>X<br/>10/27/2003</b> |
|--------------------------|-------------------------|-------------------------|-------------------------|-------------------------|-------------------------|
| <b>Water Elevation</b>   | 828.18                  | 832.50                  | 818.02                  | 817.97                  | 823.07                  |



**Table 2**  
**2003 Groundwater Elevations**  
**Carimona Member Wells**

(elevations in ft.-MSL)

| Location        | RR         | RR         | SS         | SS         | UU         | WW         | WW         |
|-----------------|------------|------------|------------|------------|------------|------------|------------|
| Date            | 10/27/2003 | 10/28/2003 | 10/27/2003 | 10/28/2003 | 10/27/2003 | 10/27/2003 | 10/28/2003 |
| Water Elevation | 831.22     | 833.52     | 824.26     | 829.13     | 831.09     | 831.10     | 833.41     |

| Location        | 8          | 9          | 10         | 11         | 12         |
|-----------------|------------|------------|------------|------------|------------|
| Date            | 10/27/2003 | 10/27/2003 | 10/27/2003 | 10/27/2003 | 10/27/2003 |
| Water Elevation | 831.22     | 831.27     | 831.46     | 831.08     | 825.42     |



**Table 3**  
**2003 Groundwater Elevations**  
**Magnolia Member Wells**  
  
**(elevations in ft.-MSL)**

| <b>Location</b>        | <b>OO</b>         | <b>OO</b>         | <b>QQ</b>         | <b>TT</b>         | <b>TT</b>         | <b>VV</b>         | <b>VV</b>         | <b>14</b>         |
|------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|-------------------|
| <b>Date</b>            | <b>10/27/2003</b> | <b>10/28/2003</b> | <b>10/27/2003</b> | <b>10/27/2003</b> | <b>10/28/2003</b> | <b>10/27/2003</b> | <b>10/28/2003</b> | <b>10/27/2003</b> |
| <b>Water Elevation</b> | 820.43            | 828.52            | 820.70            | 817.16            | 826.86            | 823.44            | 829.63            | 816.50            |



**Table 4**  
**2003 Groundwater Elevations**  
**St. Peter Sandstone Wells**

(elevations in ft.-MSL)

|                        |                   |                   |                   |                   |
|------------------------|-------------------|-------------------|-------------------|-------------------|
| <b>Location</b>        | <b>200</b>        | <b>201</b>        | <b>202</b>        | <b>203</b>        |
| <b>Date</b>            | <b>10/27/2003</b> | <b>10/27/2003</b> | <b>10/27/2003</b> | <b>10/27/2003</b> |
| <b>Water Elevation</b> | 766.23            | 779.59            | 754.56            | 754.41            |



**Table 5**  
**2003 Water Quality Data**  
**Glacial Drift Wells**

(concentrations in ug/L)

| Location<br>Date            | Q<br>10/29/2003 | T<br>10/29/2003 | V<br>10/29/2003 | W<br>10/29/2003 | X<br>10/29/2003 | Consent<br>Order Limit |
|-----------------------------|-----------------|-----------------|-----------------|-----------------|-----------------|------------------------|
| 1,1,1-Trichloroethane       | 2.4             | <1.0            | <1.0            | <2.0            | <1.0            | --                     |
| 1,1,2,2-Tetrachloroethane   | <1.0            | <1.0            | <1.0            | <2.0            | <1.0            | --                     |
| 1,1-Dichloroethane          | <1.0            | <1.0            | <1.0            | <2.0            | <1.0            | --                     |
| 1,2-Dichloroethane          | <1.0            | <1.0            | <1.0            | <2.0            | <1.0            | --                     |
| 1,2-Dichloroethylene, cis   | <1.0            | <1.0            | <1.0            | 52              | <1.0            | --                     |
| 1,2-Dichloroethylene, trans | <1.0            | <1.0            | <1.0            | 3.5             | <1.0            | --                     |
| Benzene                     | <1.0            | <1.0            | <1.0            | <2.0            | <1.0            | --                     |
| Ethyl benzene               | <1.0            | <1.0            | <1.0            | <2.0            | <1.0            | --                     |
| Tetrachloroethylene         | <1.0            | <1.0            | <1.0            | <2.0            | <1.0            | --                     |
| Toluene                     | <1.0            | <1.0            | <1.0            | <2.0            | <1.0            | --                     |
| Trichloroethylene           | <1.0            | <1.0            | 14              | 14              | <1.0            | 270                    |
| Vinyl chloride              | <1.0            | <1.0            | <1.0            | <2.0            | <1.0            | --                     |
| Xylenes total               | <3.0            | <3.0            | <3.0            | <6.0            | <3.0            | --                     |

-- No consent order limit.



**Table 6**  
**2003 Water Quality Data**  
**Carimona Member Wells**

(concentrations in ug/L)

| Location                    | SS         | UU         | 9          | 10         | 10         | 11         | 12         | Consent     |
|-----------------------------|------------|------------|------------|------------|------------|------------|------------|-------------|
| Date                        | 10/28/2003 | 10/29/2003 | 10/30/2003 | 10/30/2003 | 10/30/2003 | 10/28/2003 | 10/28/2003 | Order Limit |
| Dup                         |            |            |            |            | DUP        |            |            |             |
| 1,1,1-Trichloroethane       | <1.0       | 1.5        | <1.0       | 1.2        | 1.2        | <2.0       | <1.0       | --          |
| 1,1,2,2-Tetrachloroethane   | <1.0       | <1.0       | <1.0       | <1.0       | <1.0       | <2.0       | <1.0       | --          |
| 1,1-Dichloroethane          | 3.0        | <1.0       | <1.0       | <1.0       | <1.0       | <2.0       | <1.0       | --          |
| 1,2-Dichloroethane          | <1.0       | <1.0       | <1.0       | <1.0       | <1.0       | <2.0       | <1.0       | --          |
| 1,2-Dichloroethylene, cis   | <1.0       | <1.0       | <1.0       | <1.0       | <1.0       | 7.5        | <1.0       | --          |
| 1,2-Dichloroethylene, trans | <1.0       | <1.0       | <1.0       | <1.0       | <1.0       | <2.0       | <1.0       | --          |
| Benzene                     | <1.0       | <1.0       | 12         | <1.0       | <1.0       | 6.9        | <1.0       | --          |
| Ethyl benzene               | <1.0       | <1.0       | <1.0       | <1.0       | <1.0       | <2.0       | <1.0       | --          |
| Tetrachloroethylene         | <1.0       | <1.0       | <1.0       | <1.0       | <1.0       | <2.0       | <1.0       | --          |
| Toluene                     | <1.0       | <1.0       | <1.0       | <1.0       | <1.0       | <2.0       | <1.0       | --          |
| Trichloroethylene           | 2.9        | 25         | 1.1        | 15         | 16         | 48         | 1.7        | 27          |
| Vinyl chloride              | <1.0       | <1.0       | <1.0       | <1.0       | <1.0       | <2.0       | <1.0       | --          |
| Xylenes total               | <3.0       | <3.0       | <3.0       | <3.0       | <3.0       | <6.0       | <3.0       | --          |

-- No consent order limit.



**Table 7**  
**2003 Water Quality Data**  
**Magnolia Member Wells**

(concentrations in ug/L)

| Location<br>Date            | QQ<br>10/29/2003 | TT<br>10/28/2003 | 14<br>10/28/2003 | Consent<br>Order Limit |
|-----------------------------|------------------|------------------|------------------|------------------------|
| 1,1,1-Trichloroethane       | <1.0             | 2.0              | 1.6              | --                     |
| 1,1,2,2-Tetrachloroethane   | <1.0             | <1.0             | <1.0             | --                     |
| 1,1-Dichloroethane          | <1.0             | <1.0             | <1.0             | --                     |
| 1,2-Dichloroethane          | <1.0             | <1.0             | <1.0             | --                     |
| 1,2-Dichloroethylene, cis   | 1.1              | 2.9              | 1.7              | --                     |
| 1,2-Dichloroethylene, trans | <1.0             | <1.0             | <1.0             | --                     |
| Benzene                     | <1.0             | <1.0             | <1.0             | --                     |
| Ethyl benzene               | <1.0             | <1.0             | <1.0             | --                     |
| Tetrachloroethylene         | <1.0             | <1.0             | <1.0             | --                     |
| Toluene                     | <1.0             | <1.0             | <1.0             | --                     |
| Trichloroethylene           | <1.0             | 5.6              | 4.7              | 27                     |
| Vinyl chloride              | <1.0             | <1.0             | <1.0             | --                     |
| Xylenes total               | <3.0             | <3.0             | <3.0             | --                     |

-- No consent order limit.



**Table 8**  
**2003 Water Quality Data**  
**St. Peter Sandstone Wells**

(concentrations in ug/L)

| Location<br>Date            | 200<br>10/31/2003 | 202<br>10/30/2003 | 203<br>10/31/2003 | Consent<br>Order Limit |
|-----------------------------|-------------------|-------------------|-------------------|------------------------|
| 1,1,1-Trichloroethane       | <1.0              | <1.0              | <1.0              | --                     |
| 1,1,2,2-Tetrachloroethane   | <1.0              | <1.0              | <1.0              | --                     |
| 1,1-Dichloroethane          | <1.0              | <1.0              | <1.0              | --                     |
| 1,2-Dichloroethane          | <1.0              | <1.0              | <1.0              | --                     |
| 1,2-Dichloroethylene, cis   | 1.6               | <1.0              | 3.6               | --                     |
| 1,2-Dichloroethylene, trans | <1.0              | <1.0              | <1.0              | --                     |
| Benzene                     | <1.0              | <1.0              | <1.0              | --                     |
| Ethyl benzene               | <1.0              | <1.0              | <1.0              | --                     |
| Tetrachloroethylene         | <1.0              | <1.0              | <1.0              | --                     |
| Toluene                     | <1.0              | <1.0              | <1.0              | --                     |
| Trichloroethylene           | 4.2               | <1.0              | 28                | 27                     |
| Vinyl chloride              | <1.0              | <1.0              | <1.0              | --                     |
| Xylenes total               | <3.0              | <3.0              | <3.0              | --                     |

-- No consent order limit.



**Table 9**  
**2003 Water Quality Data**  
**Prairie Du Chien / Jordan Well**

(concentrations in ug/L)

| Location<br>Date            | HENKEL<br>10/31/2003 |
|-----------------------------|----------------------|
| 1,1,1-Trichloroethane       | <1.0                 |
| 1,1,2,2-Tetrachloroethane   | <1.0                 |
| 1,1-Dichloroethane          | <1.0                 |
| 1,2-Dichloroethane          | <1.0                 |
| 1,2-Dichloroethylene, cis   | 4.2                  |
| 1,2-Dichloroethylene, trans | <1.0                 |
| Benzene                     | <1.0                 |
| Ethyl benzene               | <1.0                 |
| Tetrachloroethylene         | <1.0                 |
| Toluene                     | <1.0                 |
| Trichloroethylene           | 4.0                  |
| Vinyl chloride              | <1.0                 |
| Xylenes total               | <3.0                 |



**Table 10**  
**2003 Water Quality Data**  
**Downgradient Glacial Drift Pump-Out System**

(concentrations in ug/L)

| Location<br>Date<br>Dup     | 111<br>3/13/2003 | 112<br>3/13/2003 | 113<br>3/13/2003 | Flow<br>Weighted<br>Discharge<br>3/13/2003 | Discharge<br>6/2/2003 | Flow<br>Weighted<br>Discharge<br>6/2/2003 | 111<br>8/26/2003 | 112<br>8/26/2003 | 113<br>8/26/2003 | 113<br>8/26/2003<br>DUP | Flow<br>Weighted<br>Discharge<br>8/26/2003 | Discharge<br>10/31/2003 | Flow<br>Weighted<br>Discharge<br>10/31/2003 |
|-----------------------------|------------------|------------------|------------------|--|-----------------------|---|------------------|------------------|------------------|-------------------------|--|-------------------------|---|
| 1,1,1-Trichloroethane       | 3.2              | 1.7              | <5.0             | NC   | 2.8                   | NC  | 1.8              | <1.0             | <5.0             | <10                     | NC   | <2.0                    | NC  |
| 1,1,2,2-Tetrachloroethane   | <1.0             | <1.0             | <5.0             | NC   | <2.0                  | NC  | <1.0             | <1.0             | <5.0             | <10                     | NC   | <2.0                    | NC  |
| 1,1-Dichloroethane          | <1.0             | <1.0             | <5.0             | NC   | <2.0                  | NC  | <1.0             | <1.0             | <5.0             | <10                     | NC   | <2.0                    | NC  |
| 1,2-Dichloroethane          | <1.0             | <1.0             | <5.0             | NC   | <2.0                  | NC  | <1.0             | <1.0             | <5.0             | <10                     | NC   | <2.0                    | NC  |
| 1,2-Dichloroethylene, cis   | <1.0             | 2.8              | 18               | NC   | 7.2                   | NC  | <1.0             | 2.7              | 19               | 20                      | NC   | 6.3                     | NC  |
| 1,2-Dichloroethylene, trans | <1.0             | <1.0             | <5.0             | NC   | <2.0                  | NC  | <1.0             | <1.0             | <5.0             | <10                     | NC   | <2.0                    | NC  |
| Benzene                     | <1.0             | <1.0             | <5.0             | NC   | <2.0                  | NC  | <1.0             | <1.0             | <5.0             | <10                     | NC   | <2.0                    | NC  |
| Ethyl benzene               | <1.0             | <1.0             | <5.0             | NC   | <2.0                  | NC  | <1.0             | <1.0             | <5.0             | <10                     | NC   | <2.0                    | NC  |
| Tetrachloroethylene         | <1.0             | 2.2              | <5.0             | NC   | <2.0                  | NC  | <1.0             | 1.4              | <5.0             | <10                     | NC   | <2.0                    | NC  |
| Toluene                     | <1.0             | <1.0             | <5.0             | NC   | <2.0                  | NC  | <1.0             | <1.0             | <5.0             | <10                     | NC   | <2.0                    | NC  |
| Trichloroethylene           | 2.9              | 52               | 110              | 47   | 44                    | 44  | 1.7              | 40               | 90               | 100                     | 55   | 48                      | 48  |
| Vinyl chloride              | <1.0             | <1.0             | <5.0             | NC   | <2.0                  | NC  | <1.0             | <1.0             | <5.0             | <10                     | NC   | <2.0                    | NC  |
| Xylenes total               | <3.0             | <3.0             | <15              | NC   | <6.0                  | NC  | <3.0             | <3.0             | <15              | <30                     | NC   | <6.0                    | NC  |
| Sum Volatile Organics       | 6.1              | 59               | 128              | 55   | 54                    | 54  | 3.5              | 44               | 109              | 120                     | 65   | 54                      | 54  |

-- Not analyzed.

NC Flow weighted average not calculated for these individual contaminants.



**Table 11**  
**2003 Water Quality Data**  
**Site Glacial Drift Pump-Out and Treatment Systems**

(concentrations in ug/L)

| Location                    | 109       | 110       | 110       | 110       | Flow Weighted Site Glacial Drift Influent Average | INF      | 109       | 110       | Flow Weighted Site Glacial Drift Influent Average | INF        | EFF **    | EFF **   | EFF **    | EFF **     |
|-----------------------------|-----------|-----------|-----------|-----------|---|----------|-----------|-----------|---|------------|-----------|----------|-----------|------------|
| Date                        | 3/13/2003 | 3/13/2003 | 3/13/2003 | 3/13/2003 | 3/13/2003   | 6/2/2003 | 8/26/2003 | 8/26/2003 | 8/26/2003   | 10/31/2003 | 3/13/2003 | 6/2/2003 | 8/26/2003 | 10/31/2003 |
| Dup                         |           |           |           | DUP       |   |          |           |           |   |            |           |          |           |            |
| 1,1,1-Trichloroethane       | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| 1,1,2,2-Tetrachloroethane   | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| 1,1-Dichloroethane          | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| 1,2-Dichloroethane          | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| 1,2-Dichloroethylene, cis   | 5.0       | 73        | 67        | 67        | NC  | 40       | <5.0      | 54        | NC  | 24         | <1.0      | <1.0     | <1.0      | <1.0       |
| 1,2-Dichloroethylene, trans | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| Benzene                     | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| Ethyl benzene               | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| Tetrachloroethylene         | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| Toluene                     | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| Trichloroethylene           | 150       | 340       | 350       | 350       | 262   | 220      | 110       | 300       | 188   | 200        | <1.0      | <1.0     | <1.0      | <1.0       |
| Vinyl chloride              | <5.0      | <10       | <10       | <10       | NC  | <10      | <5.0      | <10       | NC  | <10        | <1.0      | <1.0     | <1.0      | <1.0       |
| Xylenes total               | <15       | <30       | <30       | <30       | NC  | <30      | <15       | <30       | NC  | <30        | <3.0      | <3.0     | <3.0      | <3.0       |
| Sum Volatile Organics       | 155       | 413       | 417       | 417       | 305   | 260      | 110       | 354       | 211   | 224        | ND        | ND       | ND        | ND         |

ND Not detected.

NC Flow weighted average not calculated for these individual contaminants.

\*\* Effluent limit for TCE - 50 ug/L average and 100 ug/L instantaneous



**Table 12**  
**2003 Water Quality Data**  
**Magnolia Pump-Out System**

(concentrations in ug/L)

| Location<br>Date<br>Dup     | MG1<br>3/13/2003 | MG2<br>3/13/2003 | Flow<br>Weighted<br>MG<br>Discharge<br>Average<br>3/13/2003 | MGEFF<br>6/2/2003 | MGEFF<br>6/2/2003<br>DUP | Flow<br>Weighted<br>MG<br>Discharge<br>Average<br>6/2/2003 | MG1<br>8/26/2003 | MG2<br>8/26/2003 | Flow<br>Weighted<br>MG<br>Discharge<br>Average<br>8/26/2003 | MGEFF<br>10/31/2003 |
|-----------------------------|------------------|------------------|---|-------------------|--------------------------|--|------------------|------------------|---|---------------------|
| 1,1,1-Trichloroethane       | <1.0             | <1.0             | NC  | <1.0              | <1.0                     | NC   | <1.0             | <1.0             |   | <1.0                |
| 1,1,2,2-Tetrachloroethane   | <1.0             | <1.0             | NC  | <1.0              | <1.0                     | NC   | <1.0             | <1.0             | NC  | <1.0                |
| 1,1-Dichloroethane          | <1.0             | <1.0             | NC  | <1.0              | <1.0                     | NC   | <1.0             | <1.0             | NC  | <1.0                |
| 1,2-Dichloroethane          | <1.0             | <1.0             | NC  | <1.0              | <1.0                     | NC   | <1.0             | <1.0             | NC  | <1.0                |
| 1,2-Dichloroethylene, cis   | 3.3              | 1.6              | NC  | 2.5               | 1.7                      | NC   | 2.9              | 1.8              | NC  | 2.1                 |
| 1,2-Dichloroethylene, trans | <1.0             | <1.0             | NC  | <1.0              | <1.0                     | NC   | <1.0             | <1.0             | NC  | <1.0                |
| Benzene                     | 1.3              | <1.0             | NC  | 1.0               | 1.0                      | NC   | 1.7              | <1.0             | NC  | <1.0                |
| Ethyl benzene               | <1.0             | <1.0             | NC  | <1.0              | <1.0                     | NC   | <1.0             | <1.0             | NC  | <1.0                |
| Tetrachloroethylene         | <1.0             | <1.0             | NC  | <1.0              | <1.0                     | NC   | <1.0             | <1.0             | NC  | <1.0                |
| Toluene                     | <1.0             | <1.0             | NC  | <1.0              | <1.0                     | NC   | 2.7 b            | <1.0             | NC  | <1.0                |
| Trichloroethylene           | 19               | 9.6              | 14.4  | 12                | 12                       | 12   | 15               | 8.0              | 10.9  | 12                  |
| Vinyl chloride              | <1.0             | <1.0             | NC  | <1.0              | <1.0                     | NC   | <1.0             | <1.0             | NC  | <1.0                |
| Xylenes total               | <3.0             | <3.0             | NC  | <3.0              | <3.0                     | NC   | <3.0             | <3.0             | NC  | <3.0                |
| Sum Volatile Organics       | 23.6             | 11.2             | 17.6  | 15.5              | 14.7                     | 15.1   | 22.3             | 9.8              | 15.0  | 14.1                |

ND Not detected.

NC Flow weighted average not calculated for these individual contaminants.



Table 13  
2002 Pumping Rates

|  | Glacial Drift Pumpout Wells<br>Average Pumping Rate<br>(gpm) |     |     |     |     | Magnolia Pumpout Wells<br>Average Pumping Rate<br>(gpm) |     |
|--|--|-----|-----|-----|-----|---|-----|
|  | 109  | 110 | 111 | 112 | 113 | MG1   | MG2 |
| Target Pumping Rate<br>(Average Monthly gpm) | 30   | 50  | 90  | 100 | 90  | 100   | 100 |
| Action Level (Average<br>Monthly gpm)        | 20   | 40  | 80  | 80  | 80  | 80  | 80  |
| January-03                                   | 74   | 50  | 103 | 65  | 93  | 96  | 94  |
| February-03                                  | 80   | 53  | 110 | 64  | 8   | 105   | 100 |
| March-03                                     | 87   | 59  | 136 | 69  | 0   | 117   | 111 |
| April-03                                     | 84   | 59  | 96  | 67  | 82  | 111   | 106 |
| May-03                                       | 50   | 36  | 100 | 62  | 83  | 70  | 61  |
| June-03                                      | 78   | 55  | 106 | 70  | 87  | 110   | 94  |
| July-03                                      | 85   | 60  | 106 | 64  | 87  | 119   | 102 |
| August-03                                    | 74   | 52  | 102 | 84  | 83  | 67  | 94  |
| September-03                                 | 76   | 55  | 102 | 80  | 82  | 94  | 103 |
| October-03                                   | 74   | 54  | 107 | 77  | 86  | 79  | 99  |
| November-03                                  | 79   | 56  | 114 | 81  | 92  | 98  | 109 |
| December-03                                  | 74   | 40  | 107 | 74  | 69  | 91  | 102 |
| 2003 Average Monthly<br>gpm                  | 76   | 52  | 107 | 71  | 71  | 96  | 98  |
| 2002 Average Monthly<br>gpm                  | 80   | 51  | 109 | 50  | 100 | 97  | 99  |
| 2001 Average Monthly<br>gpm                  | 49   | 46  | 108 | 77  | 90  | 97  | 98  |
| 2000 Average Monthly<br>gpm                  | 43   | 40  | 94  | 47  | 100 | 104   | 95  |



Table 14

Recovery Test Comparison Summary

| Well | Pumping Levels in Ft. MSL |                            | Non-Pumping Levels in Ft. MSL |          | Recovery (ft)<br>10/27/03 | Drawdown (ft)<br>1992 Test | 2003 $\Delta$ (ft) | 2002 $\Delta$ (ft) | 2001 $\Delta^1$ (ft) | 2000 $\Delta^2$ (ft) |
|------|---------------------------|----------------------------|-------------------------------|----------|---------------------------|----------------------------|--------------------|--------------------|----------------------|----------------------|
|      | 10/1/92<br>(for 8 days)   | 10/27/03<br>(for 11 years) | 9/22/92                       | 10/28/03 |                           |                            |                    |                    |                      |                      |
| RR   | 828.21                    | 831.22                     | 829.81                        | 833.52   | 2.30                      | 1.60                       | 0.7                | 0.85               | 0.59                 | 0.66                 |
| OO   | 819.64                    | 820.43                     | 825.69                        | 828.52   | 8.09                      | 6.05                       | 2.04               | 2.35               | 1.52                 | 1.46                 |
| SS   | 824.57                    | 824.26                     | 827.31                        | 829.13   | 4.87                      | 2.74                       | 2.13               | 3.44               | 3.37                 | 2.60                 |
| TT   | 816.65                    | 817.16                     | 823.22                        | 826.86   | 9.70                      | 6.57                       | 3.13               | 3.42               | 2.38                 | 2.21                 |
| VV   | 821.33                    | 823.44                     | 826.96                        | 829.63   | 6.19                      | 5.23                       | 0.96               | 1.42               | 0.86                 | 0.91                 |
| WW   | 828.08                    | 831.10                     | 829.71                        | 833.41   | 2.31                      | 1.63                       | 0.68               | 1.03               | 0.55                 | 0.63                 |

$\Delta^1$  = Recovery (12/6/01) – Drawdown (1992 test)

$\Delta^2$  = Recovery (11/22/00) – Drawdown (1992 test)



**Table 15**  
**Summary of 2003 Activities**

| <b>2003</b> | <b>Monitoring and Reporting</b>  | <b>O&amp;M</b>  |
|-------------|--|---|
| January     | 10 – Quarterly NPDES Report to GMI/MPCA<br>24 – 2002 Water Appropriations Worksheets submitted | 2 – Site inspection<br>31 – Site Inspection   |
| February    | 28 – Submitted 2002 Annual Report  | 28 – Site Inspection  |
| March       | 13 – Discharge Monitoring<br>24 – Quarterly Maintenance  | Greasing motors, maintenance totalizers recording electrical AMPs. Rebuilt totalizer meter for 113. |
| April       | 9 – Quarterly NPDES report to GMI/MPCA<br>29 – Manifested media waste to SKB-Rosemount         | 3 – Site inspection<br>Upgraded Freiji system.<br>Completed media change-out.                       |
| May         | 2 – Discharge monitoring<br>22 – Completed waste profile sheet for stripper media              | 5 – Site Inspection   |
| June        |  | 2 – Site Inspection<br>Greasing motors; totalizer maintenance; recording electrical AMPs.           |
| July        | 10 – Quarterly NPDES Report to GMI/MPCA  | 1 – Site Inspection   |
| August      | 6 – Discharge monitoring   | 4 – Site inspection<br>Greasing motors, maintenance totalizers recording electrical AMPs.           |
| September   |  | 2 – Site inspection   |
| October     | Annual monitoring event<br>4 – Quarterly NPDES Report to GMI/MPCA                              | 1 – Site inspection.  |
| November    |  | Abandoned Wells 108, G, GG, 107, 106, and 1.<br>20 – Site Maintenance                               |
| December    |  | 1 – Site inspection<br>31 – Site inspection   |



Table 16  
Proposed Wells to be Abandoned

| Well Name | Geologic Unit    | Well Monitored Annually | Abandon? | Comments                                     |
|-----------|------------------|-------------------------|----------|--|
| B         | Glacial Drift    | --                      | --       | Up gradient clean glacial drift well.        |
| P         | Glacial Drift    | --                      | Yes      | Condition unknown.                           |
| Q         | Glacial Drift    | WQ                      | --       | Down gradient of source used for monitoring. |
| R         | Glacial Drift    | --                      | Yes      | Area adequately monitored by V, W, and T     |
| S         | Glacial Drift    | --                      | --       | Middle of plume between 110 and 112.         |
| T         | Glacial Drift    | WQ                      | --       | Down gradient of source.                     |
| U         | Glacial Drift    | --                      | Yes      | Well is lateral of the source.               |
| V         | Glacial Drift    | WQ                      | --       | Down gradient of source.                     |
| W         | Glacial Drift    | WQ                      | --       | Down gradient of source.                     |
| X         | Glacial Drift    | WQ                      | --       | Down gradient of source.                     |
| 2         | Glacial Drift    | --                      | --       | Good location down gradient of source.       |
| 3         | Glacial Drift    | --                      | Yes      | Area adequately monitored by V, W, and T     |
| 4         | Glacial Drift    | --                      | Yes      | Area adequately monitored by V, W, and T     |
| 5         | Glacial Drift    | --                      | Yes      | Area adequately monitored by V, W, and T     |
| 109       | Glacial Drift    | WQ                      | --       | Active pump-out well                         |
| 110       | Glacial Drift    | WQ                      | --       | Active pump-out well                         |
| 111       | Glacial Drift    | WQ                      | --       | Active pump-out well                         |
| 112       | Glacial Drift    | WQ                      | --       | Active pump-out well                         |
| 113       | Glacial Drift    | WQ                      | --       | Active pump-out well                         |
| 8         | Carimona Member  | WQ                      | --       | Possibly unnecessary because of 9, and 10.   |
| 9         | Carimona Member  | WQ                      | --       | Down gradient of source.                     |
| 10        | Carimona Member  | WQ                      | --       | Down gradient of source.                     |
| 11        | Carimona Member  | WQ                      | --       | Down gradient of source.                     |
| 12        | Carimona Member  | WQ                      | --       | Up gradient                                  |
| 13        | Carimona Member  | --                      | Yes      | Up gradient?                                 |
| BB        | Carimona Member  | --                      | --       | Center of plume                              |
| SS        | Carimona Member  | WQ                      | --       | Down gradient of source.                     |
| UU        | Carimona Member  | WQ                      | --       | Down gradient of source.                     |
| RR        | Carimona Member  | WL                      | --       | Up gradient?                                 |
| WW        | Carimona Member  | WL                      | --       | Monitoring can be collected at 9 and 10.     |
| 14        | Magnolia Member  | WQ                      | --       | Newly installed lateral location             |
| QQ        | Magnolia Member  | WQ                      | --       | Down gradient                                |
| OO        | Magnolia Member  | WL                      | --       | QQ is one block side gradient.               |
| TT        | Magnolia Member  | WQ                      | --       | Upgradient                                   |
| VV        | Magnolia Member  | WL                      | --       | Upgradient of source                         |
| ZZ        | Magnolia Member  | --                      | Yes      | Upgradient of source                         |
| MG-1      | Magnolia Member  | WQ                      | --       | Active pump-out well                         |
| MG-2      | Magnolia Member  | WQ                      | --       | Active pump-out well                         |
| 200       | St. Peter        | WQ                      | --       | Down gradient of source used for monitoring. |
| 201       | St. Peter        | WL                      | --       | Upgradient                                   |
| 202       | St. Peter        | WQ                      | --       | Down gradient of source used for monitoring. |
| 203       | St. Peter        | WQ                      | --       | Down gradient of source used for monitoring. |
| Henkel    | Prairie du Chien | WQ                      | --       | Only Prairie du Chein well                   |

WQ Water quality and water level monitoring

WL Water level monitoring only



Table 16  
Previously Abandoned Wells  
Continued

| Well Name | Geologic Unit     | Well Monitored Annually | Abandon? | Well Abandoned         |
|-----------|-------------------|-------------------------|----------|------------------------|
| 1         | Glacial Drift     | na                      | Yes      | Well Abandoned 2003    |
| A         | Glacial Drift     | na                      | Yes      | Abandoned              |
| C         | Glacial Drift     | na                      | Yes      | Abandoned              |
| D         | Glacial Drift     | na                      | Yes      | Abandoned              |
| E         | Glacial Drift     | na                      | Yes      | Abandoned              |
| F         | Glacial Drift     | na                      | Yes      | Abandoned              |
| G         | Glacial Drift     | na                      | Yes      | Well abandoned in 2003 |
| H         | Glacial Drift     | na                      | Yes      | Abandoned              |
| I         | Glacial Drift     | na                      | Yes      | Abandoned              |
| J         | Glacial Drift     | na                      | Yes      | Abandoned              |
| K         | Glacial Drift     | na                      | Yes      | Abandoned              |
| L         | Glacial Drift     | na                      | Yes      | Abandoned              |
| M         | Glacial Drift     | na                      | Yes      | Abandoned              |
| N         | Glacial Drift     | na                      | Yes      | Abandoned              |
| O         | Glacial Drift     | na                      | Yes      | Abandoned              |
| Y         | Glacial Drift     | na                      | Yes      | Abandoned              |
| Z         | Glacial Drift     | na                      | Yes      | Abandoned              |
| GG        | Magnolia Member   | na                      | Yes      | Well abandoned in 2003 |
| II        | Carimona/Magonlia | na                      | Yes      | Abandoned              |
| LL        | Carimona/Magonlia | na                      | Yes      | Abandoned              |
| PP        | Carimona Member   | na                      | Yes      | Abandoned              |
| 106       | Glacial Drift     | na                      | Yes      | Well abandoned in 2003 |
| 107       | Glacial Drift     | na                      | Yes      | Well abandoned in 2003 |
| 108       | Carimona Member   | na                      | Yes      | Well abandoned in 2003 |



## Figures







Figure 1

EAST HENNEPIN AVENUE SITE  
REGIONAL LOCATION MAP





Sand, gravelly sand and silty sand, sometimes overlain by bogs and marshes which have been drained and filled. Overlying soil is variable in composition often clayey or silty. Deposits are terrace deposits from Glacial River Warren. Thickness ranges from 23 to 57 feet.

Gray and red tills associated with Des Moines and Superior lobes. Unsorted material with variable texture containing clay sizes and boulders. Sometimes underlain by thin layer of alluvium. Contains sand lenses. Absent in many places, up to 20' thick.

Greenish-gray to olive-gray claystone, fissile, fossiliferous, contains several limestone layers. Patchy in this area. Thicknesses range up to 50'.

Carimona member - micrite, fossiliferous, often fractured and weathered, 3.5-4.5' thick.

Magnolia member - fossiliferous micrite, calcitic shale, with rippled bedding, corroded zones, some fractures. 8.5-9' thick.

Hidden Falls - micrite, shaly, fossiliferous, 6-7' thick.

Mifflin member, thin beds of limestone, interbedded shale 12-13' thick.

Pecatonica member - dolomite, hard, 1-1.5' thick.

Glenwood shale - green shale, sandy at the base, 3-5' thick.

Light yellow or white, medium grained, massive appearing sandstone composed of rounded and subrounded grains. Thin beds of green shale are present. Ranges in thickness from 150-170'.

Thickness of entire formation is 120'-150'.

Oneota Dolomite - thin to thick bedded, light brownish gray or buff, fine- to medium-grained dolomite, silt sized dolomite matrix.

New Richmond Sandstone - fine- to medium-grained quartzose sandstone and quartzitic dolomite, minor amounts of shale and pure dolomite.


Willow River Dolomite - thin to thick bedded dolomite, sandy dolomite with some interbedded quartzose sandstone.

Argillaceous and dolomitic quartz sandstone with pebble-size clasts of dolomitic sandstone and thin beds of dolomite, white or yellow, coarse to medium-grained orthoquartzites to yellow, silty, fine grained quartzose sandstone. 85-100' thick. Underlain by the St. Lawrence Formation which is 120'-200' thick and contains a variety of silty or sandy dolomitic rocks.

Figure 2

GENERALIZED GEOLOGIC COLUMN






0 80 160  
SCALE IN FEET

- ▲ Glacial Drift Pump-Out Well
- ⊕ Magnolia Member Pump-Out Well
- Monitoring Well
- Well Abandoned in 2003

Figure 3  
EAST HENNEPIN AVENUE  
SITE MAP



dmd:M:\CAD\2327169\16268-3.dwg Plot at 500 01/20/2004 5:35



- GLACIAL DRIFT MONITORING WELL
- ◆ SITE AND DOWNGRAIDENT GLACIAL DRIFT PUMP-OUT WELL
- ST. PETER SANDSTONE MONITORING WELL
- \* FORMER DISPOSAL SITE
- ▲ CARIMONA MEMBER MONITORING WELL
- ⊙ MAGNOLIA MEMBER MONITORING WELL
- ⊕ MAGNOLIA MEMBER PUMP-OUT WELL
- WELL ABANDONED 2003




Figure 4  
SITE MONITORING WELL LOCATIONS






- 



GLACIAL DRIFT AQUIFER  
WATER TABLE ELEVATIONS  
October 27, 2003





▲ CARIMONA MEMBER MONITORING WELL

830.44 CARIMONA POTENTIOMETRIC SURFACE ELEVATION (MSL)

—828— CARIMONA POTENTIOMETRIC SURFACE CONTOUR (MSL)

\* FORMER DISPOSAL SITE


○ WELL ABANDONED 2003



0 400 800  
SCALE IN FEET

Figure 6  
CARIMONA MEMBER  
POTENTIOMETRIC SURFACE ELEVATIONS  
October 27, 2003





- ⊙ MAGNOLIA MEMBER MONITORING WELL
- ⊠ MAGNOLIA MEMBER PUMP-OUT WELL
- 819.93 MAGNOLIA MEMBER POTENTIOMETRIC SURFACE ELEVATIONS (MSL)
- 820 — MAGNOLIA MEMBER SURFACE POTENTIOMETRIC SURFACE CONTOUR (MSL)
- - - CAPTURE ZONE
- \* FORMER DISPOSAL SITE




0 400 800  
SCALE IN FEET

Figure 7

MAGNOLIA MEMBER  
POTENTIOMETRIC SURFACE ELEVATIONS  
October 27, 2003





- ST. PETER SANDSTONE MONITORING WELL
- 754.08 ST. PETER SANDSTONE POTENTIOMETRIC SURFACE ELEVATION (MSL)
- 760— ST. PETER SANDSTONE POTENTIOMETRIC SURFACE CONTOUR (MSL)
- \* FORMER DISPOSAL SITE





Figure 8  
ST. PETER SANDSTONE  
MONITORING WELL LOCATIONS AND  
POTENTIOMETRIC SURFACE ELEVATIONS  
October 27, 2003



dmd M:\CAD\2327189\12337\_6.DWG Plot at 1 01/20/2004 10:52:37




NOTE: INDIVIDUAL ANALYTICAL RESULTS FOR PUMP-OUT WELLS ARE TAKEN FROM AUG. 2003.


Figure 9  
GLACIAL DRIFT  
GROUNDWATER QUALITY (TCE)  
October 2003



Figure 10  
Glacial Drift Wells  
TCE Concentrations  
1985-2003







- ▲ CARIMONA MEMBER MONITORING WELL
- [57] TRICHLOROETHYLENE CONCENTRATION (TCE) ( $\mu\text{g/L}$ )
- [ ] NOT DETECTED
- \* FORMER DISPOSAL SITE
- WELL ABANDONED IN 2003




0 400 800  
SCALE IN FEET

Figure 11


CARIMONA MEMBER  
GROUNDWATER QUALITY (TCE)  
October 2003



Figure 12  
 Carlmona Member Wells  
 TCE Concentrations  
 1985-2003







- ▲ MAGNOLIA MEMBER MONITORING WELL
- △ MAGNOLIA MEMBER PUMP-OUT WELL
- 8.4 TRICHLOROETHYLENE CONCENTRATION (TCE) (ug/L)
- ND NOT DETECTED
- \* FORMER DISPOSAL SITE





Figure 13

MAGNOLIA MEMBER  
GROUNDWATER QUALITY (TCE)  
November 2002


NOTE: INDIVIDUAL ANALYTICAL RESULTS FOR PUMP-OUT  
WELLS ARE TAKEN FROM AUG. 2003.



Figure 14  
Magnolia Member Wells  
TCE Concentrations  
1985-2003







- ST. PETER SANDSTONE MONITORING WELL
- [6.4] TRICHLOROETHYLENE CONCENTRATION (TCE) ( $\mu\text{g/L}$ )
- [ND] NOT DETECTED
- \* FORMER DISPOSAL SITE



0 400 800  
SCALE IN FEET

Figure 15

ST PETER SANDSTONE  
GROUNDWATER QUALITY (TCE)  
November 2002



Figure 16  
St. Peter Sandstone Wells  
TCE Concentrations  
1985-2003






Figure 17  
Trichloroethylene in Glacial Aquifer Pump-Out Systems  
1985-2003








Figure 18  
Magnolia Pump-Out Wells (MG1 and MG2)  
TCE Concentrations  
1992-2003






# General Mills Flow Data







0 500 1000  
SCALE IN FEET

Figure 20  
PROPOSED WELL ABANDONMENTS  
FOR 2004



## *Appendices*



## Appendix A

### East Hampton Avenue Site 2000-2005 Operation and Monitoring Plan



## **Appendix A**

### **East Hennepin Avenue Site 2000–2005 Operations and Monitoring Plan**

The following monitoring plan governs the period January 1, 2000 to December 31, 2005. The plan is consistent with the terms of the Consent Order, and is suitable for a site with a status characterized as long-term operation and monitoring.

Intensive monitoring of the East Hennepin Avenue Site has occurred since February 1984. The results from this monitoring have defined the limits of groundwater contamination; have documented the effectiveness of the site groundwater pump-out systems; and have documented that site conditions in all affected aquifers have been stable since 1987.

The Consent Order specifies that the purpose of the groundwater monitoring program is to: monitor the effectiveness of the groundwater pump-out systems; define changes in the distribution of volatile hydrocarbon concentrations; and determine when operation of the system can be shut down.

The effectiveness of groundwater pump-out systems has been determined through aquifer pumping tests and groundwater modeling. The operational history (pumping rates and total gallons pumped) has been monitored since 1985. This time period includes both record wet and record dry years.

General Mills, Inc. has agreed to monitor the continued effectiveness of the pump-out systems through water quality monitoring and through operational monitoring. Water quality monitoring, including sample collection and analysis and water level measurement, will involve the annual collection of groundwater samples from down gradient Glacial Drift wells Q, T, V, W and X; Platteville wells 9, 10, 11, 12, 14, QQ, SS, TT and UU; St. Peter Well 200 and the Henkel Well. The samples will be analyzed on alternating years for trichloroethylene and List 2 volatile organic compounds (Table A-1). Well 8 will no longer be monitored because it is downgradient from wells 9 and 10 and is upgradient of wells SS and UU. Additionally, samples will be collected annually from St. Peter wells 202 and 203 and analyzed for TCE. Water levels will continue to be measured at Well 201 but no samples will be collected for analysis at this location.

Operational monitoring will involve the comparison of monthly mean pumping rates with historic pumping rates. If pumping rates fall below an action level (Table A-2), an assessment of the operational status of the well will be conducted and necessary repairs will be made.



Platteville Formation pump-out system operational monitoring will also include an annual 24-hour recovery test. This test will be conducted to determine if Magnolia member pump-out wells MG1 and MG2 are maintaining an adequate capture zone in the Platteville Formation. The recovery test will involve the measurement of water levels in wells RR, SS, VV, OO, TT and WW. Water levels will be measured prior to and 24 hours after an annual shutdown of pump-out wells MG1 and MG2. The data will be evaluated to determine if the Magnolia wells continue to generate similar drawdown as was observed during the 1992 pumping test.

NPDES monitoring will continue as specified in the permit. NPDES monitoring currently involves the collection of effluent water quality samples from each pump-out system and the stripper tower. ~~In addition to trichloroethylene and List 2 volatile organic compounds, priority pollutant volatile organic compounds and flow rate measurements are required on a routine basis.~~ Table A-1 lists the monitoring parameters required by the new May 11, 2000 NPDES permit.

Quarterly letter reports describing the results of operations, monitoring and maintenance will be prepared and submitted to the Minnesota Pollution Control Agency. The reports will contain tables summarizing operational and monitoring data. Laboratory data reports will be attached to the report. Any data which indicates a long-term change in the operational status or effectiveness of the pump-out systems will be discussed in detail. A description of any action taken in response to this information will also be documented.



**Table A-1**

**Monitoring Parameters  
(Modified in 2001)**

| <b>Monitoring Wells<br/>Even Years</b> | <b>Monitoring Wells<br/>Odd Years (List 2)</b>   | <b>NPDES Stations</b>  |
|--|--|--|
| Water levels and field data            | Water Levels and field data  | Flows<br>pH  |
| Trichloroethylene                      | 1,1-Dichloroethane<br>1,2-Dichloroethane<br>1,2-Dichloroethene, cis<br>1,2-Dichloroethene, trans<br>1,1,2,2-Tetrachloroethane<br>Tetrachloroethylene<br>1,1,1-Trichloroethane<br>Trichloroethylene<br>Vinyl Chloride<br>Benzene<br>Ethylbenzene <sup>(1)</sup><br>Toluene<br>Xylenes | 1,1-Dichloroethane<br>1,2-Dichloroethane<br>1,2-Dichloroethene, cis<br>1,2-Dichloroethene, trans<br>1,1,2,2-Tetrachloroethane<br>Tetrachloroethylene<br>1,1,1-Trichloroethane<br>Trichloroethylene<br><br>Benzene<br>Ethylbenzene <sup>(1)</sup><br>Toluene<br>Xylenes |

(1) Added in 2001 at request of MPCA



**Table A-2**

**Pump-out System Operation Guidelines  
Pumping Rates**

| <b>Pump-out Well Identification</b> | <b>Target Pumping Rate<br/>(Average Monthly gpm)</b> | <b>Action Level<br/>(Average Monthly gpm)</b> |
|-------------------------------------|--|---|
| Well 109                            | 30   | 20  |
| Well 110                            | 50   | 40  |
| Well 111                            | 90   | 80  |
| Well 112                            | 100  | 80  |
| Well 113                            | 90   | 80  |
| Well MG1                            | 100  | 80  |
| Well MG2                            | 100  | 80  |

If action levels are not met, an assessment of the operational status of the pump-out well will be undertaken and any necessary repairs will be made.



## *Appendix B*

### *Field Sampling Report and Laboratory Data Reports*





## FIELD SAMPLING REPORT

---

**Date:** November 24, 2003  
**Project:** General Mills  
**Contact:** Bill Bangsund  
Barr Engineering Company  
4700 W. 77th Street  
Minneapolis, MN 55435-4803

### Field Sampling

Annual groundwater monitoring at the General Mills site was conducted on October 27<sup>th</sup> to 31<sup>st</sup>, 2003. The Platteville Formation pumpout system recovery test was completed on October 27<sup>th</sup> and 28<sup>th</sup>, 2003.


### Field Report

Attachments:

- Field Log Cover Sheet
- Water Level Summary
- Field Log Data Summary
- Pumpout System Recovery Test
- Field Log Data Sheets
- Meter Calibration Summary
- Chain-of-Custodies #17458 and #16559

### Laboratory Analysis Status

Samples sent to Trimatrix, Grand Rapids, Michigan for analysis. Refer to chain-of-custodies and parameter table for specific laboratory analyses.



Kirk Johannessen  
Water Quality





## FIELD LOG COVER SHEET WATER SAMPLING

**Client:** General Mills

**Project No.:** 23/27-169 YO3 1002

**Technician:** KSJ

**Sampling Period:** October 27, 28, 29, 30, 31,  
2003

| Date | Temperature | Wind Speed | Wind Direction | Cloud Cover |
|------|-------------|------------|----------------|-------------|
|------|-------------|------------|----------------|-------------|

### Summary of Field Activities

- Water levels were measured on October 27, 2003.
- Blind duplicate sample M-1 was collected at Well 10. A field blank was collected in the stripper tower on October 31.
- The 24-hour recovery test was performed on October 27 and 28, 2003.
- Fourth quarter pumpout system well-specific samples were collected on October 31, 2003.



## WATER LEVEL SUMMARY

Project: GENERAL MILLS

Project Number: 23/27-169YO3

Field Staff: KSJ

Date: 10-27-03

| Monitoring Location | Measuring point elevation | Water level depth | Total well depth | Static water elevation | Comments |
|---------------------|---------------------------|-------------------|------------------|------------------------|----------|
| 109                 | 857.97                    | 28.95             |                  | 829.02                 | toc      |
| 110                 | 852.35                    | 24.40             |                  | 827.95                 |          |
| 111                 | 846.94                    | 29.26             |                  | 817.68                 |          |
| 112                 | 841.37                    | 33.50             |                  | 807.87                 |          |
| 113                 | 841.26                    | 22.20             |                  | 819.06                 |          |
| Q                   | 850.38                    | 22.20             | 25.5             | 828.18                 |          |
| T                   | 849.36                    | 16.86             | 24.0             | 832.50                 |          |
| V                   | 838.59                    | 20.57             | 27.5             | 818.02                 |          |
| W                   | 830.78                    | 12.81             | 19.0             | 817.97                 |          |
| X                   | 842.90                    | 19.83             | 21.0             | 823.07                 |          |
| 8                   | 860.36                    | 29.14             | 64.0             | 831.22                 |          |
| 9                   | 862.48                    | 31.21             | 63.0             | 831.27                 |          |
| 10                  | 860.39                    | 28.93             | 64.0             | 831.46                 |          |
| 11                  | 852.84                    | 21.76             | 54.0             | 831.08                 |          |
| 12                  | 861.10                    | 35.68             | 63.0             | 825.42                 |          |
| RR                  | 849.97                    | 18.75             | 50.5             | 831.22                 |          |
| SS                  | 861.70                    | 37.44             | 60.5             | 824.26                 |          |
| UU                  | 863.98                    | 32.89             | 63.0             | 831.09                 |          |
| WW                  | 857.76                    | 26.66             | 60.5             | 831.10                 |          |
| OO                  | 850.07                    | 29.64             | 60.5             | 820.43                 |          |
| QQ                  | 849.01                    | 28.31             | 59.5             | 820.70                 |          |
| TT                  | 861.94                    | 44.78             | 70.0             | 817.16                 |          |
| VV                  | 859.09                    | 35.65             | 70.5             | 823.44                 |          |
| 200                 | 851.14                    | 84.91             | 198.0            | 766.23                 |          |
| MG-1                | 860.81                    | 55.84             |                  | 804.97                 | toc      |
| MG-2                | 859.82                    | 51.47             |                  | 808.35                 | toc      |
| 201                 | 885.09                    | 105.50            | 144.0            | 779.59                 |          |
| 203                 | 850.05                    | 95.64             | 118.0            | 754.41                 |          |
| 202                 | 843.45                    | 88.89             | 116.0            | 754.56                 |          |
| 14                  | 858.53                    | 42.03             | 68.5             | 816.50                 |          |



# WATER LEVEL SUMMARY

Project: GENERAL MILLS

Project Number: 23/27-169YO2

Date: 10-27-03

Field Staff: KST

| Monitoring Location | Measuring point elevation | Water level depth | Total well depth | Static water elevation | Comments |
|---------------------|---------------------------|-------------------|------------------|------------------------|----------|
| 109                 | 857.97                    | 28.95             |                  | --                     | TOC      |
| 110                 | 852.35                    | 24.40             |                  | --                     |          |
| 111                 | 846.94                    | 29.26             |                  | --                     |          |
| 112                 | 841.37                    | 33.50             |                  | --                     |          |
| 113                 | 841.26                    | 22.20             |                  | --                     |          |
| Q                   | 850.38                    | 22.20             | 25.5             | --                     |          |
| T                   | 849.36                    | 16.86             | 24.0             | --                     |          |
| V                   | 838.59                    | 20.57             | 27.5             | --                     |          |
| W                   | 830.78                    | 12.81             | 19.0             | --                     |          |
| X                   | 842.90                    | 19.83             | 21.0             | --                     |          |
| 8                   | 860.36                    | 29.14             | 64.0             | --                     |          |
| 9                   | 862.48                    | 31.21             | 63.0             | --                     |          |
| 10                  | 860.39                    | 28.93             | 64.0             | --                     |          |
| 11                  | 852.84                    | 21.76             | 54.0             | --                     |          |
| 12                  | 861.10                    | 35.68             | 63.0             | --                     |          |
| RR                  | 849.97                    | 18.75             | 50.5             | --                     |          |
| SS                  | 861.70                    | 37.44             | 60.5             | --                     |          |
| UU                  | 863.98                    | 32.89             | 63.0             | --                     |          |
| WW                  | 857.76                    | 26.66             | 60.5             | --                     |          |
| OO                  | 850.07                    | 29.64             | 60.5             | --                     |          |
| QQ                  | 849.01                    | 28.31             | 59.5             | --                     |          |
| TT                  | 861.94                    | 44.78             | 70.0             | --                     | new lock |
| VV                  | 859.09                    | 35.65             | 70.5             | --                     |          |
| 200                 | 851.14                    | 84.91             | 198.0            | --                     |          |
| MG-1                | 860.81                    | 55.84             |                  | --                     | TOC      |
| MG-2                | 859.82                    | 51.47             |                  | --                     | TOC      |
| 201                 | 885.09                    | 105.50            | 144.0            | --                     |          |
| 203                 | 850.05                    | 95.64             | 118.0            | --                     |          |
| 202                 | 843.45                    | 88.89             | 116.0            | --                     |          |
| 14                  | 858.53                    | 42.03             | 68.5             | --                     |          |

13 18.42  
 S 20.23  
 5 20.73



# WATER LEVEL SUMMARY

Platville formation 24-hour recovery test

Project: General Mills

Project Number: 2327169

Field Staff: KSJ

| Monitoring Location | Measuring point elevation | Date:<br>10/27/03 | Date:<br>10/28/03 | Date:<br>10/27/03 | Date:<br>10/28/03 | Recovery |
|---------------------|---------------------------|-------------------|-------------------|-------------------|-------------------|----------|
|                     |                           | Water level       | Water level       | Static elevation  | Static elevation  |          |
| RR                  | 849.97                    | 18.75             | 16.45             | 831.22            | 833.52            | 2.30     |
| SS                  | 861.70                    | 37.44             | 32.57             | 824.26            | 829.13            | 4.87     |
| WW                  | 857.76                    | 26.66             | 24.35             | 831.10            | 833.41            | 2.31     |
| OO                  | 850.07                    | 29.64             | 21.55             | 820.43            | 828.52            | 8.09     |
| TT                  | 861.94                    | 44.78             | 35.08             | 817.16            | 826.86            | 9.70     |
| VV                  | 859.09                    | 35.65             | 29.46             | 823.44            | 829.63            | 6.19     |
| MG 1                | 860.81                    | 55.84             | 32.29             | 804.97            | 828.52            | 23.55    |
| MG 2                | 859.82                    | 51.47             | 31.36             | 808.35            | 828.46            | 20.11    |
|                     |                           |                   |                   |                   |                   |          |
|                     |                           |                   |                   |                   |                   |          |
|                     |                           |                   |                   |                   |                   |          |

\* Measurements are referenced from top of riser pipe, unless otherwise indicated.

WLSUMM.WB2



## Platville formation 24-hour recovery test

Environmental Technician: K S J

[illegible]

\* Measurements are referenced from top of riser pipe, unless otherwise indicated.

WLSUMMWB2



## FIELD DATA SUMMARY

Project: GENERAL MILLS

Project number: 23/27-169Y03102

Field Staff: KSJ

| Monitoring location | Date     | Temp (oC) | Conductivity @ 25 oC | Dissolved Oxygen (mg/l) | pH   | Eh (mV) |
|---------------------|----------|-----------|----------------------|-------------------------|------|---------|
| EFF                 | 10/31/03 | 10.6      | 1299                 | 7.33                    | 7.82 | 26      |
| 109                 | "        | 12.2      | 1027                 | 7.59                    | 7.29 | 44      |
| 110                 | "        | 12.5      | 1202                 | 5.97                    | 7.11 | 54      |
| MG-1                | "        | 11.5      | 837                  | 7.32                    | 7.52 | 44      |
| MG-2                | "        | 11.1      | 832                  | 7.30                    | 7.25 | 48      |
| 111                 | "        | 12.0      | 1021                 | 6.47                    | 7.02 | 26      |
| 112                 | "        | 12.3      | 1058                 | 5.25                    | 6.94 | 33      |
| 113                 | "        | 11.7      | 1093                 | 8.36                    | 7.02 | 43      |
|                     |          |           |                      |                         |      |         |



## FIELD DATA SUMMARY

Project: GENERAL MILLS

Project number: 23/27-169Y01102

Field Staff: KSJ

| Monitoring location | Date     | Temp (oC) | Conductivity @ 25 oC | Dissolved Oxygen (mg/l) | pH   | Eh (mV) |
|---------------------|----------|-----------|----------------------|-------------------------|------|---------|
| EFF                 | 10-31-03 | 10.6      | 1299                 | 7.33                    | 7.82 | 26      |
| 109                 | "        | 12.2      | 1027                 | 7.59                    | 7.29 | 44      |
| 110                 | "        | 12.5      | 1202                 | 5.97                    | 7.11 | 54      |
| MG-1                | "        | 11.5      | 837                  | 7.32                    | 7.52 | 44      |
| MG-2                | "        | 11.1      | 832                  | 7.30                    | 7.25 | 48      |
| 111                 | "        | 12.0      | 1021                 | 6.47                    | 7.02 | 26      |
| 112                 | "        | 12.3      | 1058                 | 5.25                    | 6.94 | 33      |
| 113                 | "        | 11.7      | 1093                 | 8.36                    | 7.02 | 43      |
|                     |          |           |                      |                         |      |         |



## FIELD DATA SUMMARY

Project: GENERAL MILLS

Project number: 23/27-169

Field Staff: KSJ

| Monitoring location | Date     | Temp (oC) | Conductivity @ 25 oC | pH   | Eh (mV) | Dissolved Oxygen (mg/L) |
|---------------------|----------|-----------|----------------------|------|---------|-------------------------|
| 11                  | 10/28/03 | 11.4      | 898                  | 6.62 | 29      | 0.17                    |
| SS                  | "        | 11.4      | 861                  | 6.77 | 19      | 0.33                    |
| TT                  | "        | 12.0      | 851                  | 6.68 | 33      | 0.12                    |
| 14                  | "        | 12.1      | 975                  | 6.96 | -18     | 0.12                    |
| 12                  | "        | 9.8       | 492                  | 8.80 | -39     | 0.79                    |
| UU                  | 10/29/03 | 11.5      | 1087                 | 6.69 | 65      | 0.14                    |
| Q                   | "        | 13.3      | 1157                 | 6.61 | 65      | 4.40                    |
| QQ                  | "        | 10.4      | 636                  | 6.87 | -21     | 1.57                    |
| T                   | "        | 13.9      | 852                  | 6.77 | 44      | 1.21                    |
| X                   | "        | 13.7      | 1193                 | 6.41 | 59      | 6.13                    |
| V                   | "        | 17.0      | 401                  | 7.47 | 27      | 0.73                    |
| W                   | "        | 14.4      | 1338                 | 6.54 | 46      | 0.73                    |
| 9                   | 10/30/03 | 12.8      | 1442                 | 7.07 | 14      | 0.34                    |
| 10                  | "        | 12.7      | 1159                 | 7.44 | -40     | 0.17                    |
| 202                 | "        | 13.0      | 612                  | 7.04 | 45      | 3.51                    |
| 200                 | "        | 6.9       | 567                  | 7.16 | 8       | 1.97                    |
| 203                 | 10/31/03 | 11.9      | 601                  | 7.40 | 24      | 4.15                    |
| Henkel              | "        | 10.7      | 490                  | 8.10 | 29      | 7.25                    |
|                     |          |           |                      |      |         |                         |
|                     |          |           |                      |      |         |                         |
|                     |          |           |                      |      |         |                         |





# Barr Engineering Company Field Log Data Sheet

|   |                  |  |             |                             |             |                 |             |                         |
|---|------------------|--|-------------|-----------------------------|-------------|-----------------|-------------|-------------------------|
| Client: <i>General Mills</i>  |                  |  |             | Monitoring Point: <i>11</i> |             |                 |             |                         |
| Location: <i>MPLS</i>   |                  |  |             | Date: <i>10-28-03</i>       |             |                 |             |                         |
| Project #: <i>23/27-169403</i>  |                  |  |             | Sample Time: <i>1000</i>    |             |                 |             |                         |
| GENERAL DATA  |                  | STABILIZATION TEST                                     |             |                             |             |                 |             |                         |
| Barr lock:  | <i>YES</i>       |  |             |                             |             |                 |             |                         |
| Casing diameter:  | <i>4</i>         | Time/<br>Volume  | Temp.<br>°C | Cond.<br>@ 25               | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>54</i>        | <i>0917/63g</i>  | <i>11.5</i> | <i>1056</i>                 | <i>6.78</i> | <i>46</i>       | <i>0.19</i> | <i>slightly cloudy</i>  |
| Static water level:*  | <i>21.76</i>     | <i>0931/84g</i>  | <i>11.5</i> | <i>962</i>                  | <i>6.68</i> | <i>36</i>       | <i>0.24</i> | <i>clear</i>            |
| Water depth:*   | <i>32.2</i>      | <i>0945/105g</i>                                       | <i>11.4</i> | <i>916</i>                  | <i>6.65</i> | <i>32</i>       | <i>0.19</i> | <i>clear</i>            |
| Well volume: (gal)  | <i>21</i>        | <i>0959/126g</i>                                       | <i>11.4</i> | <i>898</i>                  | <i>6.62</i> | <i>29</i>       | <i>0.17</i> | <i>clear</i>            |
| Purge method:   | <i>1.5" sub.</i> |  |             |                             |             |                 |             |                         |
| Sample method:  | <i>bauler</i>    |  |             |                             |             |                 |             |                         |
| Start time:   | <i>0835</i>      | Odor: <i>none detected</i>                             |             |                             |             |                 |             |                         |
| Stop time:  | <i>0959</i>      | Purge Appearance: <i>clear, slightly cloudy, clear</i> |             |                             |             |                 |             |                         |
| Duration: (minutes)   | <i>84</i>        | Sample Appearance: <i>clear</i>                        |             |                             |             |                 |             |                         |
| Rate, gpm:  | <i>1.5</i>       | Comments:  |             |                             |             |                 |             |                         |
| Volume, purged:   | <i>126 gal</i>   |  |             |                             |             |                 |             |                         |
| Duplicate collected?  | <i>-</i>         |  |             |                             |             |                 |             |                         |
| Sample collection by:   | <i>KSJ</i>       | CO2-   | Mn2-        | Fe(T)-                      | Fe2-        |                 |             |                         |
| Others present:   |                  |  |             |                             |             |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |  |             |                             |             |                 |             |                         |
| CASING & CAP:   |                  | COLLAR:  |             | LOCK:                       |             | OTHER:          |             |                         |
| MW: groundwater monitoring well   |                  | WS: water supply well                                  |             | SW: surface water           |             | SE: sediment    |             | other:                  |
| VOC- <i>2</i> semi-volatile-  |                  | general-   |             | nutrient-                   |             | cyanide-        |             | DRO- Sulfide-           |
| oil, grease-  |                  | bacteria-  |             | total metal-                |             | filtered metal- |             | methane- filter-        |
| Others:   |                  |  |             |                             |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company

## Field Log Data Sheet

|   |                  |                                 |                             |                   |             |              |             |                         |
|---|------------------|---------------------------------|-----------------------------|-------------------|-------------|--------------|-------------|-------------------------|
| Client: <i>General Mills</i>  |                  |                                 | Monitoring Point: <i>SS</i> |                   |             |              |             |                         |
| Location: <i>MPLS</i>   |                  |                                 | Date: <i>10-28-03</i>       |                   |             |              |             |                         |
| Project #: <i>23/27-169403102</i>   |                  |                                 | Sample Time: <i>1135</i>    |                   |             |              |             |                         |
| GENERAL DATA  |                  |                                 | STABILIZATION TEST          |                   |             |              |             |                         |
| Barr lock:  | <i>YES</i>       |                                 |                             |                   |             |              |             |                         |
| Casing diameter:  | <i>2"</i>        | Time/<br>Volume                 | Temp.<br>°C                 | Cond.<br>@ 25     | pH          | Eh           | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>60.5</i>      | <i>1103/11.8</i>                | <i>12.1</i>                 | <i>835</i>        | <i>6.84</i> | <i>27</i>    | <i>0.33</i> | <i>clear</i>            |
| Static water level:*  | <i>37.44</i>     | <i>1116/15g</i>                 | <i>11.5</i>                 | <i>875</i>        | <i>6.81</i> | <i>27</i>    | <i>0.24</i> | <i>clear</i>            |
| Water depth:*   | <i>23.1</i>      | <i>1129/19g</i>                 | <i>11.3</i>                 | <i>865</i>        | <i>6.79</i> | <i>23</i>    | <i>0.38</i> | <i>clear</i>            |
| Well volume: (gal)  | <i>3.8</i>       | <i>1134/22g</i>                 | <i>11.4</i>                 | <i>861</i>        | <i>6.77</i> | <i>19</i>    | <i>0.33</i> | <i>clear</i>            |
| Purge method:   | <i>1.5" sub.</i> |                                 |                             |                   |             |              |             |                         |
| Sample method:  | <i>bailler</i>   |                                 |                             |                   |             |              |             |                         |
| Start time:   | <i>1026</i>      | Odor: <i>none detected</i>      |                             |                   |             |              |             |                         |
| Stop time:  | <i>1134</i>      | Purge Appearance: <i>clear</i>  |                             |                   |             |              |             |                         |
| Duration: (minutes)   | <i>73</i>        | Sample Appearance: <i>clear</i> |                             |                   |             |              |             |                         |
| Rate, gpm:  | <i>.3</i>        | Comments:                       |                             |                   |             |              |             |                         |
| Volume, purged:   | <i>22 gal</i>    |                                 |                             |                   |             |              |             |                         |
| Duplicate collected?  | <i>-</i>         |                                 |                             |                   |             |              |             |                         |
| Sample collection by:   | <i>KSJ</i>       |                                 |                             |                   |             |              |             |                         |
|   |                  | CO2-                            | Mn2-                        | Fe(T)-            | Fe2-        |              |             |                         |
| Others present:   |                  |                                 |                             |                   |             |              |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |                                 |                             |                   |             |              |             |                         |
| CASING & CAP:   |                  | COLLAR:                         |                             | LOCK:             |             | OTHER:       |             |                         |
| MW: groundwater monitoring well   |                  | WS: water supply well           |                             | SW: surface water |             | SE: sediment |             | other:                  |
| VOC- <i>2</i>   | semi-volatile-   | general-                        | nutrient-                   | cyanide-          | DRO-        | Sulfide-     |             |                         |
| oil, grease-  | bacteria-        | total metal-                    | filtered metal-             | methane-          | filter-     |              |             |                         |
| Others:   |                  |                                 |                             |                   |             |              |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <u>General Mills</u>  |                  | Monitoring Point: <u>TT</u>     |             |                   |             |                 |             |                         |
|---|------------------|---------------------------------|-------------|-------------------|-------------|-----------------|-------------|-------------------------|
| Location: <u>MPLS</u>   |                  | Date: <u>10-28-03</u>           |             |                   |             |                 |             |                         |
| Project #: <u>23/27-169403102</u>   |                  | Sample Time: <u>1240</u>        |             |                   |             |                 |             |                         |
| GENERAL DATA  |                  | STABILIZATION TEST              |             |                   |             |                 |             |                         |
| Barr lock:  | <u>YES</u>       |                                 |             |                   |             |                 |             |                         |
| Casing diameter:  | <u>2"</u>        | Time/<br>Volume                 | Temp.<br>°C | Cond.<br>@ 25     | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <u>70</u>        | <u>1207/12g.</u>                | <u>12.1</u> | <u>930</u>        | <u>6.72</u> | <u>27</u>       | <u>0.19</u> | <u>clear</u>            |
| Static water level:*  | <u>44.78</u>     | <u>1227/16g.</u>                | <u>11.9</u> | <u>878</u>        | <u>6.71</u> | <u>31</u>       | <u>0.15</u> | <u>clear</u>            |
| Water depth:*   | <u>25.2</u>      | <u>1237/20g.</u>                | <u>12.0</u> | <u>851</u>        | <u>6.68</u> | <u>33</u>       | <u>0.12</u> | <u>clear</u>            |
| Well volume: (gal)  | <u>4</u>         |                                 |             |                   |             |                 |             |                         |
| Purge method:   | <u>1.5" sub.</u> |                                 |             |                   |             |                 |             |                         |
| Sample method:  | <u>bailer</u>    |                                 |             |                   |             |                 |             |                         |
| Start time:   | <u>1147</u>      | Odor: <u>none detected</u>      |             |                   |             |                 |             |                         |
| Stop time:  | <u>1237</u>      | Purge Appearance: <u>clear</u>  |             |                   |             |                 |             |                         |
| Duration: (minutes)   | <u>50</u>        | Sample Appearance: <u>clear</u> |             |                   |             |                 |             |                         |
| Rate, gpm:  | <u>.4</u>        | Comments:                       |             |                   |             |                 |             |                         |
| Volume, purged:   | <u>20 gal</u>    |                                 |             |                   |             |                 |             |                         |
| Duplicate collected?  | <u>-</u>         |                                 |             |                   |             |                 |             |                         |
| Sample collection by:   | <u>KSJ</u>       | CO2-                            | Mn2-        | Fe(T)-            | Fe2-        |                 |             |                         |
| Others present:   |                  |                                 |             |                   |             |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |                                 |             |                   |             |                 |             |                         |
| CASING & CAP:   |                  | COLLAR:                         |             | LOCK:             |             | OTHER:          |             |                         |
| MW: groundwater monitoring well   |                  | WS: water supply well           |             | SW: surface water |             | SE: sediment    |             | other:                  |
| VOC- <u>2</u> semi-volatile-  |                  | general-                        |             | nutrient-         |             | cyanide-        |             | DRO- Sulfide-           |
| oil, grease-  |                  | bacteria-                       |             | total metal-      |             | filtered metal- |             | methane- filter-        |
| Others:   |                  |                                 |             |                   |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                  | Monitoring Point: <i>14</i>     |             |                   |             |                 |             |                         |
|---|------------------|---------------------------------|-------------|-------------------|-------------|-----------------|-------------|-------------------------|
| Location: <i>MPLS</i>   |                  | Date: <i>10-28-03</i>           |             |                   |             |                 |             |                         |
| Project #: <i>23/27-169403102</i>   |                  | Sample Time: <i>1435</i>        |             |                   |             |                 |             |                         |
| GENERAL DATA  |                  | STABILIZATION TEST              |             |                   |             |                 |             |                         |
| Barr lock:  | <i>YES</i>       |                                 |             |                   |             |                 |             |                         |
| Casing diameter:  | <i>2"</i>        | Time/<br>Volume                 | Temp.<br>°C | Cond.<br>@ 25     | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>68.5</i>      | <i>1353/12g</i>                 | <i>12.1</i> | <i>985</i>        | <i>7.40</i> | <i>-54</i>      | <i>0.34</i> | <i>clear</i>            |
| Static water level:*  | <i>42.03</i>     | <i>1406/16g</i>                 | <i>12.0</i> | <i>986</i>        | <i>7.19</i> | <i>-31</i>      | <i>0.37</i> | <i>"</i>                |
| Water depth:*   | <i>26.5</i>      | <i>1440/20g</i>                 | <i>12.0</i> | <i>981</i>        | <i>7.11</i> | <i>-24</i>      | <i>0.25</i> | <i>"</i>                |
| Well volume: (gal)  | <i>4</i>         | <i>1417/24g</i>                 | <i>12.1</i> | <i>975</i>        | <i>7.05</i> | <i>-20</i>      | <i>0.21</i> | <i>"</i>                |
| Purge method:   | <i>1.5" sub.</i> | <i>1423/28g</i>                 | <i>12.1</i> | <i>978</i>        | <i>6.99</i> | <i>-22</i>      | <i>0.17</i> | <i>"</i>                |
| Sample method:  | <i>Dailer</i>    | <i>1433/32g</i>                 | <i>12.1</i> | <i>975</i>        | <i>6.96</i> | <i>-18</i>      | <i>0.12</i> | <i>"</i>                |
| Start time:   | <i>1313</i>      | Odor: <i>None detected</i>      |             |                   |             |                 |             |                         |
| Stop time:  | <i>1433</i>      | Purge Appearance: <i>clear</i>  |             |                   |             |                 |             |                         |
| Duration: (minutes)   | <i>80</i>        | Sample Appearance: <i>clear</i> |             |                   |             |                 |             |                         |
| Rate, gpm:  | <i>3.4</i>       | Comments:                       |             |                   |             |                 |             |                         |
| Volume, purged:   | <i>32 gal</i>    |                                 |             |                   |             |                 |             |                         |
| Duplicate collected?  | <i>-</i>         |                                 |             |                   |             |                 |             |                         |
| Sample collection by:   | <i>KSJ</i>       |                                 |             |                   |             |                 |             |                         |
|   |                  | CO2-                            | Mn2-        | Fe(T)-            | Fe2-        |                 |             |                         |
| Others present:   |                  |                                 |             |                   |             |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |                                 |             |                   |             |                 |             |                         |
| CASING & CAP:   |                  | COLLAR:                         |             | LOCK:             |             | OTHER:          |             |                         |
| MW: groundwater monitoring well   |                  | WS: water supply well           |             | SW: surface water |             | SE: sediment    |             | other:                  |
| VOC- <i>2</i> semi-volatile-  |                  | general-                        |             | nutrient-         |             | cyanide-        |             | DRO- Sulfide-           |
| oil, grease-  |                  | bacteria-                       |             | total metal-      |             | filtered metal- |             | methane- filter-        |
| Others:   |                  |                                 |             |                   |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                  |  |                 | Monitoring Point: <i>12</i> |             |              |             |                         |
|---|------------------|--|-----------------|-----------------------------|-------------|--------------|-------------|-------------------------|
| Location: <i>MPLS</i>   |                  |  |                 | Date: <i>10-28-03</i>       |             |              |             |                         |
| Project #: <i>23/27-169 Y03102</i>  |                  |  |                 | Sample Time: <i>1735</i>    |             |              |             |                         |
| GENERAL DATA  |                  | STABILIZATION TEST                               |                 |                             |             |              |             |                         |
| Barr lock:  | <i>YES</i>       |  |                 |                             |             |              |             |                         |
| Casing diameter:  | <i>4</i>         | Time/<br>Volume                                  | Temp:<br>°C     | Cond.<br>@ 25               | pH          | Eh           | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>63</i>        | <i>1532/80g</i>                                  | <i>9.4</i>      | <i>499</i>                  | <i>8.71</i> | <i>-10</i>   | <i>1.23</i> | <i>clear</i>            |
| Static water level:*  | <i>35.68</i>     | <i>1632/80g</i>                                  | <i>9.6</i>      | <i>495</i>                  | <i>8.77</i> | <i>-23</i>   | <i>.97</i>  | <i>slightly cloudy</i>  |
| Water depth:*   | <i>27.3</i>      | <i>1732/160g</i>                                 | <i>9.8</i>      | <i>492</i>                  | <i>8.80</i> | <i>-39</i>   | <i>.79</i>  | <i>"</i>                |
| Well volume: (gal)  | <i>21</i>        |  |                 |                             |             |              |             |                         |
| Purge method:   | <i>1.5" sub.</i> |  |                 |                             |             |              |             |                         |
| Sample method:  | <i>bailer</i>    |  |                 |                             |             |              |             |                         |
| Start time:   | <i>1452</i>      | Odor: <i>none detected</i>                       |                 |                             |             |              |             |                         |
| Stop time:  | <i>1732</i>      | Purge Appearance: <i>clear - slightly cloudy</i> |                 |                             |             |              |             |                         |
| Duration: (minutes)   | <i>160</i>       | Sample Appearance: <i>slightly cloudy</i>        |                 |                             |             |              |             |                         |
| Rate, gpm:  | <i>1 → .1</i>    | Comments:  |                 |                             |             |              |             |                         |
| Volume, purged:   | <i>100 gal</i>   |  |                 |                             |             |              |             |                         |
| Duplicate collected?  | <i>-</i>         |  |                 |                             |             |              |             |                         |
| Sample collection by:   | <i>KSJ</i>       |  |                 |                             |             |              |             |                         |
|   |                  | CO2-   | Mn2-            | Fe(T)-                      | Fe2-        |              |             |                         |
| Others present:   |                  |  |                 |                             |             |              |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |  |                 |                             |             |              |             |                         |
| CASING & CAP:   |                  | COLLAR:  |                 | LOCK:                       |             | OTHER:       |             |                         |
| M/W: groundwater monitoring well  |                  | WS: water supply well                            |                 | SW: surface water           |             | SE: sediment |             | other:                  |
| VOC- <i>2</i>   | semi-volatile-   | general-   | nutrient-       | cyanide-                    | DRO-        | Sulfide-     |             |                         |
| oil, grease-  | bacteria-        | total metal-                                     | filtered metal- | methane-                    | filter-     |              |             |                         |
| Others:   |                  |  |                 |                             |             |              |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <u>General Mills</u>  |                           | Monitoring Point: <u>KK</u>     |             |                   |             |                 |             |                         |
|---|---------------------------|---------------------------------|-------------|-------------------|-------------|-----------------|-------------|-------------------------|
| Location: <u>MPLS</u>   |                           | Date: <u>10-29-03</u>           |             |                   |             |                 |             |                         |
| Project #: <u>23/27-169403102</u>   |                           | Sample Time: <u>0915</u>        |             |                   |             |                 |             |                         |
| GENERAL DATA  |                           | STABILIZATION TEST              |             |                   |             |                 |             |                         |
| Barr lock:  | <u>YES</u>                |                                 |             |                   |             |                 |             |                         |
| Casing diameter:  | <u>2"</u>                 | Time/<br>Volume                 | Temp.<br>°C | Cond.<br>@ 25     | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <u>63.'</u>               | <u>0840/15g</u>                 | <u>11.4</u> | <u>1328</u>       | <u>6.86</u> | <u>79</u>       | <u>0.19</u> | <u>clear</u>            |
| Static water level:*  | <u>32.89</u>              | <u>0850/20g</u>                 | <u>11.4</u> | <u>1182</u>       | <u>6.79</u> | <u>72</u>       | <u>0.25</u> | <u>clear</u>            |
| Water depth:*   | <u>30</u>                 | <u>0900/25g</u>                 | <u>11.5</u> | <u>1103</u>       | <u>6.73</u> | <u>68</u>       | <u>0.16</u> | <u>clear</u>            |
| Well volume: (gal)  | <u>5</u>                  | <u>0910/30g</u>                 | <u>11.5</u> | <u>1087</u>       | <u>6.69</u> | <u>65</u>       | <u>0.14</u> | <u>clear</u>            |
| Purge method:   | <u>1.5" sub.<br/>0810</u> |                                 |             |                   |             |                 |             |                         |
| Sample method:  | <u>bailer</u>             |                                 |             |                   |             |                 |             |                         |
| Start time:   | <u>0810</u>               | Odor: <u>none detected</u>      |             |                   |             |                 |             |                         |
| Stop time:  | <u>0910</u>               | Purge Appearance: <u>clear</u>  |             |                   |             |                 |             |                         |
| Duration: (minutes)   | <u>60</u>                 | Sample Appearance: <u>clear</u> |             |                   |             |                 |             |                         |
| Rate, gpm:  | <u>.5</u>                 | Comments:                       |             |                   |             |                 |             |                         |
| Volume, purged:   | <u>30 gal</u>             |                                 |             |                   |             |                 |             |                         |
| Duplicate collected?  | <u>-</u>                  |                                 |             |                   |             |                 |             |                         |
| Sample collection by:   | <u>KSJ</u>                |                                 |             |                   |             |                 |             |                         |
|   |                           | CO2-                            | Mn2-        | Fe(T)-            | Fe2-        |                 |             |                         |
| Others present:   |                           |                                 |             |                   |             |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                           |                                 |             |                   |             |                 |             |                         |
| CASING & CAP:   |                           | COLLAR:                         |             | LOCK:             |             | OTHER:          |             |                         |
| MW: groundwater monitoring well   |                           | WS: water supply well           |             | SW: surface water |             | SE: sediment    |             | other:                  |
| VOC- <u>2</u> semi-volatile-  |                           | general-                        |             | nutrient-         |             | cyanide-        |             | DRO- Sulfide-           |
| oil, grease-  |                           | bacteria-                       |             | total metal-      |             | filtered metal- |             | methane- filter-        |
| Others:   |                           |                                 |             |                   |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                 |   |                 | Monitoring Point: <i>Q</i> |             |              |             |                         |
|---|-----------------|---|-----------------|----------------------------|-------------|--------------|-------------|-------------------------|
| Location: <i>MPLS</i>   |                 |   |                 | Date: <i>10-29-03</i>      |             |              |             |                         |
| Project #: <i>23/27-169403102</i>   |                 |   |                 | Sample Time: <i>0950</i>   |             |              |             |                         |
| GENERAL DATA  |                 | STABILIZATION TEST  |                 |                            |             |              |             |                         |
| Barr lock:  | <i>YES</i>      |   |                 |                            |             |              |             |                         |
| Casing diameter:  | <i>2"</i>       | Time/<br>Volume   | Temp.<br>°C     | Cond.<br>@ 25              | pH          | Eh           | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>25.5</i>     | <i>0936/1.5g</i>  | <i>13.0</i>     | <i>1172</i>                | <i>6.75</i> | <i>90</i>    | <i>6.68</i> | <i>slightly cloudy</i>  |
| Static water level:*  | <i>22.20</i>    | <i>0938/2g</i>  | <i>13.1</i>     | <i>1168</i>                | <i>6.69</i> | <i>74</i>    | <i>5.08</i> | <i>clearing</i>         |
| Water depth:*   | <i>3.3</i>      | <i>0940/2.5g</i>  | <i>13.2</i>     | <i>1165</i>                | <i>6.65</i> | <i>68</i>    | <i>4.81</i> | <i>clear</i>            |
| Well volume: (gal)  | <i>.5</i>       | <i>0942/3g</i>  | <i>13.3</i>     | <i>1161</i>                | <i>6.63</i> | <i>69</i>    | <i>4.59</i> | <i>clear</i>            |
| Purge method:   | <i>1.5" sub</i> | <i>0944/3.5g</i>  | <i>13.3</i>     | <i>1157</i>                | <i>6.61</i> | <i>65</i>    | <i>4.40</i> | <i>clear</i>            |
| Sample method:  | <i>bailer</i>   |   |                 |                            |             |              |             |                         |
| Start time:   | <i>0928</i>     | Odor: <i>none detected</i>                                  |                 |                            |             |              |             |                         |
| Stop time:  | <i>0944</i>     | Purge Appearance: <i>begin - cloudy brown / end - clear</i> |                 |                            |             |              |             |                         |
| Duration: (minutes)   | <i>16</i>       | Sample Appearance: <i>clear</i>                             |                 |                            |             |              |             |                         |
| Rate, gpm:  | <i>.2</i>       | Comments:   |                 |                            |             |              |             |                         |
| Volume, purged:   | <i>3.5 gal</i>  |   |                 |                            |             |              |             |                         |
| Duplicate collected?  | <i>-</i>        |   |                 |                            |             |              |             |                         |
| Sample collection by:   | <i>KSS</i>      |   |                 |                            |             |              |             |                         |
|   |                 | CO2-  | Mn2-            | Fe(T)-                     | Fe2-        |              |             |                         |
| Others present:   |                 |   |                 |                            |             |              |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                 |   |                 |                            |             |              |             |                         |
| CASING & CAP:   |                 | COLLAR:   |                 | LOCK:                      |             | OTHER:       |             |                         |
| MW: groundwater monitoring well   |                 | WS: water supply well                                       |                 | SW: surface water          |             | SE: sediment |             | other:                  |
| VOC- <i>2</i>   | semi-volatile-  | general-  | nutrient-       | cyanide-                   | DRO-        | Sulfide-     |             |                         |
| oil, grease-  | bacteria-       | total metal-  | filtered metal- | methane-                   | filter-     |              |             |                         |
| Others:   |                 |   |                 |                            |             |              |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                    | Monitoring Point: <i>Q Q</i>    |             |                   |             |                 |             |                         |
|---|--------------------|---------------------------------|-------------|-------------------|-------------|-----------------|-------------|-------------------------|
| Location: <i>MPS</i>  |                    | Date: <i>10-29-03</i>           |             |                   |             |                 |             |                         |
| Project #: <i>23/27-169403102</i>   |                    | Sample Time: <i>1130</i>        |             |                   |             |                 |             |                         |
| GENERAL DATA  |                    | STABILIZATION TEST              |             |                   |             |                 |             |                         |
| Barr lock:  | <i>Yes</i>         |                                 |             |                   |             |                 |             |                         |
| Casing diameter:  | <i>1.25"</i>       | Time/<br>Volume                 | Temp.<br>°C | Cond.<br>@ 25     | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>59.5</i>        | <i>1059/7g</i>                  | <i>10.3</i> | <i>570</i>        | <i>6.93</i> | <i>-11</i>      | <i>1.69</i> | <i>clear</i>            |
| Static water level:*  | <i>28.31</i>       | <i>1112/9g</i>                  | <i>10.4</i> | <i>612</i>        | <i>6.91</i> | <i>-16</i>      | <i>1.62</i> | <i>"</i>                |
| Water depth:*   | <i>31.2</i>        | <i>1125/11g</i>                 | <i>10.4</i> | <i>636</i>        | <i>6.87</i> | <i>-21</i>      | <i>1.57</i> | <i>"</i>                |
| Well volume: (gal)  | <i>2.3</i>         |                                 |             |                   |             |                 |             |                         |
| Purge method:   | <i>Peristaltic</i> |                                 |             |                   |             |                 |             |                         |
| Sample method:  | <i>Peristaltic</i> |                                 |             |                   |             |                 |             |                         |
| Start time:   | <i>1012</i>        | Odor: <i>none detected</i>      |             |                   |             |                 |             |                         |
| Stop time:  | <i>1125</i>        | Purge Appearance: <i>clear</i>  |             |                   |             |                 |             |                         |
| Duration: (minutes)   | <i>73</i>          | Sample Appearance: <i>clear</i> |             |                   |             |                 |             |                         |
| Rate, gpm:  | <i>.15</i>         | Comments:                       |             |                   |             |                 |             |                         |
| Volume, purged:   | <i>11 gal</i>      |                                 |             |                   |             |                 |             |                         |
| Duplicate collected?  | <i>-</i>           |                                 |             |                   |             |                 |             |                         |
| Sample collection by:   | <i>KSJ</i>         |                                 |             |                   |             |                 |             |                         |
|   |                    | CO2-                            | Mn2-        | Fe(T)-            | Fe2-        |                 |             |                         |
| Others present:   |                    |                                 |             |                   |             |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                    |                                 |             |                   |             |                 |             |                         |
| CASING & CAP:   |                    | COLLAR:                         |             | LOCK:             |             | OTHER:          |             |                         |
| MW: groundwater monitoring well   |                    | WS: water supply well           |             | SW: surface water |             | SE: sediment    |             | other:                  |
| VOC- <i>2</i> semi-volatile-  |                    | general-                        |             | nutrient-         |             | cyanide-        |             | DRO- Sulfide-           |
| oil, grease-  |                    | bacteria-                       |             | total metal-      |             | filtered metal- |             | methane- filter-        |
| Others:   |                    |                                 |             |                   |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                    |                                 |             | Monitoring Point: <i>T</i> |             |                 |             |                         |
|---|--------------------|---------------------------------|-------------|----------------------------|-------------|-----------------|-------------|-------------------------|
| Location: <i>MPLS</i>   |                    |                                 |             | Date: <i>10-29-03</i>      |             |                 |             |                         |
| Project #: <i>23/27-169403102</i>   |                    |                                 |             | Sample Time: <i>1245</i>   |             |                 |             |                         |
| GENERAL DATA  |                    | STABILIZATION TEST              |             |                            |             |                 |             |                         |
| Barr lock:  | <i>YES</i>         |                                 |             |                            |             |                 |             |                         |
| Casing diameter:  | <i>2"</i>          | Time/<br>Volume                 | Temp.<br>°C | Cond.<br>@ 25              | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>24.0</i>        | <i>1218/4g</i>                  | <i>14.1</i> | <i>835</i>                 | <i>6.91</i> | <i>38</i>       | <i>3.91</i> | <i>clear</i>            |
| Static water level:*  | <i>16.86</i>       | <i>1223/5g</i>                  | <i>14.0</i> | <i>839</i>                 | <i>6.85</i> | <i>42</i>       | <i>2.72</i> | <i>clear</i>            |
| Water depth:*   | <i>7</i>           | <i>1228/6g</i>                  | <i>13.9</i> | <i>843</i>                 | <i>6.80</i> | <i>41</i>       | <i>2.14</i> | <i>clear</i>            |
| Well volume: (gal)  | <i>1.2</i>         | <i>1233/7g</i>                  | <i>13.8</i> | <i>845</i>                 | <i>6.77</i> | <i>42</i>       | <i>1.61</i> | <i>clear</i>            |
| Purge method:   | <i>Peristaltic</i> | <i>1238/8g</i>                  | <i>13.8</i> | <i>846</i>                 | <i>6.75</i> | <i>43</i>       | <i>1.32</i> | <i>clear</i>            |
| Sample method:  | <i>Peristaltic</i> | <i>1243/9g</i>                  | <i>13.9</i> | <i>852</i>                 | <i>6.77</i> | <i>44</i>       | <i>1.21</i> | <i>clear</i>            |
| Start time:   | <i>1158</i>        | Odor: <i>none detected</i>      |             |                            |             |                 |             |                         |
| Stop time:  | <i>1243</i>        | Purge Appearance: <i>clear</i>  |             |                            |             |                 |             |                         |
| Duration: (minutes)   | <i>45</i>          | Sample Appearance: <i>clear</i> |             |                            |             |                 |             |                         |
| Rate, gpm:  | <i>.2</i>          | Comments:                       |             |                            |             |                 |             |                         |
| Volume, purged:   | <i>9 gal</i>       |                                 |             |                            |             |                 |             |                         |
| Duplicate collected?  | <i>-</i>           |                                 |             |                            |             |                 |             |                         |
| Sample collection by:   | <i>KSJ</i>         |                                 |             |                            |             |                 |             |                         |
|   |                    | CO2-                            | Mn2-        | Fe(T)-                     | Fe2-        |                 |             |                         |
| Others present:   |                    |                                 |             |                            |             |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                    |                                 |             |                            |             |                 |             |                         |
| CASING & CAP:   |                    | COLLAR:                         |             | LOCK:                      |             | OTHER:          |             |                         |
| MW: groundwater monitoring well   |                    | WS: water supply well           |             | SW: surface water          |             | SE: sediment    |             | other:                  |
| VOC- <i>2</i> semi-volatile-  |                    | general-                        |             | nutrient-                  |             | cyanide-        |             | DRO- Sulfide-           |
| oil,grease-   |                    | bacteria-                       |             | total metal-               |             | filtered metal- |             | methane- filter-        |
| Others:   |                    |                                 |             |                            |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                    |   |                 | Monitoring Point: <i>X</i> |             |              |             |                         |
|---|--------------------|---|-----------------|----------------------------|-------------|--------------|-------------|-------------------------|
| Location: <i>MPLS</i>   |                    |   |                 | Date: <i>10-29-03</i>      |             |              |             |                         |
| Project #: <i>23/27-169403102</i>   |                    |   |                 | Sample Time: <i>1335</i>   |             |              |             |                         |
| GENERAL DATA  |                    | STABILIZATION TEST                                      |                 |                            |             |              |             |                         |
| Barr lock:  | <i>YES</i>         |   |                 |                            |             |              |             |                         |
| Casing diameter:  | <i>2"</i>          | Time/<br>Volume   | Temp.<br>°C     | Cond.<br>@ 25              | pH          | Eh           | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>21.0</i>        | <i>1315 / 1.6</i>                                       | <i>13.3</i>     | <i>1164</i>                | <i>6.53</i> | <i>49</i>    | <i>7.28</i> | <i>slightly cloudy</i>  |
| Static water level:*  | <i>19.83</i>       | <i>1319 / .85</i>                                       | <i>13.4</i>     | <i>1177</i>                | <i>6.46</i> | <i>52</i>    | <i>6.34</i> | <i>clearing</i>         |
| Water depth:*   | <i>1.2</i>         | <i>1323 / 1.9</i>                                       | <i>13.5</i>     | <i>1184</i>                | <i>6.42</i> | <i>54</i>    | <i>6.24</i> | <i>"</i>                |
| Well volume: (gal)  | <i>.2</i>          | <i>1327 / 1.25</i>                                      | <i>13.6</i>     | <i>1189</i>                | <i>6.40</i> | <i>56</i>    | <i>6.17</i> | <i>clear</i>            |
| Purge method:   | <i>Peristaltic</i> | <i>1331 / 1.45</i>                                      | <i>13.7</i>     | <i>1193</i>                | <i>6.41</i> | <i>59</i>    | <i>6.13</i> | <i>clear</i>            |
| Sample method:  | <i>Peristaltic</i> |   |                 |                            |             |              |             |                         |
| Start time:   | <i>1303</i>        | Odor: <i>none detected</i>                              |                 |                            |             |              |             |                         |
| Stop time:  | <i>1331</i>        | Purge Appearance: <i>begin- cloudy brown/end- clear</i> |                 |                            |             |              |             |                         |
| Duration: (minutes)   | <i>28</i>          | Sample Appearance: <i>clear</i>                         |                 |                            |             |              |             |                         |
| Rate, gpm:  | <i>2.1</i>         | Comments:   |                 |                            |             |              |             |                         |
| Volume, purged:   | <i>1.4 gal</i>     |   |                 |                            |             |              |             |                         |
| Duplicate collected?  | <i>-</i>           |   |                 |                            |             |              |             |                         |
| Sample collection by:   | <i>KSS</i>         |   |                 |                            |             |              |             |                         |
|   |                    | CO2-  | Mn2-            | Fe(T)-                     | Fe2-        |              |             |                         |
| Others present:   |                    |   |                 |                            |             |              |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                    |   |                 |                            |             |              |             |                         |
| CASING & CAP:   |                    | COLLAR:   |                 | LOCK:                      |             | OTHER:       |             |                         |
| MW: groundwater monitoring well   |                    | WS: water supply well                                   |                 | SW: surface water          |             | SE: sediment |             | other:                  |
| VOC- <i>2</i>   | semi-volatile-     | general-  | nutrient-       | cyanide-                   | DRO-        | Sulfide-     |             |                         |
| oil, grease-  | bacteria-          | total metal-  | filtered metal- | methane-                   | filter-     |              |             |                         |
| Others:   |                    |   |                 |                            |             |              |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company

## Field Log Data Sheet

| Client: <u>General Mills</u>  |                    | Monitoring Point: <u>✓</u>      |             |                   |             |                 |             |                         |
|---|--------------------|---------------------------------|-------------|-------------------|-------------|-----------------|-------------|-------------------------|
| Location: <u>MPLS</u>   |                    | Date: <u>10-29-03</u>           |             |                   |             |                 |             |                         |
| Project #: <u>23/27-169403102</u>   |                    | Sample Time: <u>1515</u>        |             |                   |             |                 |             |                         |
| GENERAL DATA  |                    | STABILIZATION TEST              |             |                   |             |                 |             |                         |
| Barr lock:  | <u>YES</u>         |                                 |             |                   |             |                 |             |                         |
| Casing diameter:  | <u>2"</u>          | Time/<br>Volume                 | Temp.<br>°C | Cond.<br>@ 25     | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <u>27.5</u>        | <u>1432/3g</u>                  | <u>17.3</u> | <u>410</u>        | <u>7.54</u> | <u>21</u>       | <u>1.64</u> | <u>clear</u>            |
| Static water level:*  | <u>20.57</u>       | <u>1442/4g</u>                  | <u>17.2</u> | <u>406</u>        | <u>7.51</u> | <u>24</u>       | <u>.82</u>  | <u>clear</u>            |
| Water depth:*   | <u>6.9</u>         | <u>1502/6g</u>                  | <u>17.1</u> | <u>403</u>        | <u>7.50</u> | <u>26</u>       | <u>.75</u>  | <u>clear</u>            |
| Well volume: (gal)  | <u>1.1</u>         | <u>1512/7g</u>                  | <u>17.0</u> | <u>401</u>        | <u>7.47</u> | <u>27</u>       | <u>.73</u>  | <u>clear</u>            |
| Purge method:   | <u>Peristaltic</u> |                                 |             |                   |             |                 |             |                         |
| Sample method:  | <u>Peristaltic</u> |                                 |             |                   |             |                 |             |                         |
| Start time:   | <u>1402</u>        | Odor: <u>none detected</u>      |             |                   |             |                 |             |                         |
| Stop time:  | <u>1512</u>        | Purge Appearance: <u>clear</u>  |             |                   |             |                 |             |                         |
| Duration: (minutes)   | <u>70</u>          | Sample Appearance: <u>clear</u> |             |                   |             |                 |             |                         |
| Rate, gpm:  | <u>.1</u>          | Comments:                       |             |                   |             |                 |             |                         |
| Volume, purged:   | <u>7 gal</u>       |                                 |             |                   |             |                 |             |                         |
| Duplicate collected?  | <u>-</u>           |                                 |             |                   |             |                 |             |                         |
| Sample collection by:   | <u>KSJ</u>         |                                 |             |                   |             |                 |             |                         |
| Others present:   |                    | CO2-                            | Mn2-        | Fe(T)-            | Fe2-        |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                    |                                 |             |                   |             |                 |             |                         |
| CASING & CAP:   |                    | COLLAR:                         |             | LOCK:             |             | OTHER:          |             |                         |
| MW: groundwater monitoring well   |                    | WS: water supply well           |             | SW: surface water |             | SE: sediment    |             | other:                  |
| VOC- <u>2</u> semi-volatile-  |                    | general-                        |             | nutrient-         |             | cyanide-        |             | DRO- Sulfide-           |
| oil, grease-  |                    | bacteria-                       |             | total metal-      |             | filtered metal- |             | methane- filter-        |
| Others:   |                    |                                 |             |                   |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                    | Monitoring Point: <i>W</i>      |             |                   |             |                 |             |                         |
|---|--------------------|---------------------------------|-------------|-------------------|-------------|-----------------|-------------|-------------------------|
| Location: <i>MPLS</i>   |                    | Date: <i>10-29-03</i>           |             |                   |             |                 |             |                         |
| Project #: <i>23/27-169403102</i>   |                    | Sample Time: <i>1630</i>        |             |                   |             |                 |             |                         |
| GENERAL DATA  |                    | STABILIZATION TEST              |             |                   |             |                 |             |                         |
| Barr lock:  | <i>YES</i>         |                                 |             |                   |             |                 |             |                         |
| Casing diameter:  | <i>2"</i>          | Time/<br>Volume                 | Temp.<br>°C | Cond.<br>@ 25     | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>19.0</i>        | <i>1607/3g</i>                  | <i>14.5</i> | <i>1353</i>       | <i>6.61</i> | <i>40</i>       | <i>0.97</i> | <i>clear</i>            |
| Static water level:*  | <i>12.81</i>       | <i>1617/4g</i>                  | <i>14.4</i> | <i>1344</i>       | <i>6.57</i> | <i>44</i>       | <i>0.77</i> | <i>clear</i>            |
| Water depth:*   | <i>6.2</i>         | <i>1627/5g</i>                  | <i>14.4</i> | <i>1338</i>       | <i>6.54</i> | <i>46</i>       | <i>0.73</i> | <i>clear</i>            |
| Well volume: (gal)  | <i>1</i>           |                                 |             |                   |             |                 |             |                         |
| Purge method:   | <i>Peristaltic</i> |                                 |             |                   |             |                 |             |                         |
| Sample method:  | <i>Peristaltic</i> |                                 |             |                   |             |                 |             |                         |
| Start time:   | <i>1537</i>        | Odor: <i>none detected</i>      |             |                   |             |                 |             |                         |
| Stop time:  | <i>1627</i>        | Purge Appearance: <i>clear</i>  |             |                   |             |                 |             |                         |
| Duration: (minutes)   | <i>50</i>          | Sample Appearance: <i>clear</i> |             |                   |             |                 |             |                         |
| Rate, gpm:  | <i>.1</i>          | Comments:                       |             |                   |             |                 |             |                         |
| Volume, purged:   | <i>5 gal</i>       |                                 |             |                   |             |                 |             |                         |
| Duplicate collected?  | <i>—</i>           |                                 |             |                   |             |                 |             |                         |
| Sample collection by:   | <i>KSS</i>         | CO2-                            | Mn2-        | Fe(T)-            | Fe2-        |                 |             |                         |
| Others present:   |                    |                                 |             |                   |             |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                    |                                 |             |                   |             |                 |             |                         |
| CASING & CAP:   |                    | COLLAR:                         |             | LOCK:             |             | OTHER:          |             |                         |
| MW: groundwater monitoring well   |                    | WS: water supply well           |             | SW: surface water |             | SE: sediment    |             | other:                  |
| VOC- <i>2</i> semi-volatile-  |                    | general-                        |             | nutrient-         |             | cyanide-        |             | DRO- Sulfide-           |
| oil, grease-  |                    | bacteria-                       |             | total metal-      |             | filtered metal- |             | methane- filter-        |
| Others:   |                    |                                 |             |                   |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                  |                                 |             | Monitoring Point: <i>9</i> |             |                 |             |                         |
|---|------------------|---------------------------------|-------------|----------------------------|-------------|-----------------|-------------|-------------------------|
| Location: <i>MPLS</i>   |                  |                                 |             | Date: <i>10-30-03</i>      |             |                 |             |                         |
| Project #: <i>23/27-169403102</i>   |                  |                                 |             | Sample Time: <i>0930</i>   |             |                 |             |                         |
| GENERAL DATA  |                  | STABILIZATION TEST              |             |                            |             |                 |             |                         |
| Barr lock:  | <i>YES</i>       |                                 |             |                            |             |                 |             |                         |
| Casing diameter:  | <i>4"</i>        | Time/<br>Volume                 | Temp.<br>°C | Cond.<br>@ 25              | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>63.0</i>      | <i>0856/62g</i>                 | <i>12.8</i> | <i>1350</i>                | <i>7.35</i> | <i>35</i>       | <i>1.32</i> | <i>clear</i>            |
| Static water level:*  | <i>31.21</i>     | <i>0903/83g</i>                 | <i>12.9</i> | <i>1394</i>                | <i>7.24</i> | <i>21</i>       | <i>1.01</i> | <i>clear</i>            |
| Water depth:*   | <i>31.8</i>      | <i>0910/104g</i>                | <i>12.8</i> | <i>1421</i>                | <i>7.17</i> | <i>20</i>       | <i>0.70</i> | <i>clear</i>            |
| Well volume: (gal)  | <i>21</i>        | <i>0917/125g</i>                | <i>12.8</i> | <i>1437</i>                | <i>7.12</i> | <i>17</i>       | <i>0.49</i> | <i>clear</i>            |
| Purge method:   | <i>Dedicated</i> | <i>0924/146g</i>                | <i>12.8</i> | <i>1442</i>                | <i>7.07</i> | <i>14</i>       | <i>0.34</i> | <i>clear</i>            |
| Sample method:  | <i>Grab</i>      |                                 |             |                            |             |                 |             |                         |
| Start time:   | <i>0835</i>      | Odor: <i>none detected</i>      |             |                            |             |                 |             |                         |
| Stop time:  | <i>0924</i>      | Purge Appearance: <i>clear</i>  |             |                            |             |                 |             |                         |
| Duration: (minutes)   | <i>51</i>        | Sample Appearance: <i>clear</i> |             |                            |             |                 |             |                         |
| Rate, gpm:  | <i>3</i>         | Comments:                       |             |                            |             |                 |             |                         |
| Volume, purged:   | <i>146 gal</i>   |                                 |             |                            |             |                 |             |                         |
| Duplicate collected?  | <i>-</i>         |                                 |             |                            |             |                 |             |                         |
| Sample collection by:   | <i>KSJ</i>       |                                 |             |                            |             |                 |             |                         |
|   |                  | CO2-                            | Mn2-        | Fe(T)-                     | Fe2-        |                 |             |                         |
| Others present:   |                  |                                 |             |                            |             |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |                                 |             |                            |             |                 |             |                         |
| CASING & CAP:   |                  | COLLAR:                         |             | LOCK:                      |             | OTHER:          |             |                         |
| MW: groundwater monitoring well   |                  | WS: water supply well           |             | SW: surface water          |             | SE: sediment    |             | other:                  |
| VOC- <i>2</i> semi-volatile-  |                  | general-                        |             | nutrient-                  |             | cyanide-        |             | DRO- Sulfide-           |
| oil, grease-  |                  | bacteria-                       |             | total metal-               |             | filtered metal- |             | methane- filter-        |
| Others:   |                  |                                 |             |                            |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                  |                                 | Monitoring Point: <i>10</i> |                   |             |              |            |                         |
|---|------------------|---------------------------------|-----------------------------|-------------------|-------------|--------------|------------|-------------------------|
| Location: <i>MPLS</i>   |                  |                                 | Date: <i>10-30-03</i>       |                   |             |              |            |                         |
| Project #: <i>23/27-169403 102</i>  |                  |                                 | Sample Time: <i>1455</i>    |                   |             |              |            |                         |
| GENERAL DATA  |                  | STABILIZATION TEST              |                             |                   |             |              |            |                         |
| Barr lock:  | <i>YES</i>       |                                 |                             |                   |             |              |            |                         |
| Casing diameter:  | <i>4</i>         | Time/<br>Volume                 | Temp.<br>°C                 | Cond.<br>@ 25     | pH          | Eh           | D.O.       | Turbidity<br>Appearance |
| Total well depth:*  | <i>64.0</i>      | <i>1415/69g</i>                 | <i>12.4</i>                 | <i>588</i>        | <i>8.55</i> | <i>-136</i>  | <i>.97</i> | <i>clear</i>            |
| Static water level:*  | <i>28.93</i>     | <i>1423/92g</i>                 | <i>12.5</i>                 | <i>735</i>        | <i>8.13</i> | <i>-87</i>   | <i>.52</i> | <i>clear</i>            |
| Water depth:*   | <i>35.1</i>      | <i>1431/115g</i>                | <i>12.6</i>                 | <i>912</i>        | <i>7.94</i> | <i>-71</i>   | <i>.38</i> | <i>clear</i>            |
| Well volume: (gal)  | <i>23</i>        | <i>1438/138g</i>                | <i>12.6</i>                 | <i>1129</i>       | <i>7.62</i> | <i>-59</i>   | <i>.27</i> | <i>clear</i>            |
| Purge method:   | <i>Dedicated</i> | <i>1446/161g</i>                | <i>12.7</i>                 | <i>1147</i>       | <i>7.51</i> | <i>-51</i>   | <i>.21</i> | <i>clear</i>            |
| Sample method:  | <i>Grab</i>      | <i>1454/194g</i>                | <i>12.7</i>                 | <i>1159</i>       | <i>7.44</i> | <i>-40</i>   | <i>.17</i> | <i>clear</i>            |
| Start time:   | <i>1352</i>      | Odor: <i>none detected</i>      |                             |                   |             |              |            |                         |
| Stop time:  | <i>1454</i>      | Purge Appearance: <i>clear</i>  |                             |                   |             |              |            |                         |
| Duration: (minutes)   | <i>62</i>        | Sample Appearance: <i>clear</i> |                             |                   |             |              |            |                         |
| Rate, gpm:  | <i>3</i>         | Comments:                       |                             |                   |             |              |            |                         |
| Volume, purged:   | <i>194 gal</i>   |                                 |                             |                   |             |              |            |                         |
| Duplicate collected?  | <i>M-1</i>       |                                 |                             |                   |             |              |            |                         |
| Sample collection by: <i>KSJ</i>  |                  |                                 |                             |                   |             |              |            |                         |
|   |                  | CO2-                            | Mn2-                        | Fe(T)-            | Fe2-        |              |            |                         |
| Others present:   |                  |                                 |                             |                   |             |              |            |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |                                 |                             |                   |             |              |            |                         |
| CASING & CAP:   |                  | COLLAR:                         |                             | LOCK:             |             | OTHER:       |            |                         |
| MW: groundwater monitoring well   |                  | WS: water supply well           |                             | SW: surface water |             | SE: sediment |            | other:                  |
| VOC- <i>2+2</i>   | semi-volatile-   | general-                        | nutrient-                   | cyanide-          | DRO-        | Sulfide-     |            |                         |
| oil, grease-  | bacteria-        | total metal-                    | filtered metal-             | methane-          | filter-     |              |            |                         |
| Others:   |                  |                                 |                             |                   |             |              |            |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company Field Log Data Sheet

| Client: <i>General Mills</i>  |                  | Monitoring Point: <i>202</i>  |                 |                   |             |              |             |                         |
|---|------------------|---|-----------------|-------------------|-------------|--------------|-------------|-------------------------|
| Location: <i>MPLS</i>   |                  | Date: <i>10-30-03</i>   |                 |                   |             |              |             |                         |
| Project #: <i>23/27-169403102</i>   |                  | Sample Time: <i>1740</i>  |                 |                   |             |              |             |                         |
| GENERAL DATA  |                  | STABILIZATION TEST  |                 |                   |             |              |             |                         |
| Barr lock:  | <i>YES</i>       |   |                 |                   |             |              |             |                         |
| Casing diameter:  | <i>4"</i>        | Time/<br>Volume   | Temp.<br>°C     | Cond.<br>@ 25     | pH          | Eh           | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>116.0</i>     | <i>1641/53g</i>   | <i>12.7</i>     | <i>657</i>        | <i>7.10</i> | <i>38</i>    | <i>3.49</i> | <i>cloudy brown</i>     |
| Static water level:*  | <i>88.89</i>     | <i>1659/71g</i>   | <i>12.8</i>     | <i>631</i>        | <i>7.18</i> | <i>41</i>    | <i>3.41</i> | <i>"</i>                |
| Water depth:*   | <i>27</i>        | <i>1718/89g</i>   | <i>12.9</i>     | <i>620</i>        | <i>7.08</i> | <i>43</i>    | <i>3.46</i> | <i>clearing</i>         |
| Well volume: (gal)  | <i>18</i>        | <i>1736/107g</i>  | <i>13.0</i>     | <i>612</i>        | <i>7.04</i> | <i>45</i>    | <i>3.51</i> |                         |
| Purge method:   | <i>Dedicated</i> |   |                 |                   |             |              |             |                         |
| Sample method:  | <i>Grab</i>      |   |                 |                   |             |              |             |                         |
| Start time:   | <i>1548</i>      | Odor:   |                 |                   |             |              |             |                         |
| Stop time:  | <i>1736</i>      | Purge Appearance: <i>cloudy brown /</i>   |                 |                   |             |              |             |                         |
| Duration: (minutes)   | <i>107</i>       | Sample Appearance:  |                 |                   |             |              |             |                         |
| Rate, gpm:  | <i>1</i>         | Comments: <i>Difficult to start pump delay about 20 minutes, 1 power cord @ generator sparked 1 became hot initially.</i> |                 |                   |             |              |             |                         |
| Volume, purged:   | <i>107 gal</i>   |   |                 |                   |             |              |             |                         |
| Duplicate collected?  | <i>-</i>         |   |                 |                   |             |              |             |                         |
| Sample collection by:   | <i>KSJ</i>       | CO2-  | Mn2-            | Fe(T)-            | Fe2-        |              |             |                         |
| Others present:   |                  |   |                 |                   |             |              |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |   |                 |                   |             |              |             |                         |
| CASING & CAP:   |                  | COLLAR:   |                 | LOCK:             |             | OTHER:       |             |                         |
| MW: groundwater monitoring well   |                  | WS: water supply well   |                 | SW: surface water |             | SE: sediment |             | other:                  |
| VOC- <i>2</i>   | semi-volatile-   | general-  | nutrient-       | cyanide-          | DRO-        | Sulfide-     |             |                         |
| oil, grease-  | bacteria-        | total metal-  | filtered metal- | methane-          | filter-     |              |             |                         |
| Others:   |                  |   |                 |                   |             |              |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company

## Field Log Data Sheet

| Client: <u>General Mills</u>  |                  | Monitoring Point: <u>200</u>    |                       |               |                   |                 |                     |                         |
|---|------------------|---------------------------------|-----------------------|---------------|-------------------|-----------------|---------------------|-------------------------|
| Location: <u>MPLS</u>   |                  | Date: <u>10-31-03</u>           |                       |               |                   |                 |                     |                         |
| Project #: <u>23/27-169403102</u>   |                  | Sample Time: <u>1210</u>        |                       |               |                   |                 |                     |                         |
| GENERAL DATA  |                  | STABILIZATION TEST              |                       |               |                   |                 |                     |                         |
| Barr lock:  | <u>YES</u>       |                                 |                       |               |                   |                 |                     |                         |
| Casing diameter:  | <u>8"</u>        | Time/<br>Volume                 | Temp.<br>°C           | Cond.<br>@ 25 | pH                | Eh              | D.O.                | Turbidity<br>Appearance |
| Total well depth:*  | <u>198.0</u>     | <u>1109/880g</u>                | <u>10.2</u>           | <u>703</u>    | <u>7.35</u>       | <u>5</u>        | <u>2.22</u>         | <u>clear</u>            |
| Static water level:*  | <u>84.91</u>     | <u>1128/1175g</u>               | <u>9.1</u>            | <u>605</u>    | <u>7.25</u>       | <u>3</u>        | <u>1.80</u>         | <u>clear</u>            |
| Water depth:*   | <u>113.1</u>     | <u>1149/1470g</u>               | <u>7.8</u>            | <u>589</u>    | <u>7.22</u>       | <u>5</u>        | <u>1.91</u>         | <u>clear</u>            |
| Well volume: (gal)  | <u>294</u>       | <u>1208/1764g</u>               | <u>6.9</u>            | <u>567</u>    | <u>7.16</u>       | <u>8</u>        | <u>1.97</u>         | <u>clear</u>            |
| Purge method:   | <u>Dedicated</u> |                                 |                       |               |                   |                 |                     |                         |
| Sample method:  | <u>Grab</u>      |                                 |                       |               |                   |                 |                     |                         |
| Start time:   | <u>1010</u>      | Odor: <u>none detected</u>      |                       |               |                   |                 |                     |                         |
| Stop time:  | <u>1208</u>      | Purge Appearance: <u>clear</u>  |                       |               |                   |                 |                     |                         |
| Duration: (minutes)   | <u>118</u>       | Sample Appearance: <u>clear</u> |                       |               |                   |                 |                     |                         |
| Rate, gpm:  | <u>15</u>        | Comments:                       |                       |               |                   |                 |                     |                         |
| Volume, purged:   | <u>1764 gal</u>  |                                 |                       |               |                   |                 |                     |                         |
| Duplicate collected?  | <u>-</u>         |                                 |                       |               |                   |                 |                     |                         |
| Sample collection by:   | <u>KSJ</u>       |                                 |                       |               |                   |                 |                     |                         |
|   |                  | CO2-                            | Mn2-                  | Fe(T)-        | Fe2-              |                 |                     |                         |
| Others present:   |                  |                                 |                       |               |                   |                 |                     |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |                                 |                       |               |                   |                 |                     |                         |
| CASING & CAP:   |                  | COLLAR:                         |                       | LOCK:         |                   | OTHER:          |                     |                         |
| MW: groundwater monitoring well   |                  |                                 | WS: water supply well |               | SW: surface water |                 | SE: sediment other: |                         |
| VOC- <u>2</u> semi-volatile-  |                  | general-                        |                       | nutrient-     |                   | cyanide-        |                     | DRO- Sulfide-           |
| oil, grease-  |                  | bacteria-                       |                       | total metal-  |                   | filtered metal- |                     | methane- filter-        |
| Others:   |                  |                                 |                       |               |                   |                 |                     |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company

## Field Log Data Sheet

| Client: <i>General Mills</i>  |                  |                                 |             | Monitoring Point: <i>203</i> |             |                 |             |                         |
|---|------------------|---------------------------------|-------------|------------------------------|-------------|-----------------|-------------|-------------------------|
| Location: <i>Mpls</i>   |                  |                                 |             | Date: <i>10.31.03</i>        |             |                 |             |                         |
| Project #: <i>23/27-169403102</i>   |                  |                                 |             | Sample Time: <i>1345</i>     |             |                 |             |                         |
| GENERAL DATA  |                  | STABILIZATION TEST              |             |                              |             |                 |             |                         |
| Barr lock:  | <i>YES</i>       |                                 |             |                              |             |                 |             |                         |
| Casing diameter:  | <i>4</i>         | Time/<br>Volume                 | Temp.<br>°C | Cond.<br>@ 25                | pH          | Eh              | D.O.        | Turbidity<br>Appearance |
| Total well depth:*  | <i>118.0</i>     | <i>1303/66g.</i>                | <i>11.8</i> | <i>598</i>                   | <i>7.55</i> | <i>18</i>       | <i>4.36</i> | <i>clear</i>            |
| Static water level:*  | <i>95.64</i>     | <i>1322/88g.</i>                | <i>11.8</i> | <i>597</i>                   | <i>7.47</i> | <i>21</i>       | <i>4.19</i> | <i>clear</i>            |
| Water depth:*   | <i>22</i>        | <i>1337/110g.</i>               | <i>11.9</i> | <i>599</i>                   | <i>7.43</i> | <i>23</i>       | <i>4.23</i> | <i>clear</i>            |
| Well volume: (gal)  | <i>14</i>        | <i>1344/132g.</i>               | <i>11.9</i> | <i>601</i>                   | <i>7.40</i> | <i>24</i>       | <i>4.15</i> | <i>clear</i>            |
| Purge method:   | <i>Dedicated</i> |                                 |             |                              |             |                 |             |                         |
| Sample method:  | <i>Grab</i>      |                                 |             |                              |             |                 |             |                         |
| Start time:   | <i>1238</i>      | Odor: <i>None detected</i>      |             |                              |             |                 |             |                         |
| Stop time:  | <i>1344</i>      | Purge Appearance: <i>clear</i>  |             |                              |             |                 |             |                         |
| Duration: (minutes)   | <i>66</i>        | Sample Appearance: <i>clear</i> |             |                              |             |                 |             |                         |
| Rate, gpm:  | <i>2</i>         | Comments:                       |             |                              |             |                 |             |                         |
| Volume, purged:   | <i>132 gal</i>   |                                 |             |                              |             |                 |             |                         |
| Duplicate collected?  | <i>-</i>         |                                 |             |                              |             |                 |             |                         |
| Sample collection by:   | <i>KSJ</i>       | CO2-                            | Mn2-        | Fe(T)-                       | Fe2-        |                 |             |                         |
| Others present:   |                  |                                 |             |                              |             |                 |             |                         |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |                                 |             |                              |             |                 |             |                         |
| CASING & CAP:   |                  | COLLAR:                         |             | LOCK:                        |             | OTHER:          |             |                         |
| MVV: groundwater monitoring well  |                  | WS: water supply well           |             | SW: surface water            |             | SE: sediment    |             | other:                  |
| VOC- <i>2</i> semi-volatile-  |                  | general-                        |             | nutrient-                    |             | cyanide-        |             | DRO- Sulfide-           |
| oil, grease-  |                  | bacteria-                       |             | total metal-                 |             | filtered metal- |             | methane- filter-        |
| Others:   |                  |                                 |             |                              |             |                 |             |                         |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.





# Barr Engineering Company

## Field Log Data Sheet

|   |                  |                       |                 |                                  |             |                     |                        |
|---|------------------|-----------------------|-----------------|----------------------------------|-------------|---------------------|------------------------|
| Client: <i>General Mills</i>  |                  |                       |                 | Monitoring Point: <i>Heinkel</i> |             |                     |                        |
| Location: <i>Mpls</i>   |                  |                       |                 | Date: <i>10-31-03</i>            |             |                     |                        |
| Project #: <i>23/27-169403102</i>   |                  |                       |                 | Sample Time:                     |             |                     |                        |
| GENERAL DATA  |                  |                       |                 | STABILIZATION TEST               |             |                     |                        |
| Barr lock:  |                  |                       |                 |                                  |             |                     |                        |
| Casing diameter:  |                  | Time/<br>Volume       | Temp.<br>°C     | Cond.<br>@ 25                    | pH          | Eh                  | D.O.                   |
| Total well depth:*  |                  |                       | <i>10.7</i>     | <i>490</i>                       | <i>8.10</i> | <i>29</i>           | <i>7.25</i>            |
| Static water level:*  |                  |                       |                 |                                  |             |                     | <i>slightly cloudy</i> |
| Water depth:*   |                  |                       |                 |                                  |             |                     |                        |
| Well volume: (gal)  |                  |                       |                 |                                  |             |                     |                        |
| Purge method:   | <i>Dedicated</i> |                       |                 |                                  |             |                     |                        |
| Sample method:  | <i>Grab</i>      |                       |                 |                                  |             |                     |                        |
| Start time:   |                  | Odor:                 |                 |                                  |             |                     |                        |
| Stop time:  |                  | Purge Appearance:     |                 |                                  |             |                     |                        |
| Duration: (minutes)   |                  | Sample Appearance:    |                 |                                  |             |                     |                        |
| Rate, gpm:  |                  | Comments:             |                 |                                  |             |                     |                        |
| Volume, purged:   |                  |                       |                 |                                  |             |                     |                        |
| Duplicate collected?  |                  |                       |                 |                                  |             |                     |                        |
| Sample collection by:   | <i>KST</i>       | CO2-                  | Mn2-            | Fe(T)-                           | Fe2-        |                     |                        |
| Others present:   |                  |                       |                 |                                  |             |                     |                        |
| WELL INSPECTION (answer for each category, state if lock replaced, detail any repairs needed on back of form) |                  |                       |                 |                                  |             |                     |                        |
| CASING & CAP:   |                  | COLLAR:               |                 | LOCK:                            |             | OTHER:              |                        |
| MW: groundwater monitoring well   |                  | WS: water supply well |                 | SW: surface water                |             | SE: sediment other: |                        |
| VOC- <i>2</i>   | semi-volatile-   | general-              | nutrient-       | cyanide-                         | DRO-        | Sulfide-            |                        |
| oil, grease-  | bacteria-        | total metal-          | filtered metal- | methane-                         | filter-     |                     |                        |
| Others:   |                  |                       |                 |                                  |             |                     |                        |

\*Measurements are referenced from top of riser pipe, unless otherwise indicated.



# BARR ENGINEERING COMPANY METER CALIBRATION SUMMARY

PROJECT

General Mills

TECHNICIAN

23/27-169 403

| Meter type<br>and number                                    | Date     | Time          | Temperature<br>C | Standard<br>Used   | Meter<br>Reading | Slope | Conductivity<br>Redline |
|---|----------|---------------|------------------|--------------------|------------------|-------|-------------------------|
| YSI 556   | 10-28-03 | 0810          | 12               | 7/10               | 7.00/10.00       | -     | -                       |
|   | 10-29-03 | 0755          | 10               | 7/10               | 7.00/10.00       | -     | -                       |
|   | 10-30-03 | 0815          | 14               | 7/10               | 7.00/10.00       | -     | -                       |
|   |          |               |                  |                    |                  |       |                         |
| Conductivity  | Date     | Solution Used | Cell Result      |                    |                  |       |                         |
| Cell Check  | 10-28-03 | 1000 umhos    | 1000 umhos       |                    |                  |       |                         |
|   | 10-29-03 | "             | "                |                    |                  |       |                         |
|   |          |               |                  |                    |                  |       |                         |
| ORP Probe   | Date     | Temp.         | ORP Reading      | Calculation Result |                  |       |                         |
| Check   | 10-28-03 | 12            | 246              | 246                |                  |       |                         |
| 231+- 10mV @ 25C  | 10-29-03 | 10            | 254              | 254                |                  |       |                         |
| 231mV = Display Value + [(Display Temp. - 25 C) x (1.3 mV)] |          |               |                  |                    |                  |       |                         |

## WEATHER CONDITIONS

| Date     | Wind<br>Direction | Wind<br>Speed | Temperature<br>F | Cloud<br>Cover | Comments |
|----------|-------------------|---------------|------------------|----------------|----------|
| 10-28-03 | NW                | 10-20 mph     | 35-43            | overcast       | drizzle  |
| 10-29-03 | NW                | 5-15 "        | 35-40            | overcast       | "        |
| 10-30-03 | NW                | 5-10 "        | 37-43            | overcast       | "        |
|          |                   |               |                  |                |          |
|          |                   |               |                  |                |          |
|          |                   |               |                  |                |          |
|          |                   |               |                  |                |          |
|          |                   |               |                  |                |          |
|          |                   |               |                  |                |          |
|          |                   |               |                  |                |          |

Comments:











November 18, 2003

Barr Engineering Company  
Attn: Marta Nelson  
4700 West 77th Street  
Minneapolis, MN 55435

RECEIVED  
NOV 20 2003  
Barr Engineering Co.

RE: 23/27-169TMF:General Mills MN Cert. #026-999-161  
Submittal Number: 34926-27

Dear Ms. Marta Nelson:


Enclosed is a copy of your laboratory report for test samples received by our laboratory on November 3, 2003.

Please note that the test results of the enclosed analyses relate only to the sample(s) as received at the laboratory, and are in compliance with the requirements of the National Environmental Laboratory Accreditation Conference (NELAC) standards. Qualification of test standards, including sample acceptance requirements, are presented within the Statement of Data Qualifications.

Estimates of analytical uncertainties for the test results contained within this report are available upon request.

If you have any questions or require further information, please do not hesitate to contact me.

Sincerely,

  
Jennifer L. Rice  
Project Chemist

Enclosure(s)

The total number of pages in this report, including this page, is 39.



**STATEMENT OF DATA QUALIFICATIONS**

All analyses have been validated and comply with our Quality Control Program. No qualifications required.

Page 1 - End of Statement of Data Qualifications

**Note:** This document is included as a part of the analytical report for the above referenced project and submittal, and should be retained as a permanent record thereof.



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: **23/27-169TMF:General Mills**  
 MN Cert. #026-999-161

Sampled: 10/28/03 @ 00:00  
 Sampler: K.J.  
 Received: 10/31/03 @ 09:00  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/07/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90837 -107  
 Anal. Batch: 209223  
 Percent Solids: n/a  
 Dilution Factor: 1

Submittal #: **34926-27**  
 Submittal: **October 2003 Samples**

Sample ID: **11**  
 Sample #: **348058**  
 Matrix: **Water**  
 Unit: **ug/L**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <2.0                 | 2.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <2.0                 | 2.0                |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>7.5</b>           | 2.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <2.0                 | 2.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <2.0                 | 2.0                |
| 127-18-4   | Tetrachloroethene                       | <2.0                 | 2.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <2.0                 | 2.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>48</b>            | 2.0                |
| 71-43-2    | <b>Benzene</b>                          | <b>6.9</b>           | 2.0                |
| 100-41-4   | Ethylbenzene                            | <2.0                 | 2.0                |
| 108-88-3   | Toluene                                 | <2.0                 | 2.0                |
| 1330-20-7  | Xylene (Total)                          | <6.0                 | 6.0                |
| 75-01-4    | Vinyl Chloride                          | <2.0                 | 2.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
**MN Cert. #026-999-161**

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **SS**  
Sample #: **348059**  
Matrix: **Water**  
Unit: **ug/L**

Sampled: **10/28/03 @ 00:00**  
Sampler: **K.J.**  
Received: **10/31/03 @ 09:00**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/07/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90837 -107**  
Anal. Batch: **209223**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | 3.0                  | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | Trichloroethene                         | 2.9                  | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
**MN Cert. #026-999-161**

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **TT**  
Sample #: **348060**  
Matrix: **Water**  
Unit: **ug/L**

Sampled: **10/28/03 @ 00:00**  
Sampler: **K.J.**  
Received: **10/31/03 @ 09:00**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/07/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90837 -107**  
Anal. Batch: **209223**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>2.9</b>           | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | <b>1,1,1-Trichloroethane</b>            | <b>2.0</b>           | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>5.6</b>           | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: **23/27-169TMF:General Mills**  
 MN Cert. #026-999-161

Sampled: 10/28/03 @ 00:00  
 Sampler: K.J.  
 Received: 10/31/03 @ 09:00  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/07/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90837 -107  
 Anal. Batch: 209223  
 Percent Solids: n/a  
 Dilution Factor: 1

Submittal #: **34926-27**  
 Submittal: **October 2003 Samples**

Sample ID: **14**  
 Sample #: **348061**  
 Matrix: **Water**  
 Unit: **ug/L**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>1.7</b>           | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | <b>1,1,1-Trichloroethane</b>            | <b>1.6</b>           | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>4.7</b>           | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: **23/27-169TMF:General Mills**  
 MN Cert. #026-999-161

Submittal #: **34926-27**  
 Submittal: **October 2003 Samples**

Sample ID: **12**  
 Sample #: **348062**  
 Matrix: **Water**  
 Unit: **ug/L**

Sampled: **10/28/03 @ 00:00**  
 Sampler: **K.J.**  
 Received: **10/31/03 @ 09:00**  
 Prepared: **n/a**  
 Prep. Method: **n/a**  
 Analyzed: **11/07/03 by TME**  
 Anal. Method: **USEPA-8021B**  
 QC Batch: **90837 -107**  
 Anal. Batch: **209223**  
 Percent Solids: **n/a**  
 Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>1.7</b>           | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: 23/27-169TMF:General Mills  
 MN Cert. #026-999-161

Sampled: 10/29/03 @ 00:00  
 Sampler: K.J.  
 Received: 10/31/03 @ 09:00  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/07/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90837 -107  
 Anal. Batch: 209223  
 Percent Solids: n/a  
 Dilution Factor: 1

Submittal #: **34926-27**  
 Submittal: October 2003 Samples

Sample ID: **UU**  
 Sample #: **348063**  
 Matrix: Water  
 Unit: ug/L

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | <b>1,1,1-Trichloroethane</b>            | <b>1.5</b>           | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>25</b>            | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: **23/27-169TMF:General Mills**  
 MN Cert. #026-999-161

Sampled: 10/29/03 @ 00:00  
 Sampler: K.J.  
 Received: 10/31/03 @ 09:00  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/07/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90837 -107  
 Anal. Batch: 209223  
 Percent Solids: n/a  
 Dilution Factor: 1

Submittal #: **34926-27**  
 Submittal: October 2003 Samples

Sample ID: **Q**  
 Sample #: **348064**  
 Matrix: Water  
 Unit: ug/L

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | <b>1,1,1-Trichloroethane</b>            | <b>2.4</b>           | 1.0                |
| 79-01-6    | Trichloroethene                         | <1.0                 | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
MN Cert. #026-999-161

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **QQ**  
Sample #: **348065**  
Matrix: **Water**  
Unit: **ug/L**

Sampled: **10/29/03 @ 00:00**  
Sampler: **K.J.**  
Received: **10/31/03 @ 09:00**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/07/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90837 -107**  
Anal. Batch: **209223**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>1.1</b>           | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | Trichloroethene                         | <1.0                 | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
**MN Cert. #026-999-161**

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **T**  
Sample #: **348066**  
Matrix: **Water**  
Unit: **ug/L**

Sampled: **10/29/03 @ 00:00**  
Sampler: **K.J.**  
Received: **10/31/03 @ 09:00**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/07/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90837 -107**  
Anal. Batch: **209223**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | Trichloroethene                         | <1.0                 | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
**MN Cert. #026-999-161**

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **X**  
Sample #: **348067**  
Matrix: **Water**  
Unit: **ug/L**

Sampled: **10/29/03 @ 00:00**  
Sampler: **K.J.**  
Received: **10/31/03 @ 09:00**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/08/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90837 -107**  
Anal. Batch: **209223**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | Trichloroethene                         | <1.0                 | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: 23/27-169TMF:General Mills  
MN Cert. #026-999-161

Submittal #: **34926-27**  
Submittal: October 2003 Samples

Sample ID: **V**  
Sample #: **348068**  
Matrix: Water  
Unit: ug/L

Sampled: 10/29/03 @ 00:00  
Sampler: K.J.  
Received: 10/31/03 @ 09:00  
Prepared: n/a  
Prep. Method: n/a  
Analyzed: 11/10/03 by TME  
Anal. Method: USEPA-8021B  
QC Batch: 90837 -110  
Anal. Batch: 209225  
Percent Solids: n/a  
Dilution Factor: 1

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>14</b>            | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
**MN Cert. #026-999-161**

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **W**  
Sample #: **348069**  
Matrix: **Water**  
Unit: **ug/L**

Sampled: **10/29/03 @ 00:00**  
Sampler: **K.J.**  
Received: **10/31/03 @ 09:00**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/08/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90837 -107**  
Anal. Batch: **209223**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <2.0                 | 2.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <2.0                 | 2.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | 52                   | 2.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | 3.5                  | 2.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <2.0                 | 2.0                |
| 127-18-4   | Tetrachloroethene                       | <2.0                 | 2.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <2.0                 | 2.0                |
| 79-01-6    | Trichloroethene                         | 14                   | 2.0                |
| 71-43-2    | Benzene                                 | <2.0                 | 2.0                |
| 100-41-4   | Ethylbenzene                            | <2.0                 | 2.0                |
| 108-88-3   | Toluene                                 | <2.0                 | 2.0                |
| 1330-20-7  | Xylene (Total)                          | <6.0                 | 6.0                |
| 75-01-4    | Vinyl Chloride                          | <2.0                 | 2.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: 23/27-169TMF:General Mills  
MN Cert. #026-999-161

Sampled: 10/30/03 @ 00:00  
Sampler: K.J.  
Received: 10/31/03 @ 09:00  
Prepared: n/a  
Prep. Method: n/a  
Analyzed: 11/08/03 by TME  
Anal. Method: USEPA-8021B  
QC Batch: 90837 -107  
Anal. Batch: 209223  
Percent Solids: n/a  
Dilution Factor: 1

Submittal #: **34926-27**  
Submittal: October 2003 Samples

Sample ID: **9**  
Sample #: **348070**  
Matrix: Water  
Unit: ug/L

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>1.1</b>           | 1.0                |
| 71-43-2    | <b>Benzene</b>                          | <b>12</b>            | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: **23/27-169TMF:General Mills**  
 MN Cert. #026-999-161

Sampled: 10/30/03 @ 00:00  
 Sampler: K.J.  
 Received: 10/31/03 @ 09:00  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/08/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90837 -107  
 Anal. Batch: 209223  
 Percent Solids: n/a  
 Dilution Factor: 1

Submittal #: **34926-27**  
 Submittal: **October 2003 Samples**

Sample ID: **10**  
 Sample #: **348071**  
 Matrix: **Water**  
 Unit: **ug/L**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | <b>1,1,1-Trichloroethane</b>            | <b>1.2</b>           | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>15</b>            | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
**MN Cert. #026-999-161**

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **M-1**  
Sample #: **348072**  
Matrix: **Water**  
Unit: **ug/L**

Sampled: **10/30/03 @ 00:00**  
Sampler: **K.J.**  
Received: **10/31/03 @ 09:00**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/10/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90837 -110**  
Anal. Batch: **209225**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | 1.2                  | 1.0                |
| 79-01-6    | Trichloroethene                         | 16                   | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: **23/27-169TMF:General Mills**  
 MN Cert. #026-999-161

Submittal #: **34926-27**  
 Submittal: **October 2003 Samples**

Sample ID: **202**  
 Sample #: **348073**  
 Matrix: **Water**  
 Unit: **ug/L**

Sampled: **10/30/03 @ 00:00**  
 Sampler: **K.J.**  
 Received: **10/31/03 @ 09:00**  
 Prepared: **n/a**  
 Prep. Method: **n/a**  
 Analyzed: **11/08/03 by TME**  
 Anal. Method: **USEPA-8021B**  
 QC Batch: **90837 -107**  
 Anal. Batch: **209223**  
 Percent Solids: **n/a**  
 Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | Trichloroethene                         | <1.0                 | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: 23/27-169TMF:General Mills  
 MN Cert. #026-999-161

Sampled: 10/31/03 @ 00:00  
 Sampler: K.J.  
 Received: 11/01/03 @ 09:10  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/12/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90937 -112  
 Anal. Batch: 209352  
 Percent Solids: n/a  
 Dilution Factor: 1

Submittal #: **34926-27**  
 Submittal: October 2003 Samples

Sample ID: **200**  
 Sample #: **348192**  
 Matrix: Water  
 Unit: ug/L

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>1.6</b>           | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>4.2</b>           | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
**MN Cert. #026-999-161**

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **203**  
Sample #: **348193**  
Matrix: **Water**  
Unit: **ug/L**

Sampled: **10/31/03 @ 00:00**  
Sampler: **K.J.**  
Received: **11/01/03 @ 09:10**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/12/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90937 -112**  
Anal. Batch: **209352**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>3.6</b>           | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>28</b>            | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: **23/27-169TMF:General Mills**  
 MN Cert. #026-999-161

Sampled: 10/31/03 @ 00:00  
 Sampler: K.J.  
 Received: 11/01/03 @ 09:10  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/13/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90937 -112  
 Anal. Batch: 209352  
 Percent Solids: n/a  
 Dilution Factor: 1

Submittal #: **34926-27**  
 Submittal: October 2003 Samples

Sample ID: **Henkel**  
 Sample #: **348194**  
 Matrix: Water  
 Unit: ug/L

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>4.2</b>           | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>4.0</b>           | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
**MN Cert. #026-999-161**

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **DSCHG**  
Sample #: **348195**  
Matrix: **Water**  
Unit: **ug/L**

Sampled: **10/31/03 @ 00:00**  
Sampler: **K.J.**  
Received: **11/01/03 @ 09:10**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/12/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90937 -112**  
Anal. Batch: **209352**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <2.0                 | 2.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <2.0                 | 2.0                |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>6.3</b>           | 2.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <2.0                 | 2.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <2.0                 | 2.0                |
| 127-18-4   | Tetrachloroethene                       | <2.0                 | 2.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <2.0                 | 2.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>48</b>            | 2.0                |
| 71-43-2    | Benzene                                 | <2.0                 | 2.0                |
| 100-41-4   | Ethylbenzene                            | <2.0                 | 2.0                |
| 108-88-3   | Toluene                                 | <2.0                 | 2.0                |
| 1330-20-7  | Xylene (Total)                          | <6.0                 | 6.0                |
| 75-01-4    | Vinyl Chloride                          | <2.0                 | 2.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: **23/27-169TMF:General Mills**  
 MN Cert. #026-999-161

Sampled: 10/31/03 @ 00:00  
 Sampler: K.J.  
 Received: 11/01/03 @ 09:10  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/12/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90937 -112  
 Anal. Batch: 209352  
 Percent Solids: n/a  
 Dilution Factor: 1

Submittal #: **34926-27**  
 Submittal: October 2003 Samples

Sample ID: **INF**  
 Sample #: **348196**  
 Matrix: Water  
 Unit: ug/L

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <10                  | 10                 |
| 107-06-2   | 1,2-Dichloroethane                      | <10                  | 10                 |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>24</b>            | 10                 |
| 156-60-5   | trans-1,2-Dichloroethene                | <10                  | 10                 |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <10                  | 10                 |
| 127-18-4   | Tetrachloroethene                       | <10                  | 10                 |
| 71-55-6    | 1,1,1-Trichloroethane                   | <10                  | 10                 |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>200</b>           | 10                 |
| 71-43-2    | Benzene                                 | <10                  | 10                 |
| 100-41-4   | Ethylbenzene                            | <10                  | 10                 |
| 108-88-3   | Toluene                                 | <10                  | 10                 |
| 1330-20-7  | Xylene (Total)                          | <30                  | 30                 |
| 75-01-4    | Vinyl Chloride                          | <10                  | 10                 |



# ANALYTICAL REPORT

|              |                                 |                  |                  |
|--------------|---------------------------------|------------------|------------------|
| Client:      | <b>Barr Engineering Company</b> | Sampled:         | 10/31/03 @ 00:00 |
| Project:     | 23/27-169TMF:General Mills      | Sampler:         | K.J.             |
|              | MN Cert. #026-999-161           | Received:        | 11/01/03 @ 09:10 |
|              |                                 | Prepared:        | n/a              |
| Submittal #: | <b>34926-27</b>                 | Prep. Method:    | n/a              |
| Submittal:   | October 2003 Samples            | Analyzed:        | 11/12/03 by TME  |
|              |                                 | Anal. Method:    | USEPA-8021B      |
| Sample ID:   | <b>M6 EFF</b>                   | QC Batch:        | 90937 -112       |
| Sample #:    | <b>348197</b>                   | Anal. Batch:     | 209352           |
| Matrix:      | Water                           | Percent Solids:  | n/a              |
| Unit:        | ug/L                            | Dilution Factor: | 1                |

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | <b>cis-1,2-Dichloroethene</b>           | <b>2.1</b>           | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | <b>Trichloroethene</b>                  | <b>12</b>            | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: 23/27-169TMF:General Mills  
 MN Cert. #026-999-161

Submittal #: **34926-27**  
 Submittal: October 2003 Samples

Sample ID: **EFF**  
 Sample #: **348198**  
 Matrix: Water  
 Unit: ug/L

Sampled: 10/31/03 @ 00:00  
 Sampler: K.J.  
 Received: 11/01/03 @ 09:10  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/12/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90937 -112  
 Anal. Batch: 209352  
 Percent Solids: n/a  
 Dilution Factor: 1

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | Trichloroethene                         | <1.0                 | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



# ANALYTICAL REPORT

Client: **Barr Engineering Company**  
 Project: 23/27-169TMF:General Mills  
 MN Cert. #026-999-161

Sampled: 10/31/03 @ 00:00  
 Sampler: K.J.  
 Received: 11/01/03 @ 09:10  
 Prepared: n/a  
 Prep. Method: n/a  
 Analyzed: 11/13/03 by TME  
 Anal. Method: USEPA-8021B  
 QC Batch: 90937 -112  
 Anal. Batch: 209352  
 Percent Solids: n/a  
 Dilution Factor: 1

Submittal #: **34926-27**  
 Submittal: October 2003 Samples

Sample ID: **FB-1**  
 Sample #: **348199**  
 Matrix: Water  
 Unit: ug/L

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | Trichloroethene                         | <1.0                 | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



**ANALYTICAL REPORT**

Client: **Barr Engineering Company**  
Project: **23/27-169TMF:General Mills**  
**MN Cert. #026-999-161**

Submittal #: **34926-27**  
Submittal: **October 2003 Samples**

Sample ID: **TB**  
Sample #: **348200**  
Matrix: **QC Water**  
Unit: **ug/L**

Sampled: **10/31/03 @ 00:00**  
Sampler: **K.J.**  
Received: **11/01/03 @ 09:10**  
Prepared: **n/a**  
Prep. Method: **n/a**  
Analyzed: **11/13/03 by TME**  
Anal. Method: **USEPA-8021B**  
QC Batch: **90937 -113**  
Anal. Batch: **209356**  
Percent Solids: **n/a**  
Dilution Factor: **1**

| CAS Number | Project Specific Fraction<br>USEPA 8021 | Analytical<br>Result | Reporting<br>Limit |
|------------|---|----------------------|--------------------|
| 75-34-3    | 1,1-Dichloroethane                      | <1.0                 | 1.0                |
| 107-06-2   | 1,2-Dichloroethane                      | <1.0                 | 1.0                |
| 156-59-2   | cis-1,2-Dichloroethene                  | <1.0                 | 1.0                |
| 156-60-5   | trans-1,2-Dichloroethene                | <1.0                 | 1.0                |
| 79-34-5    | 1,1,2,2-Tetrachloroethane               | <1.0                 | 1.0                |
| 127-18-4   | Tetrachloroethene                       | <1.0                 | 1.0                |
| 71-55-6    | 1,1,1-Trichloroethane                   | <1.0                 | 1.0                |
| 79-01-6    | Trichloroethene                         | <1.0                 | 1.0                |
| 71-43-2    | Benzene                                 | <1.0                 | 1.0                |
| 100-41-4   | Ethylbenzene                            | <1.0                 | 1.0                |
| 108-88-3   | Toluene                                 | <1.0                 | 1.0                |
| 1330-20-7  | Xylene (Total)                          | <3.0                 | 3.0                |
| 75-01-4    | Vinyl Chloride                          | <1.0                 | 1.0                |



## QUALITY CONTROL REPORT

## LABORATORY FORTIFIED BLANK

Fraction: Volatile Organic Fraction USEPA Method-8021  
Method: Halogenated and Aromatic Volatiles by GC  
Analyst: Timothy M. Eldridge Test Date: 11/07/03  
Units: ug/L  
QC Batch: 90837-107

| Parameter            | Spike<br>Quantity | Spike<br>Result | Spike<br>% Rec | Control<br>Limits |
|----------------------|-------------------|-----------------|----------------|-------------------|
| Benzene              | 20.0              | 18.2            | 91             | 83 - 119          |
| Chlorobenzene        | 20.0              | 20.0            | 100            | 79 - 119          |
| 1,1-Dichloroethylene | 20.0              | 17.4            | 87             | 66 - 135          |
| Trichloroethene      | 20.0              | 17.2            | 86             | 82 - 121          |
| Toluene              | 20.0              | 19.0            | 95             | 77 - 128          |
| 1,2-Dichloroethane   | 20.0              | 20.1            | 101            | 81 - 123          |



## QUALITY CONTROL REPORT

## LABORATORY FORTIFIED BLANK

Fraction: Volatile Organic Fraction      USEPA Method-8021  
Method: Halogenated and Aromatic Volatiles by GC  
Analyst: Timothy M. Eldridge      Test Date: 11/10/03  
Units: ug/L  
QC Batch: 90837-110

| Parameter            | Spike<br>Quantity | Spike<br>Result | Spike<br>% Rec | Control<br>Limits |
|----------------------|-------------------|-----------------|----------------|-------------------|
| Benzene              | 20.0              | 19.0            | 95             | 83 - 119          |
| Chlorobenzene        | 20.0              | 21.1            | 106            | 79 - 119          |
| 1,1-Dichloroethylene | 20.0              | 17.1            | 86             | 66 - 135          |
| Trichloroethene      | 20.0              | 20.7            | 104            | 82 - 121          |
| Toluene              | 20.0              | 19.7            | 99             | 77 - 128          |
| 1,2-Dichloroethane   | 20.0              | 20.8            | 104            | 81 - 123          |



**QUALITY CONTROL REPORT****LABORATORY FORTIFIED BLANK**

Fraction: Volatile Organic Fraction USEPA Method-8021  
Method: Halogenated and Aromatic Volatiles by GC  
Analyst: Timothy M. Eldridge Test Date: 11/12/03  
Units: ug/L  
QC Batch: 90937-112

| Parameter            | Spike<br>Quantity | Spike<br>Result | Spike<br>% Rec | Control<br>Limits |
|----------------------|-------------------|-----------------|----------------|-------------------|
| Benzene              | 20.0              | 18.7            | 94             | 83 - 119          |
| Chlorobenzene        | 20.0              | 18.6            | 93             | 79 - 119          |
| 1,1-Dichloroethylene | 20.0              | 20.8            | 104            | 66 - 135          |
| Trichloroethene      | 20.0              | 18.1            | 91             | 82 - 121          |
| Toluene              | 20.0              | 19.4            | 97             | 77 - 128          |
| 1,2-Dichloroethane   | 20.0              | 19.1            | 96             | 81 - 123          |



## QUALITY CONTROL REPORT

## LABORATORY FORTIFIED BLANK

Fraction: Volatile Organic Fraction USEPA Method-8021  
Method: Halogenated and Aromatic Volatiles by GC  
Analyst: Timothy M. Eldridge Test Date: 11/13/03  
Units: ug/L  
QC Batch: 90937-113

| Parameter            | Spike<br>Quantity | Spike<br>Result | Spike<br>% Rec | Control<br>Limits |
|----------------------|-------------------|-----------------|----------------|-------------------|
| Benzene              | 20.0              | 19.6            | 98             | 83 - 119          |
| Chlorobenzene        | 20.0              | 20.0            | 100            | 79 - 119          |
| 1,1-Dichloroethylene | 20.0              | 22.2            | 111            | 66 - 135          |
| Trichloroethene      | 20.0              | 18.8            | 94             | 82 - 121          |
| Toluene              | 20.0              | 20.5            | 103            | 77 - 128          |
| 1,2-Dichloroethane   | 20.0              | 19.9            | 100            | 81 - 123          |



## QUALITY CONTROL REPORT

## MATRIX SPIKE RECOVERY

Fraction: Volatile Organic Fraction USEPA Method-8021  
Method: Halogenated and Aromatic Volatiles by GC USEPA-8021B WATER  
Analyst: Timothy M. Eldridge Test Date: 11/12/03  
Sample No: 348197  
Units: ug/L  
QC Batch: 90937-112

| Parameter            | Sample<br>Conc | Spike<br>Quantity | Sample<br>+Spike | Spike<br>% Rec | Control<br>Limits |
|----------------------|----------------|-------------------|------------------|----------------|-------------------|
| Benzene              | <1.0           | 20.0              | 18.9             | 95             | 69 - 140          |
| Chlorobenzene        | <1.0           | 20.0              | 18.1             | 91             | 72 - 129          |
| 1,1-Dichloroethylene | <1.0           | 20.0              | 20.5             | 103            | 60 - 143          |
| Trichloroethene      | 12             | 20.0              | 29.1             | 86             | 60 - 131          |
| Toluene              | <1.0           | 20.0              | 18.7             | 94             | 75 - 131          |
| 1,2-Dichloroethane   | <1.0           | 20.0              | 17.5             | 88             | 64 - 131          |



## QUALITY CONTROL REPORT

## MATRIX SPIKE RECOVERY

Fraction: Volatile Organic Fraction USEPA Method-8021  
Method: Halogenated and Aromatic Volatiles by GC USEPA-8021B WATER  
Analyst: Timothy M. Eldridge Test Date: 11/12/03  
Sample No: 348197  
Units: ug/L  
QC Batch: 90937-112

| Parameter            | Sample<br>Conc | Spike<br>Quantity | Sample<br>+Spike | Spike<br>% Rec | Control<br>Limits |
|----------------------|----------------|-------------------|------------------|----------------|-------------------|
| Benzene              | <1.0           | 20.0              | 18.5             | 93             | 69 - 140          |
| Chlorobenzene        | <1.0           | 20.0              | 18.0             | 90             | 72 - 129          |
| 1,1-Dichloroethylene | <1.0           | 20.0              | 20.3             | 102            | 60 - 143          |
| Trichloroethene      | 12             | 20.0              | 29.3             | 87             | 60 - 131          |
| Toluene              | <1.0           | 20.0              | 18.4             | 92             | 75 - 131          |
| 1,2-Dichloroethane   | <1.0           | 20.0              | 18.7             | 94             | 64 - 131          |



## QUALITY CONTROL REPORT

## MATRIX SPIKE DUPLICATE

Fraction: Volatile Organic Fraction USEPA Method-8021  
Method: Halogenated and Aromatic Volatiles by GC USEPA-8021B WATER  
Analyst: Timothy M. Eldridge Test Date: 11/12/03  
Sample No: 348197  
Units: ug/L  
QC Batch: 90937-112

| Parameter            | Sample+Spike<br>Conc #1 | Sample+Spike<br>Conc #2 | Relative<br>% Diff. | Control<br>Limits |
|----------------------|-------------------------|-------------------------|---------------------|-------------------|
| Benzene              | 18.9                    | 18.5                    | 2                   | 0 - 11            |
| Chlorobenzene        | 18.1                    | 18.0                    | 1                   | 0 - 13            |
| 1,1-Dichloroethylene | 20.5                    | 20.3                    | 1                   | 0 - 20            |
| Trichloroethene      | 29.1                    | 29.3                    | 1                   | 0 - 14            |
| Toluene              | 18.7                    | 18.4                    | 2                   | 0 - 11            |
| 1,2-Dichloroethane   | 17.5                    | 18.7                    | 7                   | 0 - 20            |



**QUALITY CONTROL REPORT****METHOD PREPARATION BLANK**

Fraction: Volatile Organics USEPA Method 8021  
Method: Halogenated and Aromatic Volatiles by GC  
Analyst: Timothy M. Eldridge Test Date: 11/07/03  
Units: ug/L  
QC Batch: 90837-107

| Parameter                 | Blank<br>Concentration | Quantitation<br>Limit |
|---------------------------|------------------------|-----------------------|
| Benzene                   | <1.00                  | 1.0                   |
| 1,1-Dichloroethane        | <1.00                  | 1.0                   |
| 1,2-Dichloroethane        | <1.00                  | 1.0                   |
| cis-1,2-Dichloroethene    | <1.00                  | 1.0                   |
| trans-1,2-Dichloroethene  | <1.00                  | 1.0                   |
| Ethylbenzene              | <1.00                  | 1.0                   |
| 1,1,2,2-Tetrachloroethane | <1.00                  | 1.0                   |
| Tetrachloroethene         | <1.00                  | 1.0                   |
| Toluene                   | <1.00                  | 1.0                   |
| 1,1,1-Trichloroethane     | <1.00                  | 1.0                   |
| Trichloroethene           | <1.00                  | 1.0                   |
| Vinyl Chloride            | <1.00                  | 1.0                   |
| Xylene (Total)            | <3.00                  | 3.0                   |



**QUALITY CONTROL REPORT****METHOD PREPARATION BLANK**

Fraction: Volatile Organics USEPA Method 8021  
Method: Halogenated and Aromatic Volatiles by GC  
Analyst: Timothy M. Eldridge Test Date: 11/10/03  
Units: ug/L  
QC Batch: 90837-110

| Parameter                 | Blank<br>Concentration | Quantitation<br>Limit |
|---------------------------|------------------------|-----------------------|
| Benzene                   | <1.00                  | 1.0                   |
| 1,1-Dichloroethane        | <1.00                  | 1.0                   |
| 1,2-Dichloroethane        | <1.00                  | 1.0                   |
| cis-1,2-Dichloroethene    | <1.00                  | 1.0                   |
| trans-1,2-Dichloroethene  | <1.00                  | 1.0                   |
| Ethylbenzene              | <1.00                  | 1.0                   |
| 1,1,2,2-Tetrachloroethane | <1.00                  | 1.0                   |
| Tetrachloroethene         | <1.00                  | 1.0                   |
| Toluene                   | <1.00                  | 1.0                   |
| 1,1,1-Trichloroethane     | <1.00                  | 1.0                   |
| Trichloroethene           | <1.00                  | 1.0                   |
| Vinyl Chloride            | <1.00                  | 1.0                   |
| Xylene (Total)            | <3.00                  | 3.0                   |



## QUALITY CONTROL REPORT

## METHOD PREPARATION BLANK

Fraction: Volatile Organics USEPA Method 8021  
Method: Halogenated and Aromatic Volatiles by GC  
Analyst: Timothy M. Eldridge Test Date: 11/12/03  
Units: ug/L  
QC Batch: 90937-112

| Parameter                 | Blank<br>Concentration | Quantitation<br>Limit |
|---------------------------|------------------------|-----------------------|
| Benzene                   | <1.00                  | 1.0                   |
| Chlorobenzene             | <1.00                  | 1.0                   |
| 1,1-Dichloroethane        | <1.00                  | 1.0                   |
| 1,2-Dichloroethane        | <1.00                  | 1.0                   |
| 1,1-Dichloroethylene      | <1.00                  | 1.0                   |
| cis-1,2-Dichloroethene    | <1.00                  | 1.0                   |
| trans-1,2-Dichloroethene  | <1.00                  | 1.0                   |
| Ethylbenzene              | <1.00                  | 1.0                   |
| 1,1,2,2-Tetrachloroethane | <1.00                  | 1.0                   |
| Tetrachloroethene         | <1.00                  | 1.0                   |
| Toluene                   | <1.00                  | 1.0                   |
| 1,1,1-Trichloroethane     | <1.00                  | 1.0                   |
| Trichloroethene           | <1.00                  | 1.0                   |
| Vinyl Chloride            | <1.00                  | 1.0                   |
| Xylene (Total)            | <3.00                  | 3.0                   |



## QUALITY CONTROL REPORT

## METHOD PREPARATION BLANK

Fraction: Volatile Organics USEPA Method 8021  
Method: Halogenated and Aromatic Volatiles by GC  
Analyst: Timothy M. Eldridge Test Date: 11/13/03  
Units: ug/L  
QC Batch: 90937-113

| Parameter                 | Blank<br>Concentration | Quantitation<br>Limit |
|---------------------------|------------------------|-----------------------|
| Benzene                   | <1.00                  | 1.0                   |
| 1,1-Dichloroethane        | <1.00                  | 1.0                   |
| 1,2-Dichloroethane        | <1.00                  | 1.0                   |
| cis-1,2-Dichloroethene    | <1.00                  | 1.0                   |
| trans-1,2-Dichloroethene  | <1.00                  | 1.0                   |
| Ethylbenzene              | <1.00                  | 1.0                   |
| 1,1,2,2-Tetrachloroethane | <1.00                  | 1.0                   |
| Tetrachloroethene         | <1.00                  | 1.0                   |
| Toluene                   | <1.00                  | 1.0                   |
| 1,1,1-Trichloroethane     | <1.00                  | 1.0                   |
| Trichloroethene           | <1.00                  | 1.0                   |
| Vinyl Chloride            | <1.00                  | 1.0                   |
| Xylene (Total)            | <3.00                  | 3.0                   |



**QUALITY CONTROL REPORT  
SURROGATE RECOVERIES**

Method: Halogenated and Aromatic Volatiles by GC USEPA-8021B WATER

## Surrogate Compound List

-----  
SUR-1: aaa-Trifluorotoluene-sur  
SUR-2: d4-1,2-Dichloroethane-sur

% R = Percent Recovery

Compounds: SUR-1 SUR-2  
Control Limits: 90-113 76-129

| Sample # / ID | Batch     | % R | % R |
|---------------|-----------|-----|-----|
| -----         | -----     | --- | --- |
| MPB-01        | 90837-107 | 100 | 100 |
| MPB-01        | 90837-110 | 99  | 97  |
| MPB-01        | 90937-112 | 100 | 103 |
| MPB-01        | 90937-113 | 100 | 103 |
| LFB-01        | 90837-107 | 100 | 101 |
| LFB-01        | 90837-110 | 100 | 101 |
| LFB-01        | 90937-112 | 100 | 98  |
| LFB-01        | 90937-113 | 101 | 97  |
| 348058        | 90837-107 | 100 | 98  |
| 348059        | 90837-107 | 99  | 98  |
| 348060        | 90837-107 | 99  | 95  |
| 348061        | 90837-107 | 99  | 95  |
| 348062        | 90837-107 | 99  | 99  |
| 348063        | 90837-107 | 99  | 93  |
| 348064        | 90837-107 | 100 | 95  |
| 348065        | 90837-107 | 100 | 99  |
| 348066        | 90837-107 | 99  | 100 |
| 348067        | 90837-107 | 99  | 98  |
| 348068        | 90837-110 | 100 | 104 |
| 348069        | 90837-107 | 100 | 99  |
| 348070        | 90837-107 | 94  | 101 |
| 348071        | 90837-107 | 99  | 93  |
| 348072        | 90837-110 | 99  | 98  |
| 348073        | 90837-107 | 99  | 100 |
| 348192        | 90937-112 | 100 | 106 |
| 348193        | 90937-112 | 100 | 100 |
| 348194        | 90937-112 | 100 | 99  |
| 348195        | 90937-112 | 101 | 94  |
| 348196        | 90937-112 | 100 | 98  |
| 348197        | 90937-112 | 100 | 100 |
| 348198        | 90937-112 | 101 | 99  |
| 348199        | 90937-112 | 101 | 98  |
| 348200        | 90937-113 | 101 | 103 |











## *Appendix C*

### *Process Performance Quality Control Data*



## **Appendix C**

### **Quality Assurance/Quality Control**

#### **List of Tables**

Table C-1 2003 Blank Sample Data

Table C-2 2003 Blind Duplicate Sample Data



**Table C-1**  
**2003 Blank Sample Data**

(concentrations in ug/L)

| Location<br>Date            | Field Blank<br>3/13/2003 | Field Blank<br>6/2/2003 | Field Blank<br>8/26/2003 | Field Blank<br>10/31/2003 | Trip Blank<br>3/13/2003 | Trip Blank<br>6/2/2003 | Trip Blank<br>8/26/2003 | Trip Blank<br>10/31/2003 | Lab Blank<br>3/13/2003 | Lab Blank<br>3/13/2003 | Lab Blank<br>6/2/2003 | Lab Blank<br>6/2/2003 | Lab Blank<br>8/26/2003 |
|-----------------------------|--------------------------|-------------------------|--------------------------|---------------------------|-------------------------|------------------------|-------------------------|--------------------------|------------------------|------------------------|-----------------------|-----------------------|------------------------|
| 1,1,1-Trichloroethane       | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| 1,1,2,2-Tetrachloroethane   | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| 1,1-Dichloroethane          | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| 1,2-Dichloroethane          | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| 1,2-Dichloroethylene, cis   | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| 1,2-Dichloroethylene, trans | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| Benzene                     | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| Ethyl benzene               | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| Tetrachloroethylene         | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| Toluene                     | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | 2.2                     | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| Trichloroethylene           | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| Vinyl chloride              | <1.0                     | <1.0                    | <1.0                     | <1.0                      | <1.0                    | <1.0                   | <1.0                    | <1.0                     | <1.0                   | <1.0                   | <1.0                  | <1.0                  | <1.0                   |
| Xylenes total               | <3.0                     | <3.0                    | <3.0                     | <3.0                      | <3.0                    | <3.0                   | <3.0                    | <3.0                     | <3.0                   | <3.0                   | <3.0                  | <3.0                  | <3.0                   |

-- Not analyzed.



**Table C-1**  
**2003 Blank Sample Data**  
 (concentrations in ug/L)

| Location<br>Date            | Lab Blank<br>8/26/2003 | Lab Blank<br>10/28/2003 | Lab Blank<br>10/28/2003 | Lab Blank<br>10/28/2003 | Lab Blank<br>10/28/2003 |
|-----------------------------|------------------------|-------------------------|-------------------------|-------------------------|-------------------------|
| 1,1,1-Trichloroethane       | --                     | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| 1,1,2,2-Tetrachloroethane   | --                     | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| 1,1-Dichloroethane          | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| 1,2-Dichloroethane          | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| 1,2-Dichloroethylene, cis   | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| 1,2-Dichloroethylene, trans | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| Benzene                     | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| Ethyl benzene               | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| Tetrachloroethylene         | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| Toluene                     | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| Trichloroethylene           | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| Vinyl chloride              | <1.0                   | <1.00                   | <1.00                   | <1.00                   | <1.00                   |
| Xylenes total               | <3.0                   | <3.00                   | <3.00                   | <3.00                   | <3.00                   |

-- Not analyzed.



**Table C-2**  
**2003 Blind Duplicate Data**

(concentrations in ug/L)

| Location                    | 10         | 10         | RPD       | 110       | 110       | RPD       | 113       | 113       | RPD       | MGEFF     | MGEFF     | RPD       |
|-----------------------------|------------|------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Date                        | 10/30/2003 | 10/30/2003 | 1/14/2004 | 3/13/2003 | 3/13/2003 | 1/14/2004 | 8/26/2003 | 8/26/2003 | 1/14/2004 | 6/2/2003  | 6/2/2003  | 1/14/2004 |
| Lab                         | TriMatrix  | TriMatrix  |           | TriMatrix | TriMatrix |           | TriMatrix | TriMatrix |           | TriMatrix | TriMatrix |           |
| Dup                         |            | DUP        |           | DUP       | DUP       |           | DUP       | DUP       |           | DUP       | DUP       |           |
| 1,1-Dichloroethane          | <1.0       | <1.0       |           | <10       | <10       |           | <5.0      | <10       |           | <1.0      | <1.0      |           |
| 1,2-Dichloroethane          | <1.0       | <1.0       |           | <10       | <10       |           | <5.0      | <10       |           | <1.0      | <1.0      |           |
| 1,2-Dichloroethylene, cis   | <1.0       | <1.0       |           | 73        | 67        | 8.6       | 19        | 20        | 5.1       | 2.5       | 1.7       | 38        |
| 1,2-Dichloroethylene, trans | <1.0       | <1.0       |           | <10       | <10       |           | <5.0      | <10       |           | <1.0      | <1.0      |           |
| 1,1,2,2-Tetrachloroethane   | <1.0       | <1.0       |           | <10       | <10       |           | <5.0      | <10       |           | <1.0      | <1.0      |           |
| Tetrachloroethylene         | <1.0       | <1.0       |           | <10       | <10       |           | <5.0      | <10       |           | <1.0      | <1.0      |           |
| 1,1,1-Trichloroethane       | 1.2        | 1.2        | 0         | <10       | <10       |           | <5.0      | <10       |           | <1.0      | <1.0      |           |
| Trichloroethylene           | 15         | 16         | 6.5       | 340       | 350       | 2.9       | 90        | 100       | 11        | 12        | 12        | 0         |
| Benzene                     | <1.0       | <1.0       |           | <10       | <10       |           | <5.0      | <10       |           | 1.0       | 1.0       | 0         |
| Toluene                     | <1.0       | <1.0       |           | <10       | <10       |           | <5.0      | <10       |           | <1.0      | <1.0      |           |
| Vinyl chloride              | <1.0       | <1.0       |           | <10       | <10       |           | <5.0      | <10       |           | <1.0      | <1.0      |           |
| Xylenes total               | <3.0       | <3.0       |           | <30       | <30       |           | <15       | <30       |           | <3.0      | <3.0      |           |
| Sum Volatile Organics       | 16.2       | 17.2       |           | 413       | 417       |           | 109       | 120       |           | 15.5      | 14.7      |           |

-- Not analyzed.



## Appendix D

### Historical Water Quantity, Water Quality Data, and Bank Construction Information



## **Appendix D**

### **Historic Water Elevation, Water Quality Data, And Well Construction Information**

#### **List of Tables**

|            |  |
|------------|--|
| Table D-1  | Historic Water Elevation Data, Glacial Drift Wells   |
| Table D-2  | Historic Water Elevation Data, Carimona Member Wells   |
| Table D-3  | Historic Water Elevation Data, Magnolia Member Wells   |
| Table D-4  | Historic Water Elevation Data, St. Peter Sandstone Wells   |
| Table D-5  | Historic Water Elevation Data, Glacial Drift Pump-out Wells  |
| Table D-6  | Historic Water Quality Data, Glacial Drift Wells, Trichloroethene  |
| Table D-7  | Historic Water Quality Data, Carimona Member Wells, Trichloroethene  |
| Table D-8  | Historic Water Quality Data, Magnolia Member Wells, Trichloroethene  |
| Table D-9  | Historic Water Quality Data, St. Peter Sandstone Wells, Trichloroethene  |
| Table D-10 | Historic Water Quality Data, Prairie du Chien/Jordan Well, Trichloroethene                                     |
| Table D-11 | Historic Water Quality Data, Site Pump-out and Treatment System, Downgradient Pump-out System, Trichloroethene |
| Table D-12 | Historic Water Quality in Monitoring and Recovery Wells – BTEX   |
| Table D-13 | Well Construction Information  |



Table D-1  
Historical Water Elevation Data  
Glacial Drift Wells  
(elevations in ft.-MSL)

| Location   | 1      | 3      | 4      | 106    | 107    | B      | Q      | R      | S      | T      | U      | V      | W      | X      | Y      | Z      |
|------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| 10/30/1981 | --     | --     | --     | --     | --     | 843.31 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 02/09/1982 | --     | --     | --     | --     | --     | 844.45 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 02/16/1982 | 843.19 | --     | --     | --     | --     | 842.78 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 02/26/1982 | 842.37 | --     | --     | --     | --     | 842.77 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 03/04/1982 | 842.37 | --     | --     | --     | --     | 842.84 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 03/12/1982 | 842.28 | --     | --     | --     | --     | 842.72 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 03/17/1982 | 842.29 | --     | --     | --     | --     | 842.68 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 03/25/1982 | 842.63 | 835.95 | 833.20 | --     | --     | 824.89 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 04/01/1982 | 842.56 | 836.08 | 833.23 | --     | --     | 842.96 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 04/05/1982 | 842.54 | 836.07 | 833.30 | --     | --     | 843.03 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 04/08/1982 | 842.59 | 836.12 | 833.35 | --     | --     | 843.03 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 04/19/1982 | 842.78 | 836.36 | 833.50 | --     | --     | 843.14 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 11/18/1982 | 843.70 | 836.48 | 833.89 | --     | --     | 843.56 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 12/01/1982 | --     | --     | --     | --     | --     | 843.59 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 02/11/1983 | 842.96 | 836.16 | 833.53 | --     | --     | 843.30 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 04/06/1983 | 843.44 | 836.88 | 834.11 | --     | --     | 844.13 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 04/28/1983 | --     | --     | --     | 840.25 | 840.19 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 06/06/1983 | 842.90 | 837.58 | 834.88 | 839.40 | 839.25 | 844.37 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 09/22/1983 | 842.67 | --     | --     | 838.80 | 838.68 | 844.14 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 09/26/1983 | --     | 836.95 | 834.38 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 11/11/1983 | 842.57 | 826.67 | 824.02 | 838.57 | --     | 844.01 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 01/09/1984 | 843.49 | 830.13 | 834.07 | 839.40 | 837.36 | 843.93 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 01/16/1984 | --     | --     | --     | 838.48 | 838.41 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 02/15/1984 | --     | --     | --     | --     | --     | --     | 830.49 | 827.64 | 829.85 | 832.38 | 837.07 | --     | --     | --     | --     | --     |
| 03/28/1984 | --     | 837.23 | 834.20 | 838.68 | 838.65 | 844.13 | 832.08 | 829.15 | 831.21 | 833.89 | 838.82 | 818.16 | 818.25 | 829.00 | 821.15 | 810.0  |
| 10/15/1985 | 842.68 | 836.57 | --     | --     | 838.42 | 843.89 | 831.58 | 829.00 | 832.00 | 833.96 | 838.11 | 818.61 | 818.49 | 831.59 | 818.93 | 811.33 |
| 10/28/1985 | --     | --     | --     | 838.52 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 12/04/1985 | 842.38 | 835.19 | 833.40 | 837.12 | 836.96 | 843.86 | 831.22 | 828.73 | 830.95 | 833.37 | 837.30 | 817.99 | 817.96 | 829.02 | 818.84 | 810.36 |
| 07/06/1987 | 842.0  | 832.75 | --     | --     | --     | --     | --     | DRY    | 824.91 | 831.74 | --     | 815.3  | 814.4  | DRY    | --     | --     |
| 10/01/1987 | 842.34 | 834.30 | --     | --     | --     | --     | --     | --     | 826.36 | 832.72 | --     | 815.93 | 816.10 | --     | --     | --     |
| 04/05/1988 | 841.90 | 832.89 | 830.23 | 835.63 | 835.54 | 843.38 | 826.86 | --     | 824.94 | 831.80 | 835.58 | 814.51 | 814.59 | DRY    | --     | --     |
| 07/11/1988 | 841.69 | 832.45 | --     | --     | --     | --     | 826.46 | DRY    | 824.63 | 832.44 | --     | 814.03 | 814.03 | DRY    | --     | --     |
| 10/26/1988 | 841.77 | 833.00 | --     | --     | --     | --     | 826.77 | DRY    | 824.92 | 833.03 | --     | 814.44 | 814.54 | DRY    | --     | --     |
| 04/03/1989 | 841.74 | 833.30 | 830.79 | --     | 835.34 | 843.17 | 827.45 | DRY    | 825.23 | 832.25 | 835.72 | 814.19 | 814.34 | DRY    | --     | --     |
| 07/12/1989 | 841.75 | 833.76 | --     | --     | --     | --     | 827.95 | DRY    | 825.55 | 832.41 | --     | 814.77 | 814.86 | 822.05 | --     | --     |
| 10/09/1989 | --     | 833.98 | --     | --     | --     | --     | 828.26 | DRY    | 826.45 | 832.23 | --     | 815.16 | 815.26 | DRY    | --     | --     |
| 10/13/1989 | 841.72 | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     | --     |
| 05/14/1990 | --     | 833.65 | 830.43 | --     | --     | --     | 827.08 | DRY    | 825.92 | 832.14 | 835.86 | 814.64 | 814.38 | 822.07 | --     | --     |



**Table D-1**  
**Historical Water Elevation Data**  
**Glacial Drift Wells**  
**(elevations in ft.-MSL)**

| Location   | 1      | 3      | 4  | 106    | 107    | B      | Q      | R   | S      | T      | U      | V      | W      | X      | Y  | Z  |
|------------|--------|--------|----|--------|--------|--------|--------|-----|--------|--------|--------|--------|--------|--------|----|----|
| 07/10/1990 | 841.90 | 834.35 | -- | 836.36 | 836.17 | 844.33 | 828.50 | DRY | 827.38 | 832.89 | --     | 816.65 | 816.75 | 822.95 | -- | -- |
| 10/08/1990 | 841.69 | 834.15 | -- | --     | --     | --     | 828.28 | DRY | 827.43 | 832.62 | --     | 816.70 | 816.80 | 823.08 | -- | -- |
| 04/01/1991 | 841.36 | 832.92 | -- | --     | --     | 842.76 | 827.43 | --  | 825.96 | 832.14 | 835.35 | 815.60 | 815.69 | DRY    | -- | -- |
| 09/25/1991 | 842.02 | 834.25 | -- | --     | --     | 843.46 | 828.90 | --  | 828.42 | 833.06 | 836.54 | 818.19 | 818.18 | 824.25 | -- | -- |
| 05/11/1992 | 841.96 | 834.19 | -- | --     | --     | 843.40 | 828.80 | --  | 828.55 | 833.05 | 836.50 | 817.77 | 817.81 | 823.41 | -- | -- |
| 11/02/1992 | 841.98 | 834.02 | -- | --     | --     | 843.43 | 828.88 | --  | 828.09 | 832.61 | 836.21 | 817.27 | 817.44 | 824.05 | -- | -- |
| 05/18/1993 | 842.00 | 833.85 | -- | --     | --     | 843.47 | 828.18 | --  | 827.04 | 832.56 | 836.22 | 816.13 | 816.29 | 822.55 | -- | -- |
| 11/22/1993 | 842.17 | 834.07 | -- | --     | --     | 843.64 | 828.42 | DRY | 828.07 | 833.74 | 836.42 | 817.17 | 817.23 | 823.81 | -- | -- |
| 08/03/1994 | --     | --     | -- | --     | --     | --     | 827.96 | --  | --     | 832.78 | --     | 816.53 | 816.66 | 822.63 | -- | -- |
| 09/25/1995 | --     | --     | -- | --     | --     | --     | 828.27 | --  | --     | 833.03 | --     | 817.18 | 817.29 | 823.02 | -- | -- |
| 08/13/1996 | --     | --     | -- | --     | --     | --     | 828.23 | --  | --     | 833.30 | --     | 815.94 | 816.10 | 822.86 | -- | -- |
| 08/19/1997 | --     | --     | -- | --     | --     | --     | 829.05 | --  | --     | 833.41 | --     | 819.59 | 819.31 | 822.86 | -- | -- |
| 10/13/1998 | --     | --     | -- | --     | --     | --     | 828.16 | --  | --     | 832.46 | --     | 817.14 | 817.28 | 822.96 | -- | -- |
| 12/06/1999 | --     | --     | -- | --     | --     | --     | 829.05 | --  | --     | 832.86 | --     | 817.21 | 817.27 | 824.06 | -- | -- |
| 11/16/2000 | --     | --     | -- | --     | --     | --     | 827.69 | DRY | 826.95 | 832.32 | --     | 816.91 | 817.06 | 822.36 | -- | -- |
| 12/04/2001 | --     | --     | -- | --     | --     | --     | 828.57 | --  | 827.31 | 832.50 | --     | 817.44 | 817.53 | 822.85 | -- | -- |
| 11/26/2002 | --     | --     | -- | --     | --     | --     | 828.25 | --  | --     | 832.65 | --     | 818.38 | 818.27 | 823.32 | -- | -- |
| 10/27/2003 | --     | --     | -- | --     | --     | --     | 828.18 | --  | --     | 832.50 | --     | 818.02 | 817.97 | 823.07 | -- | -- |

-- Not measured.



**Table D-2**  
**Historical Water Elevation Data**  
**Carimona Member Wells**  
**(elevations in ft.-MSL)**

| Location   | 8      | 9      | 10     | 11     | 12     | 13     | 108 (1) | BB     | RR     | SS     | UU     | WW     |
|------------|--------|--------|--------|--------|--------|--------|---------|--------|--------|--------|--------|--------|
| 10/30/1981 | --     | --     | --     | --     | --     | --     | --      | 828.09 | --     | --     | --     | --     |
| 11/24/1981 | --     | --     | --     | --     | --     | --     | --      | 827.85 | --     | --     | --     | --     |
| 02/09/1982 | --     | --     | --     | --     | --     | --     | --      | 829.87 | --     | --     | --     | --     |
| 02/16/1982 | --     | --     | --     | --     | --     | --     | --      | 827.85 | --     | --     | --     | --     |
| 02/26/1982 | --     | --     | --     | --     | --     | --     | --      | 827.77 | --     | --     | --     | --     |
| 03/04/1982 | --     | --     | --     | --     | --     | --     | --      | 827.85 | --     | --     | --     | --     |
| 03/12/1982 | --     | --     | --     | --     | --     | --     | --      | 828.61 | --     | --     | --     | --     |
| 03/17/1982 | --     | --     | --     | --     | --     | --     | --      | 827.81 | --     | --     | --     | --     |
| 03/19/1982 | --     | --     | --     | --     | --     | --     | --      | --     | 827.73 | --     | --     | --     |
| 03/25/1982 | --     | --     | --     | --     | --     | --     | --      | 827.76 | 827.73 | --     | --     | --     |
| 04/01/1982 | --     | --     | --     | --     | --     | --     | --      | 827.89 | 827.76 | --     | --     | --     |
| 04/05/1982 | --     | --     | --     | --     | --     | --     | --      | 827.82 | --     | --     | --     | --     |
| 04/08/1982 | --     | --     | --     | --     | --     | --     | --      | 827.82 | 827.57 | --     | --     | --     |
| 04/19/1982 | --     | --     | --     | --     | --     | --     | --      | 828.08 | 828.17 | --     | --     | --     |
| 11/18/1982 | 828.91 | --     | --     | --     | --     | --     | --      | 829.07 | 829.12 | 835.43 | 828.85 | 828.91 |
| 12/01/1982 | --     | --     | --     | --     | --     | --     | --      | 829.18 | 829.22 | 835.67 | 831.10 | 829.08 |
| 02/11/1983 | --     | --     | --     | --     | --     | --     | --      | 828.89 | 828.98 | 834.07 | 828.98 | 828.76 |
| 02/14/1983 | --     | --     | --     | --     | --     | --     | --      | --     | --     | 834.25 | --     | --     |
| 04/06/1983 | --     | --     | --     | --     | --     | --     | --      | 829.69 | 829.72 | 834.13 | 829.54 | 829.48 |
| 04/28/1983 | 836.76 | --     | --     | --     | --     | --     | --      | --     | --     | --     | --     | --     |
| 06/06/1983 | 835.81 | --     | --     | --     | --     | --     | --      | 829.96 | 829.97 | 834.29 | 829.86 | 829.77 |
| 09/22/1983 | 838.68 | --     | --     | --     | --     | --     | --      | 829.66 | --     | --     | --     | --     |
| 09/23/1983 | 835.51 | --     | --     | --     | --     | --     | --      | --     | --     | 823.15 | 829.55 | 829.45 |
| 09/26/1983 | --     | --     | --     | --     | --     | --     | --      | --     | 829.53 | --     | --     | --     |
| 11/11/1983 | 829.98 | 830.06 | 830.03 | 830.02 | 832.30 | --     | 830.12  | 830.15 | 830.08 | 833.90 | 830.24 | 829.95 |
| 01/09/1984 | 829.85 | 829.86 | 829.88 | 829.93 | --     | --     | --      | 829.84 | --     | 833.55 | 829.80 | 829.69 |
| 01/16/1984 | 830.1  | 830.08 | 830.12 | 830.13 | 831.76 | --     | 830.65  | 830.12 | 828.99 | 833.50 | 830.02 | 829.94 |
| 03/28/1984 | 830.15 | 830.21 | 830.21 | 830.18 | 831.43 | 830.21 | 830.92  | 830.25 | 830.16 | 832.34 | 830.18 | 830.08 |
| 10/15/1985 | 830.58 | 830.61 | 830.62 | 830.65 | 832.11 | 830.01 | 830.77  | 830.26 | 830.19 | 831.76 | 830.63 | 830.60 |
| 12/04/1985 | 829.71 | 830.05 | 829.86 | 829.73 | 831.50 | 829.25 | --      | 829.76 | 829.90 | 830.59 | 829.88 | 829.79 |
| 12/05/1985 | --     | --     | --     | --     | --     | --     | 812.90  | --     | --     | --     | --     | --     |
| 07/06/1987 | 827.10 | 827.3  | 827.28 | 827.26 | 827.83 | 826.49 | 805.9   | --     | 827.11 | 826.18 | --     | --     |
| 10/01/1987 | 828.79 | 828.69 | 828.72 | 828.79 | 828.63 | 828.14 | 806.06  | --     | 828.82 | 827.27 | --     | --     |
| 04/05/1988 | 827.71 | 827.85 | 827.86 | 827.74 | 828.12 | 827.05 | 804.57  | 827.81 | 827.85 | 826.22 | 827.72 | 827.71 |
| 07/11/1988 | 824.91 | 825.12 | 825.07 | 824.97 | 825.40 | 824.36 | 804.45  | --     | 825.11 | 824.05 | --     | --     |
| 10/26/1988 | 826.83 | 826.98 | 826.99 | 826.86 | 826.61 | 826.17 | 804.49  | --     | 826.95 | 825.37 | --     | --     |
| 04/03/1989 | 827.13 | 827.37 | 827.37 | 827.16 | 827.20 | 826.63 | 807.81  | 827.34 | 827.35 | 825.54 | 827.31 | 827.31 |



**Table D-2**  
**Historical Water Elevation Data**  
**Carimona Member Wells**  
**(elevations in ft.-MSL)**

| Location   | 8      | 9      | 10     | 11     | 12     | 13     | 108 (1) | BB     | RR     | SS     | UU     | WW     |
|------------|--------|--------|--------|--------|--------|--------|---------|--------|--------|--------|--------|--------|
| 07/12/1989 | 825.41 | 825.64 | 825.59 | 825.43 | 826.18 | 824.74 | 804.51  | --     | 825.65 | 823.62 | --     | --     |
| 10/09/1989 | 827.32 | 827.52 | 827.82 | 827.37 | 826.70 | 826.78 | --      | --     | --     | 825.12 | --     | --     |
| 10/13/1989 | --     | --     | --     | --     | --     | --     | 827.49  | --     | 827.57 | --     | --     | --     |
| 05/14/1990 | 827.06 | 827.38 | 827.26 | 827.31 | 827.52 | 826.65 | --      | --     | 827.41 | 824.77 | 827.28 | 827.27 |
| 07/10/1990 | 827.92 | 828.18 | 828.10 | 827.84 | 826.73 | 827.20 | 804.54  | 828.01 | 827.98 | 827.05 | --     | --     |
| 10/08/1990 | 828.38 | 828.59 | 828.58 | 828.41 | 828.23 | 827.78 | 804.64  | --     | 828.48 | 826.74 | --     | --     |
| 04/01/1991 | 828.63 | 828.84 | 828.83 | 828.70 | 828.92 | 828.06 | 807.87  | 828.75 | 828.76 | 826.42 | 828.69 | 828.66 |
| 09/25/1991 | 829.19 | 829.40 | 829.40 | 829.15 | 828.46 | 828.55 | 804.55  | 829.25 | 829.41 | 826.95 | 829.23 | 831.23 |
| 01/03/1992 | --     | --     | --     | --     | --     | --     | 830.22  | --     | --     | --     | --     | --     |
| 05/11/1992 | 828.87 | 829.02 | 829.01 | 828.93 | 829.26 | 828.29 | 805.36  | 828.93 | 829.08 | 826.42 | 828.92 | 828.89 |
| 11/02/1992 | 828.81 | 828.98 | 829.03 | 828.85 | 827.60 | 828.23 | 829.22  | 828.65 | 829.01 | 824.50 | 828.93 | 828.86 |
| 05/18/1993 | 827.37 | 827.38 | 827.58 | 827.39 | 826.95 | 826.72 | 824.46  | 827.16 | 827.48 | 822.62 | 827.40 | 827.04 |
| 11/22/1993 | 829.26 | 829.34 | 829.45 | 829.56 | 828.36 | 828.89 | 829.53  | 829.29 | 829.63 | 823.68 | 829.50 | 829.50 |
| 08/03/1994 | 827.58 | 827.59 | 827.67 | 827.85 | 826.94 | --     | --      | --     | --     | 822.79 | 827.90 | --     |
| 09/25/1995 | 829.76 | 829.98 | 829.96 | 829.78 | 828.18 | --     | --      | --     | 829.95 | 824.46 | 829.83 | 829.79 |
| 01/03/1996 | --     | 829.53 | --     | --     | --     | --     | --      | --     | --     | --     | --     | --     |
| 08/13/1996 | 827.95 | 828.16 | 827.94 | 827.99 | 827.20 | --     | --      | --     | 828.14 | 821.98 | 827.95 | 828.01 |
| 08/19/1997 | 830.92 | 831.24 | 831.84 | 831.99 | 829.35 | --     | --      | --     | 830.38 | 824.40 | 832.33 | 830.26 |
| 10/13/1998 | 831.61 | 831.78 | 831.77 | 831.69 | 830.10 | --     | --      | --     | --     | 825.97 | 831.68 | --     |
| 12/22/1998 | --     | --     | --     | --     | --     | --     | --      | --     | 830.25 | 822.95 | --     | 830.12 |
| 12/23/1998 | --     | --     | --     | --     | --     | --     | --      | --     | 832.75 | 829.02 | --     | 832.63 |
| 12/06/1999 | 831.15 | 831.40 | 831.41 | 831.42 | 829.92 | --     | --      | --     | 831.36 | 824.39 | 831.41 | 831.28 |
| 11/16/2000 | 829.07 | 829.17 | 829.23 | 828.89 | 827.88 | --     | --      | --     | 829.01 | 822.27 | 828.87 | 828.92 |
| 11/21/2000 | --     | --     | --     | --     | --     | --     | --      | --     | 829.01 | 822.83 | --     | 828.92 |
| 11/22/2000 | --     | --     | --     | --     | --     | --     | --      | --     | 831.27 | 828.17 | --     | 831.18 |
| 12/04/2001 | 829.90 | 830.10 | 830.10 | 829.95 | 828.78 | --     | --      | --     | 830.04 | 823.32 | 829.92 | 829.94 |
| 12/05/2001 | --     | --     | --     | --     | --     | --     | --      | --     | 832.23 | 829.43 | --     | 832.12 |
| 11/26/2002 | 831.06 | 831.28 | 831.27 | 831.14 | 829.94 | --     | --      | --     | 831.21 | 823.87 | 831.09 | 830.91 |
| 11/27/2002 | --     | --     | --     | --     | --     | --     | --      | --     | 833.67 | 830.05 | --     | 833.57 |
| 10/27/2003 | 831.22 | 831.27 | 831.46 | 831.08 | 825.42 | --     | --      | --     | 831.22 | 824.26 | 831.09 | 831.10 |
| 10/28/2003 | --     | --     | --     | --     | --     | --     | --      | --     | 833.52 | 829.13 | --     | 833.41 |

-- Not measured

(1) Carimona pump-out well



**Table D-3**  
**Historical Water Elevation Data**  
**Magnolia Member Wells**  
**(elevations in ft.-MSL)**

| Location   | OO     | QQ     | TT     | VV     | ZZ     | 14 |
|------------|--------|--------|--------|--------|--------|----|
| 03/09/1982 | 823.60 | --     | --     | --     | --     | -- |
| 03/17/1982 | --     | 823.25 | --     | --     | --     | -- |
| 03/19/1982 | 823.60 | 823.34 | --     | --     | --     | -- |
| 03/25/1982 | 823.48 | 823.29 | --     | --     | --     | -- |
| 04/01/1982 | 823.64 | 823.37 | --     | --     | --     | -- |
| 04/08/1982 | 823.72 | 823.42 | --     | --     | --     | -- |
| 04/19/1982 | 823.99 | 823.75 | --     | --     | --     | -- |
| 11/18/1982 | 824.96 | 824.61 | 822.41 | 825.57 | --     | -- |
| 12/01/1982 | 824.79 | 824.41 | 822.59 | 825.76 | --     | -- |
| 02/11/1983 | 825.51 | 823.57 | 822.34 | 825.50 | --     | -- |
| 02/14/1983 | --     | --     | 822.62 | --     | --     | -- |
| 04/06/1983 | 825.29 | 823.00 | 822.90 | 826.32 | --     | -- |
| 06/06/1983 | 825.80 | 825.61 | 823.60 | 826.43 | --     | -- |
| 09/23/1983 | --     | --     | 829.55 | 826.18 | --     | -- |
| 09/26/1983 | 824.71 | 825.20 | --     | --     | --     | -- |
| 11/11/1983 | 825.69 | 825.44 | 823.44 | 826.52 | --     | -- |
| 01/16/1984 | 825.46 | --     | 823.26 | 826.32 | --     | -- |
| 03/28/1984 | 825.78 | 825.61 | 823.54 | 826.64 | 830.2  | -- |
| 02/14/1985 | --     | --     | 822.62 | --     | --     | -- |
| 10/15/1985 | 825.76 | 825.46 | 823.26 | 826.99 | 830.67 | -- |
| 12/04/1985 | 825.57 | 825.39 | 822.74 | 826.24 | 830.65 | -- |
| 02/05/1986 | 824.74 | 824.49 | 822.10 | 825.60 | 830.05 | -- |
| 04/01/1986 | 824.75 | 824.52 | 822.10 | 825.60 | 829.65 | -- |
| 06/06/1986 | 824.89 | 824.68 | 822.31 | 825.66 | 828.31 | -- |
| 08/01/1986 | 824.86 | 824.71 | 822.32 | 825.65 | 829.44 | -- |
| 10/22/1986 | 825.49 | 825.24 | 822.90 | 826.33 | 830.45 | -- |
| 04/03/1987 | 823.87 | 823.66 | 821.46 | 824.83 | 829.25 | -- |
| 07/06/1987 | 822.85 | 822.53 | 820.42 | 823.42 | 827.93 | -- |
| 10/01/1987 | 824.24 | 823.96 | 821.77 | 824.99 | 829.98 | -- |
| 04/05/1988 | 823.31 | 823.03 | 820.91 | 824.14 | 828.44 | -- |
| 07/11/1988 | 821.14 | 820.82 | 818.88 | 821.73 | 825.73 | -- |
| 10/26/1988 | 822.46 | 822.11 | 820.13 | 823.34 | 827.57 | -- |
| 04/03/1989 | 822.82 | 822.47 | 820.46 | 823.75 | 828.72 | -- |
| 07/12/1989 | 821.66 | 821.32 | 819.38 | 822.36 | 826.05 | -- |
| 10/09/1989 | 823.07 | 822.70 | 820.69 | 823.98 | 828.20 | -- |
| 05/14/1990 | 822.79 | 822.51 | 820.42 | 823.65 | 828.04 | -- |
| 07/10/1990 | 823.67 | 823.36 | 821.35 | 824.57 | 828.65 | -- |



**Table D-3**  
**Historical Water Elevation Data**  
**Magnolia Member Wells**  
**(elevations in ft.-MSL)**

| Location   | OO     | QQ     | TT     | VV     | ZZ     | 14     |
|------------|--------|--------|--------|--------|--------|--------|
| 10/08/1990 | 823.99 | 823.73 | 821.56 | 824.88 | 829.16 | --     |
| 04/01/1991 | 824.52 | 824.25 | 821.75 | 825.46 | 829.44 | --     |
| 09/25/1991 | 825.50 | 825.19 | 823.05 | 826.28 | 829.94 | --     |
| 05/11/1992 | 825.10 | 824.82 | 822.63 | 825.87 | 829.66 | --     |
| 11/02/1992 | 820.27 | 820.33 | 817.29 | 822.01 | 829.61 | --     |
| 05/18/1993 | 820.42 | 818.46 | 815.64 | 820.33 | 828.12 | --     |
| 11/22/1993 | 820.28 | 820.31 | 817.42 | 822.23 | 830.26 | --     |
| 08/03/1994 | --     | 818.90 | 816.30 | --     | --     | --     |
| 09/25/1995 | 820.19 | 820.23 | 817.47 | 822.25 | --     | --     |
| 08/13/1996 | 818.66 | 818.66 | 816.01 | 820.74 | --     | --     |
| 08/19/1997 | 821.07 | 827.46 | 818.24 | 823.09 | --     | --     |
| 10/13/1998 | --     | 824.01 | 822.04 | --     | --     | 821.63 |
| 12/22/1998 | 819.57 | --     | 816.60 | 822.00 | --     | --     |
| 12/23/1998 | 827.92 | --     | 826.14 | 828.93 | --     | --     |
| 12/06/1999 | 821.05 | 821.10 | 818.23 | 823.42 | --     | 817.53 |
| 11/16/2000 | 818.70 | 818.76 | 815.99 | 820.93 | --     | 815.41 |
| 11/21/2000 | 818.70 | --     | 816.02 | 820.93 | --     | --     |
| 11/22/2000 | 826.21 | --     | 824.80 | 827.07 | --     | --     |
| 12/04/2001 | 819.80 | 819.93 | 816.88 | 822.23 | --     | 816.46 |
| 12/05/2001 | 827.37 | --     | 825.83 | 828.32 | --     | --     |
| 11/26/2002 | 820.41 | 820.61 | 817.15 | 823.23 | --     | 816.54 |
| 11/27/2002 | 828.81 | --     | 827.14 | 829.88 | --     | --     |
| 10/27/2003 | 820.43 | 820.70 | 817.16 | 823.44 | --     | 816.50 |
| 10/28/2003 | 828.52 | --     | 826.86 | 829.63 | --     | --     |

-- Not measured



**Table D-4**  
**Historical Water Elevation Data**  
**St. Peter Sandstone Wells**  
**(elevations in ft.-MSL)**

| Location   | 200    | 201    | 202    | 203    |
|------------|--------|--------|--------|--------|
|            |        |        |        |        |
| 10/15/1985 | --     | 779.64 | 751.98 | 752.05 |
| 12/04/1985 | 758.68 | --     | 752.60 | 757.58 |
| 12/05/1985 | --     | 780.24 | --     | --     |
| 07/06/1987 | 760.63 | 777.82 | 753.86 | 753.43 |
| 10/01/1987 | 760.47 | 779.35 | 753.28 | 753.42 |
| 04/05/1988 | 761.89 | 780.40 | 753.36 | 753.37 |
| 07/11/1988 | 758.57 | 773.59 | 752.28 | 752.10 |
| 10/26/1988 | 760.78 | 778.42 | 752.53 | 752.43 |
| 04/03/1989 | 762.22 | 779.61 | 753.67 | 753.57 |
| 07/12/1989 | 758.96 | 775.98 | 752.77 | 752.37 |
| 10/09/1989 | 760.36 | 777.25 | 752.70 | 752.43 |
| 05/14/1990 | 761.79 | 778.59 | 753.72 | 753.29 |
| 07/10/1990 | 759.54 | 776.15 | 753.16 | 752.61 |
| 10/08/1990 | 759.90 | 776.67 | 752.44 | 751.93 |
| 04/01/1991 | 761.75 | 778.01 | 753.50 | 752.94 |
| 09/25/1991 | 761.38 | 778.26 | 753.38 | 752.96 |
| 05/11/1992 | 762.57 | 778.37 | 754.73 | 754.01 |
| 11/02/1992 | 763.44 | 780.11 | 754.93 | 754.23 |
| 05/18/1993 | 763.12 | 778.52 | 754.94 | 754.05 |
| 11/22/1993 | 764.00 | 780.11 | 754.86 | 753.79 |
| 08/03/1994 | 760.90 | --     | --     | --     |
| 12/20/1994 | 764.19 | --     | --     | --     |
| 09/25/1995 | 763.78 | --     | --     | --     |
| 08/13/1996 | 762.45 | --     | --     | --     |
| 07/02/1997 | 763.31 | 779.21 | 755.20 | 754.47 |
| 08/19/1997 | 762.59 | 777.82 | 753.86 | 753.49 |
| 10/13/1998 | 763.58 | 778.53 | 753.55 | 753.15 |
| 12/06/1999 | 764.97 | 779.76 | 754.04 | 753.68 |
| 11/16/2000 | 765.75 | 779.48 | 754.03 | 754.02 |
| 12/04/2001 | 766.10 | 780.84 | 754.72 | 754.08 |
| 11/26/2002 | 766.58 | 779.72 | 754.15 | 753.74 |
| 10/27/2003 | 766.23 | 779.59 | 754.56 | 754.41 |

-- Not analyzed.



**Table D-5**  
**Historical Water Elevation Data**  
**Glacial Drift Pump-Out Wells**  
**(elevations in ft.-MSL)**

| Location   | 109    | 110 (1) | 111 (2) | 112 (2) | 113 (2) |
|------------|--------|---------|---------|---------|---------|
|            |        |         |         |         |         |
| 10/15/1985 | 837.21 | 835.62  | 829.25  | 829.10  | 829.20  |
| 12/04/1985 | --     | 829.11  | 828.83  | 828.59  | 828.77  |
| 12/05/1985 | 828.19 | --      | --      | --      | --      |
| 07/06/1987 | 831.26 | 829.63  | 816.75  | 811.67  | 814.24  |
| 10/01/1987 | 829.94 | 828.98  | 813.70  | 814.64  | 815.68  |
| 04/05/1988 | 828.90 | 823.37  | 808.70  | 811.81  | 813.00  |
| 07/11/1988 | 831.00 | 822.35  | 815.35  | 807.91  | 812.63  |
| 10/26/1988 | 829.99 | 829.52  | 815.62  | 811.68  | 813.15  |
| 04/03/1989 | 831.41 | 828.90  | 818.43  | 811.80  | 817.22  |
| 05/14/1990 | --     | 830.71  | 818.20  | 807.67  | 817.96  |
| 07/10/1990 | 827.27 | 831.02  | 819.07  | 811.77  | 818.80  |
| 10/08/1990 | 829.63 | 831.51  | 819.23  | 811.03  | 819.12  |
| 04/01/1991 | 826.58 | 826.60  | 817.98  | 808.26  | 817.91  |
| 09/25/1991 | 830.56 | 829.33  | 820.19  | 816.07  | 820.27  |
| 01/03/1992 | 826.56 | 828.73  | 819.50  | 812.12  | 819.42  |
| 05/11/1992 | 827.20 | 829.41  | 819.34  | 812.17  | 820.21  |
| 11/02/1992 | 827.67 | 830.60  | 820.15  | 815.62  | 820.43  |
| 05/18/1993 | 827.24 | 829.56  | 818.46  | 807.05  | 818.74  |
| 11/22/1993 | 828.06 | 830.81  | 819.26  | 810.43  | 819.83  |
| 08/13/1996 | 835.18 | 829.93  | 817.84  | 816.22  | 818.41  |
| 08/19/1997 | 828.12 | 830.40  | 819.10  | 813.22  | 819.62  |
| 10/13/1998 | 827.02 | 829.08  | 817.79  | 807.37  | 818.82  |
| 12/06/1999 | 835.37 | --      | 825.82  | 815.79  | 820.24  |
| 11/16/2000 | 828.78 | --      | 817.09  | 809.53  | 817.81  |
| 12/04/2001 | 828.27 | --      | 818.03  | 812.83  | 818.51  |
| 11/26/2002 | 828.17 | 828.65  | 818.13  | 816.88  | 819.17  |
| 10/27/2003 | 829.02 | 827.95  | 817.68  | 807.87  | 819.06  |

-- Not analyzed.

(1) Site Glacial Drift pump-out well

(2) Down-Gradient drift pump-out wells



**Table D-6**  
**Historical Water Quality Data**  
**Glacial Drift Wells**  
**Trichloroethylene**  
**[Consent Order Limit: 270 ug/L]**  
**(concentrations in ug/L)**

| Location | B    | Q     | R    | S    | T     | U    | V   | W    | X     | 1     | 3    | 4   |
|----------|------|-------|------|------|-------|------|-----|------|-------|-------|------|-----|
| Apr-82   | 6.0  | --    | --   | --   | --    | --   | --  | --   | --    | 6.0   | 780  | 4.5 |
| Dec-82   | 1100 | --    | --   | --   | --    | --   | --  | --   | --    | --    | --   | --  |
| Dec-83   | 780  | --    | --   | --   | --    | --   | --  | --   | --    | 27    | 800  | 380 |
| Feb-84   | --   | <1.3  | 670  | 770  | <1.3  | <1.3 | --  | --   | --    | --    | --   | --  |
| Mar-84   | --   | --    | --   | --   | --    | --   | 78  | 7.5  | 2.2   | --    | --   | --  |
| Oct-85   | 1200 | 20    | 1100 | 740  | <0.3  | 2.6  | 220 | 8.1  | 2.1   | 1.4   | 1100 | --  |
| Nov-85   | --   | --    | --   | --   | --    | --   | --  | --   | --    | --    | --   | 440 |
| Dec-85   | 1100 | 14    | 820  | 750  | <0.8  | 3.9  | 140 | 32   | 5.0   | 1.5   | 770  | 440 |
| Feb-86   | 1300 | 11    | 31   | 650  | <0.5  | 2.9  | 180 | 14   | 0.9 s | 1.4 s | 680  | 200 |
| Apr-86   | 1000 | 13    | DRY  | 1100 | <0.2  | 3.2  | 170 | 18   | 0.9   | 3.1   | 1200 | 210 |
| Jun-86   | 1100 | 4.7   | 160  | 930  | <0.2  | 1.6  | 97  | 10   | 0.9   | 8.1   | 1300 | 180 |
| Aug-86   | 1000 | 5.6   | DRY  | 880  | <0.2  | 1.6  | 130 | 18   | 0.7   | 9.3   | 890  | 280 |
| Oct-86   | --   | 3.2   | --   | 620  | <0.2  | 1.4  | 92  | 6.2  | 0.5   | 0.9   | 720  | 200 |
| Nov-86   | 830  | --    | --   | --   | --    | --   | --  | --   | --    | --    | --   | --  |
| Apr-87   | 800  | 2.6   | DRY  | 650  | <0.2  | 2.7  | 160 | 24   | --    | 2.7   | 740  | 120 |
| Jul-87   | --   | --    | DRY  | 740  | --    | --   | 180 | 42   | --    | 0.4   | 770  | --  |
| Oct-87   | --   | --    | --   | 1000 | --    | --   | 140 | 56   | --    | 0.8   | 960  | --  |
| Apr-88*  | 330  | 0.86  | DRY  | 460  | <0.50 | --   | 160 | 43   | DRY   | <0.50 | 440  | 55  |
| Jul-88*  | --   | --    | DRY  | 160  | --    | --   | 33  | 8.1  | --    | 0.5   | 140  | --  |
| Oct-88*  | --   | --    | DRY  | 110  | --    | --   | 37  | 26   | --    | <0.5  | 98   | --  |
| Apr-89   | 250  | 1.1   | --   | 860  | <0.5  | --   | 130 | 57   | --    | 0.8   | 320  | 55  |
| Jul-89   | --   | --    | --   | 620  | --    | --   | 120 | 22   | --    | 0.6 s | 340  | --  |
| Oct-89   | --   | --    | --   | 630  | --    | --   | 120 | 25   | --    | 0.5   | 530  | --  |
| May-90   | --   | 0.7   | --   | 710  | <0.5  | --   | 110 | 31   | --    | --    | 520  | 77  |
| Jul-90   | 330  | --    | --   | 200  | --    | --   | 120 | <0.5 | --    | 0.8   | 770  | --  |
| Oct-90   | --   | --    | --   | 770  | --    | --   | 110 | 11   | --    | <0.5  | 310  | --  |
| Apr-91   | 340  | 0.7   | --   | 870  | <0.5  | 2.0  | 130 | 40   | --    | 3.1   | 1500 | --  |
| Sep-91   | --   | --    | --   | 480  | --    | --   | 73  | 20   | --    | 1.3   | 300  | --  |
| May-92   | 510  | <1.0  | --   | 510  | <1.0  | <1.0 | 63  | 5.9  | <1.0  | 2.2   | 400  | --  |
| Nov-92   | --   | --    | --   | 770  | --    | --   | 83  | 1.3  | --    | 0.5   | 170  | --  |
| May-93   | 580  | <0.50 | --   | 390  | <0.50 | 0.7  | 68  | 2.9  | <0.50 | <0.50 | 470  | --  |
| Nov-93   | --   | --    | --   | 400  | --    | --   | 100 | 2.9  | --    | <0.50 | 740  | --  |
| Aug-94   | --   | <0.5  | --   | --   | <0.5  | --   | 69  | 8.4  | <0.5  | --    | --   | --  |
| Sep-95   | --   | <0.50 | --   | --   | <0.50 | --   | 94  | 0.80 | <0.50 | --    | --   | --  |
| Aug-96   | --   | <0.5  | --   | --   | <0.5  | --   | 100 | 1.4  | <0.5  | --    | --   | --  |
| Aug-97   | --   | <0.5  | --   | --   | <0.5  | --   | 19  | 1.5  | <0.5  | --    | --   | --  |
| Oct-98   | --   | <0.5  | --   | --   | <0.5  | --   | 140 | 15   | <0.5  | --    | --   | --  |
| Dec-99   | --   | <1.0  | --   | --   | <1.0  | --   | 83  | 15   | <1.0  | --    | --   | --  |
| Nov-00   | --   | <1.0  | --   | --   | <1.0  | --   | 97  | 17   | <1.0  | --    | --   | --  |
| Dec-01   | --   | 1.6   | --   | --   | <1.0  | --   | 91  | 14   | <1.0  | --    | --   | --  |
| Dec-02   | --   | <1.0  | --   | --   | <1.0  | --   | 50  | 17   | <1.0  | --    | --   | --  |
| Oct-03   | --   | <1.0  | --   | --   | <1.0  | --   | 14  | 14   | <1.0  | --    | --   | --  |

-- Not analyzed

s Potential false positive value based on statistical analysis of blank sample data.

\* The 1988\* analytical data has been determined to be unreliable due to laboratory equipment and method performance problems.



**Table D-7**  
**Historical Water Quality Data**  
**Carimona Member Wells**  
**Trichloroethylene**  
**[Consent Order Limit: 27 ug/L]**  
**(concentrations in ug/L)**

| Location | 8    | 9     | 10   | 11   | 12    | 13    | 108  | BB   | RR  | SS    | UU  | WW   |
|----------|------|-------|------|------|-------|-------|------|------|-----|-------|-----|------|
| May-82   | --   | --    | --   | --   | --    | --    | --   | --   | 46  | --    | --  | --   |
| Jun-82   | --   | --    | --   | --   | --    | --    | --   | 1600 | --  | --    | --  | --   |
| Dec-82   | --   | --    | --   | --   | --    | --    | --   | 1600 | 43  | <0.05 | 78  | 2100 |
| Apr-83   | 820  | --    | --   | --   | --    | --    | --   | --   | --  | --    | --  | --   |
| Nov-83   | --   | --    | --   | --   | --    | --    | 1100 | --   | --  | --    | --  | --   |
| Dec-83   | 96   | <0.05 | 2.6  | 120  | <1.5  | --    | --   | 1400 | 33  | <1.5  | 81  | 1700 |
| Jan-84   | --   | --    | --   | --   | --    | --    | 1000 | --   | --  | --    | --  | --   |
| Jan-84   | --   | --    | --   | --   | --    | --    | 1100 | --   | --  | --    | --  | --   |
| Jan-84   | --   | --    | --   | --   | --    | --    | 1100 | --   | --  | --    | --  | --   |
| Jan-84   | --   | --    | --   | --   | --    | --    | 1100 | --   | --  | --    | --  | --   |
| Mar-84   | --   | --    | --   | --   | --    | 25    | --   | --   | --  | --    | --  | --   |
| Oct-85   | 2300 | 17    | 1500 | 2.7  | --    | 1.9   | --   | 1900 | 110 | 0.4 s | 150 | 2300 |
| Nov-85   | --   | --    | --   | --   | <0.2  | --    | 1500 | --   | --  | --    | --  | --   |
| Dec-85   | 650  | 10    | 1100 | 520  | <0.8  | 21    | 820  | 1100 | 95  | 1.2   | 79  | 1200 |
| Feb-86   | 240  | 6.7   | 420  | 250  | <0.5  | 9.7   | 700  | 1300 | 88  | <0.5  | 71  | 740  |
| Apr-86   | 180  | 8.0   | 290  | 120  | 0.5   | 120   | 750  | 2200 | 170 | 0.4   | 81  | 540  |
| Jun-86   | 140  | 6.1   | 280  | 58   | <0.2  | 130   | 640  | 2100 | 85  | 0.3   | 37  | 290  |
| Aug-86   | 160  | 6.7   | 270  | 67   | 0.2   | 14    | 580  | 1800 | 100 | 0.3   | 45  | 220  |
| Oct-86   | --   | 5.4   | --   | 40   | <0.2  | 0.5   | 540  | --   | --  | <0.2  | 36  | --   |
| Nov-86   | 110  | --    | 220  | --   | --    | --    | --   | 1300 | 100 | --    | --  | 290  |
| Apr-87   | 86   | 5.1   | 120  | 160  | <0.2  | 140   | 450  | 1100 | 110 | 1.2   | 12  | 290  |
| Jul-87   | --   | 0.6   | 150  | 25   | <0.2  | --    | 580  | --   | --  | --    | --  | --   |
| Oct-87   | --   | 9.5   | 170  | 180  | <0.5  | --    | 560  | --   | --  | --    | --  | --   |
| Apr-88*  | 160  | 4.5   | 56   | 79   | <0.5  | <0.50 | 200  | 530  | 220 | <0.50 | 23  | 320  |
| Jul-88*  | --   | 1.7   | 34   | 0.3  | <0.5  | --    | 96   | --   | --  | --    | --  | --   |
| Oct-88*  | --   | 10    | 58   | 0.7  | 1.0 s | --    | 87   | --   | --  | --    | --  | --   |
| Apr-89   | 380  | 9.8   | 160  | 110  | <0.5  | 110   | 530  | 340  | 180 | 1.3   | 38  | 530  |
| Jul-89   | --   | 9.9   | 99   | 3.6  | 2.1   | --    | 340  | --   | --  | --    | --  | --   |
| Oct-89   | --   | 12    | 140  | 5.0  | <0.5  | --    | --   | --   | --  | --    | --  | --   |
| Dec-89   | --   | --    | --   | --   | --    | --    | 490  | --   | --  | --    | --  | --   |
| May-90   | 100  | 8.5   | 150  | <0.5 | 0.7   | 110   | 570  | --   | 60  | 4.1   | 35  | 450  |
| Jul-90   | --   | 43    | 180  | 16   | <0.5  | --    | 400  | 530  | --  | --    | --  | --   |
| Oct-90   | --   | 9.4   | 130  | 240  | <0.5  | --    | 420  | --   | --  | --    | --  | --   |
| Apr-91   | 80   | 7.3   | 110  | 8.7  | <0.5  | <0.5  | 710  | 1100 | 150 | 4.5   | 64  | 420  |
| Sep-91   | --   | 10    | 120  | 3.2  | <0.5  | --    | 76   | --   | --  | --    | --  | --   |
| May-92   | 47   | 3.2   | 58   | 190  | <1.0  | 71    | 380  | 870  | 90  | 2.2   | 23  | 700  |
| Nov-92   | --   | 2.4   | 59   | 66   | <0.5  | --    | --   | --   | --  | --    | --  | --   |
| May-93   | 92   | 1.9   | 46   | 120  | <0.50 | 26    | --   | 940  | 93  | 2.5   | 29  | 130  |
| Jun-93   | --   | --    | --   | --   | --    | --    | 640  | --   | --  | --    | --  | --   |
| Nov-93   | --   | 0.78  | 43   | 180  | <0.50 | --    | 300  | --   | --  | --    | --  | --   |
| Aug-94   | 38   | 0.81  | 20   | 21   | <0.5  | --    | --   | --   | --  | 1.0   | 8.6 | --   |
| Sep-95   | 40   | --    | 38   | 3.3  | <0.50 | --    | --   | --   | --  | 0.89  | 6.0 | --   |
| Jan-96   | --   | <0.50 | --   | --   | --    | --    | --   | --   | --  | --    | --  | --   |
| Aug-96   | 35   | 3.0   | 24   | 17   | <0.5  | --    | --   | --   | --  | 2.2   | 47  | --   |



**Table D-7**  
**Historical Water Quality Data**  
**Carimona Member Wells**  
**Trichloroethylene**  
**[Consent Order Limit: 27 ug/L]**  
**(concentrations in ug/L)**

| Location | 8  | 9    | 10 | 11 | 12   | 13 | 108 | BB | RR | SS   | UU | WW |
|----------|----|------|----|----|------|----|-----|----|----|------|----|----|
| Aug-97   | 36 | 3.7  | 34 | 12 | <0.5 | -- | --  | -- | -- | 1.4  | 48 | -- |
| Oct-98   | 44 | 4.8  | 42 | 16 | <0.5 | -- | --  | -- | -- | <0.5 | 23 | -- |
| Dec-99   | 30 | 15   | 32 | 55 | <1.0 | -- | --  | -- | -- | <1.0 | 44 | -- |
| Nov-00   | 53 | <1.0 | 23 | 60 | <1.0 | -- | --  | -- | -- | <1.0 | 50 | -- |
| Dec-01   | 57 | 2.2  | 27 | 70 | 1.1  | -- | --  | -- | -- | 2.0  | 56 | -- |
| Dec-02   | 26 | 1.1  | 21 | 46 | <1.0 | -- | --  | -- | -- | 2.0  | 26 | -- |
| Oct-03   | -- | 1.1  | 15 | 48 | 1.7  | -- | --  | -- | -- | 2.9  | 25 | -- |

-- Not analyzed.

\* The 1988\* analytical data has been determined to be unreliable due to laboratory equipment and method performance problems.

s Potential false positive value based on statistical analysis of blank sample data.



**Table D-8**  
**Historical Water Quality Data**  
**Magnolia Member Wells**  
**Trichloroethylene**  
**[Consent Order Limit: 27 ug/L]**  
**(concentrations in ug/L)**

| Location | OO  | QQ    | TT  | VV  | ZZ  | 14   |
|----------|-----|-------|-----|-----|-----|------|
| May-82   | 15  | --    | --  | --  | --  | --   |
| Jun-82   | --  | 13    | --  | --  | --  | --   |
| Dec-82   | 56  | 13    | 8.9 | --  | --  | --   |
| Mar-84   | --  | --    | --  | --  | 14  | --   |
| Oct-85   | 49  | 2.9   | 26  | 140 | 85  | --   |
| Dec-85   | 31  | 7.3   | 19  | 93  | 28  | --   |
| Feb-86   | 36  | 5.2   | 27  | 92  | 200 | --   |
| Apr-86   | 120 | 6.0   | 33  | 280 | 440 | --   |
| Jun-86   | 27  | 1.0   | 20  | 83  | 91  | --   |
| Aug-86   | 19  | 0.6   | 40  | 99  | 39  | --   |
| Oct-86   | 32  | 6.4   | 23  | 77  | 190 | --   |
| Apr-87   | 130 | 2.5   | 34  | 63  | 230 | --   |
| Apr-88*  | 160 | <0.50 | 16  | 63  | 130 | --   |
| Jul-88*  | 20  | --    | --  | 94  | --  | --   |
| Oct-88*  | 34  | --    | --  | 25  | 83  | --   |
| Oct-88*  | --  | --    | --  | --  | 43  | --   |
| Apr-89   | 90  | 3.7   | 30  | 59  | 180 | --   |
| Jul-89   | 70  | --    | --  | 87  | 34  | --   |
| Oct-89   | 67  | --    | --  | 150 | 33  | --   |
| May-90   | 58  | 3.4   | 26  | 33  | 120 | --   |
| Jul-90   | 62  | --    | --  | 27  | 61  | --   |
| Oct-90   | 30  | --    | --  | 46  | 36  | --   |
| Apr-91   | 5.1 | <0.5  | 140 | 75  | 170 | --   |
| Sep-91   | 5.0 | --    | --  | 48  | 30  | --   |
| May-92   | 3.1 | --    | 58  | 60  | 88  | --   |
| Jun-92   | --  | 4.7   | --  | --  | --  | --   |
| Nov-92   | 17  | --    | 6.4 | 29  | 96  | --   |
| May-93   | 11  | 13    | 0.7 | 190 | 73  | --   |
| Nov-93   | 5.7 | --    | 1.8 | 150 | 70  | --   |
| Aug-94   | --  | 3.2   | 1.4 | --  | --  | --   |
| Sep-95   | --  | 3.7   | 1.5 | --  | --  | --   |
| Aug-96   | --  | 2.2   | 1.0 | --  | --  | --   |
| Aug-97   | --  | 1.8   | 1.9 | --  | --  | --   |
| Oct-98   | --  | <0.5  | 0.5 | --  | --  | <0.5 |
| Dec-99   | --  | <1.0  | 6.4 | --  | --  | 4.9  |
| Nov-00   | --  | <1.0  | 7.8 | --  | --  | 8.2  |
| Dec-01   | --  | <1.0  | 8.4 | --  | --  | 9.6  |
| Dec-02   | --  | <1.0  | 8.7 | --  | --  | 8.1  |
| Oct-03   | --  | <1.0  | 5.6 | --  | --  | 4.7  |

-- Not analyzed.

\* The 1988\* analytical data has been determined to be unreliable due to laboratory equipment and method performance problems.



**Table D-9**  
**Historical Water Quality Data**  
**St. Peter Sandstone Wells**  
**Trichloroethylene**  
**(concentrations in ug/L)**

| Location | 200   | 201   | 202   | 203   |
|----------|-------|-------|-------|-------|
| Oct-85   | --    | 0.5 s | --    | --    |
| Nov-85   | 120   | --    | 2.6   | 0.5 s |
| Dec-85   | 100   | 2.9   | 2.0   | 1.2   |
| Feb-86   | 72    | <0.5  | 1.9   | 2.5   |
| Apr-86   | 130   | <0.2  | 0.2   | 0.6   |
| Jun-86   | 110   | <0.2  | 0.2 s | 0.5   |
| Aug-86   | 110   | <0.2  | 2.7   | 0.5   |
| Oct-86   | 78    | <0.2  | <0.2  | 0.5   |
| Apr-87   | 100   | 0.1   | <0.2  | 0.7   |
| Jul-87   | 120   | --    | --    | --    |
| Oct-87   | 160   | --    | --    | --    |
| Apr-88*  | 89    | <0.50 | <0.50 | <0.50 |
| Jul-88*  | 33    | --    | --    | --    |
| Oct-88*  | 56    | --    | --    | --    |
| Apr-89   | 150   | <0.5  | <0.5  | 2.1   |
| Jul-89   | 130   | --    | --    | --    |
| Oct-89   | 120   | --    | --    | --    |
| May-90   | 110   | <0.5  | 0.8   | 2.8   |
| Jul-90   | 11 ** | --    | --    | --    |
| Oct-90   | 130   | --    | --    | --    |
| Apr-91   | 140   | <0.5  | <0.5  | 3.0   |
| Sep-91   | 77    | --    | --    | --    |
| May-92   | 61    | <1.0  | <1.0  | 1.2   |
| Nov-92   | 64    | --    | --    | --    |
| May-93   | 89    | <0.50 | <0.50 | 1.4   |
| Nov-93   | 19    | --    | --    | --    |
| Dec-94   | 110   | --    | --    | --    |
| Sep-95   | 110   | --    | --    | --    |
| Aug-96   | 96    | --    | --    | --    |
| Jul-97   | 98    | <0.5  | <0.5  | 5.4   |
| Aug-97   | 97    | <0.5  | --    | 5.0   |
| Dec-97   | --    | --    | <0.5  | --    |
| Oct-98   | 58    | --    | <0.5  | 4.5   |
| Dec-99   | 30    | --    | <1.0  | 4.1   |
| Nov-00   | <1.0  | --    | <1.0  | 7.2   |
| Dec-01   | 6.4   | --    | <1.0  | 15    |
| Dec-02   | 9.7   | --    | <1.0  | 24    |
| Oct-03   | 4.2   | --    | <1.0  | 28    |

-- Not analyzed.

\* The 1988\* analytical data has been determined to be unreliable due to laboratory equipment and method performance problems.

\*\* Estimated value, QA/QC criteria not met.

s Potential false positive value based on statistical analysis of blank sample data.



**Table D-10**  
**Historical Water Quality Data**  
**Prairie Du Chien/Jordan Well**  
**Trichloroethylene**  
**(concentrations in ug/L)**

| Location | HENKEL |
|----------|--------|
|          |        |
| Oct-85   | 71     |
| Dec-85   | 44     |
| Feb-86   | 48     |
| Apr-86   | OFF    |
| Jun-86   | OFF    |
| Aug-86   | 54     |
| Nov-86   | 6.9    |
| Apr-87   | 7.1    |
| Jul-87   | 20     |
| Oct-87   | 6.7    |
| Apr-88*  | 13     |
| Jul-88*  | 1.5    |
| Oct-88*  | 8.0    |
| Apr-89   | 12     |
| Jul-89   | 10     |
| Oct-89   | 11     |
| Jul-91   | 49     |
| Sep-91   | 18     |
| May-92   | 31     |
| Nov-92   | <0.5   |
| May-93   | 16     |
| Nov-93   | 35     |
| Aug-94   | 6.1    |
| Dec-95   | 6.5    |
| Aug-96   | 9.2    |
| Aug-97   | 13     |
| Oct-98   | 8.2    |
| Dec-99   | <1.0   |
| Nov-00   | <1.0   |
| Dec-01   | 7.1    |
| Nov-02   | <1.0   |
| Oct-03   | 4.0    |

\* The 1988\* analytical data has been determined to be unreliable due to laboratory equipment and method performance problems.



**Table D-11**  
**Historical Water Quality Data**  
**Site Pump-Out and Treatment System**  
**Downgradient Pump-Out System**  
**Trichloroethylene**  
**(concentrations in ug/L)**

| Location | Discharge (1) | Influent (2) | Effluent 100/50 (3) | MG-Effluent (4) |
|----------|---------------|--------------|---------------------|-----------------|
| Nov-85   | 160           | 1200         | 13                  | --              |
| Nov-85   | --            | 970          | 6.9                 | --              |
| Dec-85   | 140           | 690          | 6.1                 | --              |
| Dec-85   | --            | 870          | 12                  | --              |
| Dec-85   | --            | 670          | 6.5                 | --              |
| Jan-86   | --            | 1100         | 17                  | --              |
| Feb-86   | 290           | 760          | 8.4                 | --              |
| Mar-86   | --            | 1700         | 14                  | --              |
| Apr-86   | 400           | 860          | 11                  | --              |
| Jun-86   | 250           | --           | --                  | --              |
| Aug-86   | 350           | 870          | 6.7                 | --              |
| Oct-86   | 190           | 610          | 1.0                 | --              |
| Mar-87   | 320           | 730          | 6.8                 | --              |
| Apr-87   | 170           | 530          | 8.3                 | --              |
| Jul-87   | 310           | 660          | 2.8                 | --              |
| Oct-87   | 230           | 720          | <0.5                | --              |
| Nov-87   | --            | 490          | 2.6                 | --              |
| Jan-88*  | 300           | 470          | 4.4                 | --              |
| Apr-88*  | 210           | 370          | 5.3                 | --              |
| Apr-88*  | --            | 600          | --                  | --              |
| Jul-88*  | 70            | 160          | 1.2                 | --              |
| Oct-88*  | 64            | --           | --                  | --              |
| Nov-88*  | --            | 84           | 3.7                 | --              |
| Jan-89   | 210           | 390          | 9.8                 | --              |
| Apr-89   | 200           | 440          | 13                  | --              |
| Jul-89   | 170           | 380          | 20                  | --              |
| Oct-89   | 110           | --           | --                  | --              |
| Dec-89   | --            | 140          | 190                 | --              |
| Jan-90   | 140           | 380          | 96                  | --              |
| May-90   | 220           | 370          | 1.2                 | --              |
| Jul-90   | 180           | 310          | 0.9                 | --              |
| Oct-90   | 100           | 360          | 2.9                 | --              |
| Jan-91   | 150           | 430          | 0.8                 | --              |
| Apr-91   | 290           | 890          | 1.0                 | --              |
| Jul-91   | 210           | 370          | <0.5                | --              |
| Sep-91   | 110           | 320          | <0.5                | --              |
| Jan-92   | 99            | 260          | <1.0                | --              |
| May-92   | 55            | 320          | 8.3                 | --              |
| Aug-92   | 78            | 420          | 15                  | --              |
| Nov-92   | 110           | 450          | 28                  | 32              |
| Mar-93   | 130           | 270          | <0.50               | --              |
| May-93   | 82            | 450 h        | <0.50               | 22              |
| Aug-93   | 83            | 530          | <0.50               | 33              |
| Nov-93   | 78            | 630          | <0.50               | 24              |
| Mar-94   | 140           | 540          | <0.5                | 25              |
| Jun-94   | 60            | 430          | <0.5                | 23              |
| Aug-94   | 58            | 310          | <0.5                | 17              |
| Dec-94   | 65            | 400          | <0.50               | 18              |



**Table D-11**  
**Historical Water Quality Data**  
**Site Pump-Out and Treatment System**  
**Downgradient Pump-Out System**  
**Trichloroethylene**  
**(concentrations in ug/L)**

| Location | Discharge (1) | Influent (2) | Effluent<br>100/50 (3) | MG-<br>Effluent (4) |
|----------|---------------|--------------|------------------------|---------------------|
| Mar-95   | 93            | 650          | 7.6                    | 26                  |
| May-95   | 87            | 580          | 20                     | 25                  |
| Sep-95   | 53            | 450          | 0.63                   | 15                  |
| Dec-95   | 68            | 410          | 2.7                    | 15                  |
| Mar-96   | 63            | 360          | 38                     | 18                  |
| Jul-96   | 77            | 390          | 1.0                    | 21                  |
| Aug-96   | 40            | 400          | 64                     | 19                  |
| Nov-96   | 59            | 370          | <0.5                   | 22                  |
| Feb-97   | 89            | 390          | 1.8                    | 22                  |
| May-97   | 90            | 390          | 3.8                    | 23                  |
| Aug-97   | 82            | 370          | 68                     | 17                  |
| Dec-97   | 64            | 410          | 38                     | 19                  |
| Jan-98   | 56            | 370          | 0.5                    | 19                  |
| Apr-98   | 52.1          | 384.5        | 2.0                    | 19.9                |
| Aug-98   | 125.2         | 442.2        | <0.5                   | 30.5                |
| Oct-98   | 59            | 418.6        | 200                    | 40                  |
| Jan-99   | 74            | 315          | 33                     | 18.6                |
| Jun-99   | 64            | 280          | 140                    | 16.6                |
| Aug-99   | --            | 280          | 130                    | 16                  |
| Dec-99   | 56            | --           | --                     | 17.4                |
| Mar-00   | --            | --           | <1.0                   | --                  |
| Apr-00   | 32            | 280          | <1.0                   | 18                  |
| Sep-00   | 94            | 300          | <1.0                   | 21                  |
| Nov-00   | --            | --           | <1.0                   | --                  |
| Feb-01   | --            | --           | <1.0                   | --                  |
| May-01   | 75            | 230          | <1.0                   | 15                  |
| Aug-01   | --            | --           | <1.0                   | --                  |
| Nov-01   | --            | --           | <1.0                   | --                  |
| Feb-02   | --            | --           | <1.0                   | --                  |
| May-02   | 60            | 240          | 1.3                    | 12                  |
| Aug-02   | 68            | 210          | 2.9                    | 13                  |
| Nov-02   | --            | --           | <1.0                   | --                  |
| Mar-03   | --            | --           | <1.0                   | --                  |
| Jun-03   | 44            | 220          | <1.0                   | 12                  |
| Aug-03   | --            | --           | <1.0                   | --                  |
| Oct-03   | 48            | 200          | <1.0                   | 12                  |

-- Not analyzed.

(1) Flow rate weighted composite sample (pump-out wells 111, 112, and 113)

(2) Flow rate weighted composite sample (pump-out wells 108, 109, and 110 from 1985 to 1993, pump-out wells 109 and 110 from 1994 to present).

(3) Effluent from treatment system. NPDES daily limit: 100 ug/L and NPDES annual average limit: 50 ug/L.

(4) Flow rate weighted composite sample (Effluent from site pump-out wells MG1 and MG2).

\* The 1988 analytical data has been determined to be unreliable due to laboratory equipment and method performance problems.

h EPA sample extraction or analysis holding time was exceeded.



## Appendix E

Long-term effects on 2011



MINNESOTA DEPARTMENT OF HEALTH  
**WELL AND BORING SEALING RECORD**  
Minnesota Statutes, Chapter 103I

Minnesota Well and Boring  
Sealing No.  
Minnesota Unique Well No.  
or W-series No.  
(Leave blank if not known)

**H 217955**  
**1 9 6 7 2 1**

**WELL OR BORING LOCATION**  
County Name  
**Hennepin**

Ship Name **S** Township No. **29** Range No. **23** Section No. **19** Fraction (sm → lg) **NW SE NW** Date Sealed **11/21/03** Date Well or Boring Constructed **12/14/1981**


GPS LOCATION: Latitude \_\_\_\_\_ degrees \_\_\_\_\_ minutes \_\_\_\_\_ seconds  
Longitude \_\_\_\_\_ degrees \_\_\_\_\_ minutes \_\_\_\_\_ seconds

Numerical Street Address or Fire Number and City of Well or Boring Location

**2010 East Hennepin Avenue  
Minneapolis MN 55413**

Show exact location of well or boring in section grid with "X"

1 Sketch map of well or boring location, showing property lines, roads, and buildings.



**Hennepin Ave.**  
**well**  
**21st Ave SE**

Depth Before Sealing **28** ft. Original Depth **28** ft.

**AQUIFER(S)**  
☒ Single Aquifer ☐ Multiaquifer

**WELL/BORING**

☐ Water Supply Well ☒ Monit. Well  
☐ Env. Bore Hole ☐ Other \_\_\_\_\_

**STATIC WATER LEVEL**

☐ Measured ☒ Estimated

**23** ft. ☒ below ☐ above land surface

**CASING TYPE(S)**

☒ Steel ☐ Plastic ☐ Tile ☐ Other \_\_\_\_\_

**WELLHEAD COMPLETION**

Outside: ☐ Well House

Inside: ☐ Basement Offset

☐ Pitless Adapter/Unit

☐ Well Pit

☐ Well Pit

☐ Buried

☐ Buried

**Outside: Above Grade**

**PROPERTY OWNER'S NAME/COMPANY NAME**

**HED Holdings**

Property owner's mailing address if different than well location address indicated above

**2010 East Hennepin Avenue  
Minneapolis MN 55413**

**CASING(S)**

| Diameter                                    | Depth | Set in oversize hole?   | Annular space initially grouted?   |
|---|-------|---|--|
| <b>4</b> in. from <b>0</b> to <b>18</b> ft. |       | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Unknown |
| _____ in. from _____ to _____ ft.           |       | <input type="checkbox"/> Yes <input type="checkbox"/> No            | <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Unknown            |
| _____ in. from _____ to _____ ft.           |       | <input type="checkbox"/> Yes <input type="checkbox"/> No            | <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> Unknown            |

**WELL OWNER'S NAME/COMPANY NAME**

**General Mills**

Well owner's mailing address if different than property owner's address indicated above

**arr Engineering  
West 77th Street  
Minneapolis MN 55435-4808**

**SCREEN/OPEN HOLE**

Screen from **18** to **28** ft. Open Hole from \_\_\_\_\_ to \_\_\_\_\_ ft.

**OBSTRUCTIONS**

☐ Rods/Drop Pipe ☐ Check Valve(s) ☐ Debris ☐ Fill ☒ No Obstruction

Type of Obstructions (Describe) \_\_\_\_\_

Obstructions removed? ☐ Yes ☐ No Describe \_\_\_\_\_

**PUMP**

Type \_\_\_\_\_

☐ Removed ☒ Not Present ☐ Other \_\_\_\_\_

**METHOD USED TO SEAL ANNULAR SPACE BETWEEN 2 CASINGS, OR CASING AND BORE HOLE:**

☒ No Annular Space Exists ☐ Annular space grouted with tremie pipe ☐ Casing Perforation/Removal

\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft. ☐ Perforated ☐ Removed

\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft. ☐ Perforated ☐ Removed

Type of perforator \_\_\_\_\_

☐ Other \_\_\_\_\_

**GROUTING MATERIAL(S)**

(One bag of cement = 94 lbs., one bag of bentonite = 50 lbs.)

Grouting Material **Cement** from \_\_\_\_\_ to \_\_\_\_\_ ft. \_\_\_\_\_ yards **2.5** bags

\_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft. \_\_\_\_\_ yards \_\_\_\_\_ bags

\_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft. \_\_\_\_\_ yards \_\_\_\_\_ bags

| GEOLOGICAL MATERIAL       | COLOR    | HARDNESS OR FORMATION | FROM | TO |
|---------------------------|----------|-----------------------|------|----|
| Topsoil                   | Grey     |                       | 0    | 2  |
| Sandy Clay                | Grey     |                       | 2    | 12 |
| Course ledge and boulders | Grey     |                       | 12   | 20 |
| Sand                      | Dk. Grey |                       | 20   | 28 |
|                           |          |                       |      |    |
|                           |          |                       |      |    |
|                           |          |                       |      |    |
|                           |          |                       |      |    |
|                           |          |                       |      |    |
|                           |          |                       |      |    |
|                           |          |                       |      |    |

**REMARKS, SOURCE OF DATA, DIFFICULTIES IN SEALING**

**OTHER WELLS AND BORINGS**

Other unsealed and unused well or boring on property? ☐ Yes ☒ No How many? \_\_\_\_\_

**LICENSED OR REGISTERED CONTRACTOR CERTIFICATION**

This well or boring was sealed in accordance with Minnesota Rules, Chapter 4725. The information contained in this report is true to the best of my knowledge.

**T.L. Stevens Well Company**

Contractor Business Name

**27194**

License or Registration No.

Authorized Representative Signature

**11/26/03**  
Date







WELL OR BORING LOCATION  
County Name **Regin**

MINNESOTA DEPARTMENT OF HEALTH  
**WELL AND BORING SEALING RECORD**  
Minnesota Statutes, Chapter 103I

Minnesota Well and Boring  
Sealing No.  
Minnesota Unique Well No.  
or W-series No.  
(Leave blank if not known)

H **217958**

Tr. Ship Name **3** Township No. **29** Range No. **23** Section No. **19** Fraction (sm → lg) **NW SE NW** Date Sealed **11/21/03** Date Well or Boring Constructed **Unknown**

GPS LOCATION: Latitude \_\_\_\_\_ degrees \_\_\_\_\_ minutes \_\_\_\_\_ seconds  
Longitude \_\_\_\_\_ degrees \_\_\_\_\_ minutes \_\_\_\_\_ seconds  
Depth Before Sealing **24** ft. Original Depth **Unknown** ft.

Numerical Street Address or Fire Number and City of Well or Boring Location  
**1083 19th Avenue SE Minneapolis MN 55413**  
Show exact location of well or boring in section grid with "X"  
Sketch map of well or boring location, showing property lines, roads, and buildings.  
**19th AVE SE**  
**well**  
**R.R. Tracks**  
**G**  
**1/2 mile**  
**1 mile**

AQUIFER(S)  
☒ Single Aquifer ☐ Multiaquifer  
WELL/BORING  
☐ Water Supply Well ☒ Monit. Well  
☐ Env. Bore Hole ☐ Other \_\_\_\_\_  
STATIC WATER LEVEL  
☒ Measured ☐ Estimated  
**17** ft. ☒ below ☐ above land surface

CASING TYPE(S)  
☐ Steel ☐ Plastic ☐ Tile ☐ Other \_\_\_\_\_  
WELLHEAD COMPLETION  
Outside: ☐ Well House ☐ Pitless Adapter/Unit ☐ Well Pit ☐ Buried  
Inside: ☐ Basement Offset ☐ Well Pit ☐ Buried  
**Outside: Above Grade Cover Pipe**

PROPERTY OWNER'S NAME/COMPANY NAME  
**Frederick Puzak**  
**PO Box 158**  
**Spring Park MN 55384**  
CASING(S)  
Diameter \_\_\_\_\_ Depth \_\_\_\_\_ Set in oversize hole? ☐ Yes ☒ No Annular space initially grouted? ☐ Yes ☐ No ☒ Unknown  
**2** in. from **0** to **14** ft. ☐ Yes ☒ No ☐ Yes ☐ No ☐ Unknown  
\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft. ☐ Yes ☐ No ☐ Yes ☐ No ☐ Unknown  
\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft. ☐ Yes ☐ No ☐ Yes ☐ No ☐ Unknown

WELL OWNER'S NAME/COMPANY NAME  
**Verel Mills**  
Owner's mailing address if different than property owner's address indicated above  
**Sarr Engineering**  
**1 West 77th Street**  
**Minneapolis MN 55435-4008**  
SCREEN/OPEN HOLE  
Screen from **14** to **24** ft. Open Hole from \_\_\_\_\_ to \_\_\_\_\_ ft.

OBSTRUCTIONS  
☐ Rods/Drop Pipe ☐ Check Valve(s) ☐ Debris ☐ Fill ☒ No Obstruction  
Type of Obstructions (Describe) \_\_\_\_\_  
Obstructions removed? ☐ Yes ☐ No Describe \_\_\_\_\_

PUMP  
Type \_\_\_\_\_  
☐ Removed ☒ Not Present ☐ Other \_\_\_\_\_

METHOD USED TO SEAL ANNULAR SPACE BETWEEN 2 CASINGS, OR CASING AND BORE HOLE:  
☒ No Annular Space Exists ☐ Annular space grouted with tremie pipe ☐ Casing Perforation/Removal  
\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft. ☐ Perforated ☐ Removed  
\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft. ☐ Perforated ☐ Removed  
Type of perforator \_\_\_\_\_  
☐ Other \_\_\_\_\_

GROUTING MATERIAL(S) (One bag of cement = 94 lbs., one bag of bentonite = 50 lbs.)  
Grouting Material **Cement** from **0** to **24** ft. \_\_\_\_\_ yards **3/4** bags  
\_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft. \_\_\_\_\_ yards \_\_\_\_\_ bags  
\_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft. \_\_\_\_\_ yards \_\_\_\_\_ bags

OTHER WELLS AND BORINGS  
Other unsealed and unused well or boring on property? ☐ Yes ☒ No How many? \_\_\_\_\_

REMARKS, SOURCE OF DATA, DIFFICULTIES IN SEALING  
LICENSED OR REGISTERED CONTRACTOR CERTIFICATION  
This well or boring was sealed in accordance with Minnesota Rules, Chapter 4725. The information contained in this report is true to the best of my knowledge.  
**T.L. Stevens Well Company**  
Contractor Business Name  
**27194**  
License or Registration No.  
**11/26/03**  
Date  
**Thomas Stevens**  
Authorized Representative Signature







WELL OR BORING LOCATION

County Name  
**Hennepin**

Well Name  
**S**

Township No.  
**29**

Range No.  
**23**

Section No.  
**19**


Fraction (sm -> lg)  
**NE SE NW**

Date Sealed  
**11/21/03**

Date Well or Boring Constructed  
**Unknown**

GPS LOCATION  
Latitude \_\_\_\_\_ degrees \_\_\_\_\_ minutes \_\_\_\_\_ seconds  
Longitude \_\_\_\_\_ degrees \_\_\_\_\_ minutes \_\_\_\_\_ seconds

Numerical Street Address or Fire Number and City of Well or Boring Location  
**2010 East Hennepin Avenue  
Minneapolis MN 55413**

Sketch map of well or boring location, showing property lines, roads, and buildings.  


AQUIFER(S)  
☒ Single Aquifer ☐ Multiaquifer

WELL/BORING  
☐ Water Supply Well ☒ Monit. Well  
☐ Env. Bore Hole ☐ Other \_\_\_\_\_

CASING TYPE(S)  
☒ Steel ☐ Plastic ☐ Tile ☐ Other \_\_\_\_\_

WELLHEAD COMPLETION  
Outside: ☐ Well House ☐ Pitless Adapter/Unit ☐ Well Pit ☐ Buried  
Inside: ☐ Basement Offset ☐ Well Pit ☐ Buried  
**Outside: Above grade cover pipe**

PROPERTY OWNER'S NAME/COMPANY NAME  
**BED Holdings**

Property owner's mailing address if different than well location address indicated above  
**2010 East Hennepin Avenue  
Minneapolis MN 55413**

WELL OWNER'S NAME/COMPANY NAME  
**General Mills**

Well owner's mailing address if different than property owner's address indicated above  
**Bar Engineering  
West 77th Street  
Minneapolis MN 55435-4808**

GEOLOGICAL MATERIAL  
**Sand**

COLOR

HARDNESS OR FORMATION

FROM  
**0**

TO  
**36**

REMARKS, SOURCE OF DATA, DIFFICULTIES IN SEALING.

Other unsealed and unused well or boring on property? ☐ Yes ☒ No How many? \_\_\_\_\_

LICENSED OR REGISTERED CONTRACTOR CERTIFICATION  
This well or boring was sealed in accordance with Minnesota Rules, Chapter 4725. The information contained in this report is true to the best of my knowledge.  
**T.L. Stevens Well Company**  
Contractor Business Name  
**Joe Stevens**  
Authorized Representative Signature  
License or Registration No. **27194**  
Date **11/26/03**

MINNESOTA DEPARTMENT OF HEALTH

WELL AND BORING SEALING RECORD

Minnesota Statutes, Chapter 103I

Minnesota Well and Boring Sealing No.  
Minnesota Unique Well No. or W-series No.  
(Leave blank if not known)

H- 217957



WELL OR BORING LOCATION

County Name

mnepin

MINNESOTA DEPARTMENT OF HEALTH

WELL AND BORING SEALING RECORD

Minnesota Statutes, Chapter 103I

Minnesota Well and Boring Sealing No.

Minnesota Unique Well No. or W-series No.

(Leave blank if not known)

H

217961

Tr. Ship Name

Is

Township No.

29

Range No.

23

Section No.

19

Fraction (sm → lg)

NW SE NW

Date Sealed

11/21/03

Date Well or Boring Constructed

Unknown

GPS LOCATION

Latitude \_\_\_\_\_ degrees \_\_\_\_\_ minutes \_\_\_\_\_ seconds

Longitude \_\_\_\_\_ degrees \_\_\_\_\_ minutes \_\_\_\_\_ seconds

Numerical Street Address or Fire Number and City of Well or Boring Location


2110 East Hennepin Avenue

Minneapolis MN 55413

Show exact location of well or boring in section grid with "X"

108

Sketch map of well or boring location, showing property lines, roads, and buildings.



PROPERTY OWNER'S NAME/COMPANY NAME

ED Holdings

Property owner's mailing address if different than well location address indicated above

2110 East Hennepin Avenue

Minneapolis MN 55413

WELL OWNER'S NAME/COMPANY NAME

General Mills

Owner's mailing address if different than property owner's address indicated above

100 West 77th Street

Minneapolis MN 55435-4808

GEOLOGICAL MATERIAL

COLOR

HARDNESS OR FORMATION

FROM

TO

If not known, indicate estimated formation log from nearby well or boring

CAQUIFER(S)

☒ Single Aquifer ☐ Multi-aquifer

WELL/BORING

☐ Water Supply Well ☒ Monit. Well

☐ Env. Bore Hole ☐ Other \_\_\_\_\_

STATIC WATER LEVEL

☒ Measured ☐ Estimated

27 ft. ☒ below ☐ above land surface

CASING TYPE(S)

☐ Steel ☐ Plastic ☐ Tile ☐ Other \_\_\_\_\_

WELLHEAD COMPLETION

Outside: ☐ Well House ☐ Pitless Adapter/Unit ☐ Well Pit ☐ Buried

Inside: ☐ Basement Offset ☐ Well Pit ☐ Buried

CASING(S)

Diameter

0 in. from 0 to 50 ft.

Set in oversized hole? ☐ Yes ☒ No

Annular space initially grouted? ☐ Yes ☐ No ☒ Unknown

\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft.

☐ Yes ☐ No ☐ Yes ☐ No ☐ Unknown

\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft.

☐ Yes ☐ No ☐ Yes ☐ No ☐ Unknown

SCREEN/OPEN HOLE

Screen from \_\_\_\_\_ to \_\_\_\_\_ ft.

Open Hole from 50 to 56 ft.

OBSTRUCTIONS

☐ Rods/Drop Pipe ☐ Check Valve(s) ☐ Debris ☐ Fill ☒ No Obstruction

Type of Obstructions (Describe) \_\_\_\_\_

Obstructions removed? ☐ Yes ☐ No Describe \_\_\_\_\_

PUMP

Type

Submersible

☒ Removed ☐ Not Present ☐ Other \_\_\_\_\_

METHOD USED TO SEAL ANNULAR SPACE BETWEEN 2 CASINGS, OR CASING AND BORE HOLE:

☒ No Annular Space Exists ☐ Annular space grouted with tremie pipe ☐ Casing Perforation/Removal

\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft. ☐ Perforated ☐ Remove

\_\_\_\_\_ in. from \_\_\_\_\_ to \_\_\_\_\_ ft. ☐ Perforated ☐ Removed

Type of perforator \_\_\_\_\_

☐ Other \_\_\_\_\_

GROUTING MATERIAL(S)

(One bag of cement = 94 lbs., one bag of bentonite = 50 lbs.)

Grouting Material

Cement from 0 to 56 ft. \_\_\_\_\_ yards 8 bags

\_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft. \_\_\_\_\_ yards \_\_\_\_\_ bags

\_\_\_\_\_ from \_\_\_\_\_ to \_\_\_\_\_ ft. \_\_\_\_\_ yards \_\_\_\_\_ bags

OTHER WELLS AND BORINGS

Other unsealed and unused well or boring on property? ☐ Yes ☒ No How many? \_\_\_\_\_

REMARKS, SOURCE OF DATA, DIFFICULTIES IN SEALING

LICENSED OR REGISTERED CONTRACTOR CERTIFICATION

This well or boring was sealed in accordance with Minnesota Rules, Chapter 4725. The information contained in this report is true to the best of my knowledge.

T.L. Stevens Well Company

Contractor Business Name

27194

License or Registration No.

11/26/03

Date

Joe Stevens

Authorized Representative Signature

IMPORTANT-FILE WITH PROPERTY

217961